

Application for Park Master Plan


Municipality of Anchorage
Planning Department
PO Box 196650
Anchorage, AK 99519-6650



PETITIONER		PETITIONER REPRESENTATIVE (if any)	
Name (last name first) Anchorage Parks & Recreation Department, Josh Durand		Name (last name first) Rafuse, Steve; Project Manager, MOA Parks & Recreation Department	
Mailing Address Municipality of Anchorage PO Box 196650 Anchorage, AK 99519-6650		Mailing Address Municipality Of Anchorage PO Box 196650 Anchorage, AK 99519-6650	
Contact Phone: Day 907-343-4585 Evening 907-343-4585		Contact Phone: Day 907-343-4586 Evening 907-343-4586	
Fax 907-249-7542		Fax	
E-mail DurandJA@muni.org		E-mail rafusesj@muni.org	

PROPERTY INFORMATION			
Property Tax # (000-000-00-000): 006-401-07-000; 006-401-10-000, 006-401-08-000, 006-401-09-000, 006-401-05-000			
Site Street Address: 1301 Muldoon Rd, SE corner of Debarr Rd and Muldoon Rd			
Current legal description: (use additional sheet if necessary)			
See attached sheet (5 parcels)			
Zoning: R2M, B3SL	Acreage: 26.74	Grid #: SW1441	Underlying plat #: 14-0030; 07-0018
Park Name: Muldoon Town Square Park			
Park Classification: ☒ Community Use ☐ Special Use ☐ Natural Resource Use ☐ Neighborhood Use ☐ Large Urban ☐ Regional ☐ Playlot, Mini Park, Vest Pocket ☐ Not classified/other			
☒ New master plan ☐ Amendment/revision to existing master plan Original Case #:			

I hereby certify that (I am)(I have been authorized to act for) owner of the property described above and that I petition for a park master plan in conformance with Title 21 of the Anchorage Municipal, Code of Ordinances. I understand that payment of the application fee is nonrefundable and is to cover the costs associated with processing this application, and that it does not assure approval of the master plan. I also understand that assigned hearing dates are tentative and may have to be postponed by Planning Department staff or the Planning and Zoning Commission, for administrative reasons.



Signature ☒ Owner ☐ Representative (Agents must provide written proof of authorization)

Date January 25, 2016

Print Name Josh Durand

Accepted by:

Poster & Affidavit:

Fee:

Case Number:

Requested Meeting Date:

2016-0025

4-11-16 P2C

COMPREHENSIVE PLAN INFORMATIONAnchorage 2020 Urban/Rural Services: ☒ Urban ☐ Rural

Anchorage 2020 Major Elements – site is within or abuts:

- ☐ Major employment center ☐ Redevelopment/mixed use area ☐ Town center
☐ Neighborhood commercial center ☐ Industrial reserve
☐ Transit - supportive development corridor ☒ District/area plan area: East Anchorage District Plan

Chugiak-Eagle River Land Use Classification:

- ☐ Commercial ☐ Industrial ☐ Parks/open space ☐ Public lands/institutions ☐ Town center
☐ Transportation/community facility ☐ Alpine/slope affected ☐ Special study area ☐ Development reserve
☐ Residential at _____ dwelling units per acre ☐ Environmentally sensitive area

Girdwood- Turnagain Arm Land Use Classification

- ☐ Commercial ☐ Industrial ☐ Parks/open space ☐ Public lands/institutions ☐ Resort
☐ Transportation/community facility ☐ Alpine/slope affected ☐ Special study area ☐ Reserve
☐ Residential at _____ dwelling units per acre ☐ Mixed use ☐ Rural homestead

ENVIRONMENTAL INFORMATION (All or portion of site affected)

- Wetland Classification: ☐ None ☐ "C" ☐ "B" ☒ "A"
 Avalanche Zone: ☒ None ☐ Blue Zone ☐ Red Zone
 Floodplain: ☐ None ☒ 100 year ☒ 500 year
 Seismic Zone (Harding/Lawson): ☐ "1" ☒ "2" ☒ "3" ☐ "4" ☐ "5"

RECENT REGULATORY INFORMATION (Events that have occurred in last 5 years for all or portion of site)

- ☐ Rezoning - Case Number:
☐ Preliminary Plat ☒ Final Plat - Case Number(s): S11700 (Plat #2014-30) See attached.
☐ Conditional Use - Case Number(s):
☐ Zoning variance - Case Number(s):
☐ Land Use Enforcement Action for
☐ Building or Land Use Permit for Picnic Shelter
☐ Wetland permit: ☐ Army Corp of Engineers ☐ Municipality of Anchorage

APPLICATION REQUIREMENTS

- 1 copy required: ☒ Signed application (original)
☒ Watershed sign off form, completed
☒ 8 ½" by 11" copy of park master plan
 35 copies required: ☐ Signed application (copies)
☐ Park master plan
☐ Assembly Ordinance enacting zoning special limitations, if applicable
☐ Applicable parks board resolution or summary of parks board meeting(s)

(Additional information may be required.)



Municipality of Anchorage, Alaska
Parks & Recreation Department

632 W. 6th Avenue, Suite 630
P.O. Box 196650
Anchorage, AK 99519
Tel 907-343-4355

URL www.muni.org/departments/parks



MEMORANDUM

Date: January 25, 2016

To: MOA Planning for PZC Review

Cc: Josh Durand, Parks Superintendent

From: Steve Rafuse, Project Manager

Project: Muldoon Town Square Park Master Plan

INTRODUCTION

Muldoon Town Square Park is a newly dedicated Community Use Park located in the heart of East Anchorage at the southeast corner of the Muldoon and DeBarr Road intersection. The park encompasses 26.4 acres of natural and previously developed areas and features the South Fork of Chester Creek, upland forests, open meadows and informal trails.

The park is defined by East Debarr Road and its right-of-way (ROW) to the north; Muldoon Road to the west; East 14th Avenue ROW, residences and Windsong Park to the south; and Joint Base Elmendorf-Richardson (JBER) to the east. The park will serve area residents and greater Anchorage by providing a recreation destination and community event space developed with a mix of year-round activities.

BACKGROUND

The creation and development of a Muldoon Town Square Park has long been a priority of residents in East Anchorage as well as the Northeast and Scenic Foothill Community Councils. Over the years, area activists, neighbors, and community members have voiced a strong desire for a shared public space and destination fronting Muldoon Road that is reminiscent of the character, uniqueness and popularity of the Alaska Greenhouses, a commercial nursery operation formerly located on this site and owned by the late Mann Leiser.

In 2014, the East Anchorage District Plan was formally adopted. The plan identifies the development of a "small area plan" (Muldoon Town Square Park Master Plan) as a priority action for implementation of the District Plan. In July 2015, the Anchorage Assembly formally dedicated the entire property as parkland. With this resolution, the Parks and Recreation Department began the master planning process. The result is a Master Plan that recognizes the community's vision and establishes a framework for future development.

PURPOSE

This Master Plan is intended to provide a long range vision for the Muldoon Town Square Park over the next 20 years. It identifies community needs, addresses public expectations and establishes a framework for future development of the park. More specifically, the purpose of the Master Plan is to:

- Identify and prioritize improvements consistent with the desires of the East Anchorage community
- Develop a "small area plan" for the Muldoon Road frontage as prescribed in the EADP
- Provide a park that encourages positive use and discourages undesirable activities
- Develop the park in a manner that balances new facilities with existing natural areas
- Create a tool for future fundraising

PLANNING AND PUBLIC INVOLVEMENT

Public involvement is an important component of any planning process. To ensure that the Muldoon Town Square Park Master Plan aligns with the desires of the community, a public involvement process was led by Anchorage Parks and Recreation with assistance from Bettisworth North and R&M Consultants.

Outreach The planning team kicked off the project with a meeting of the Park Advisory Committee and a presentation at the Scenic Foothills Community Council. Parks and Recreation staff attended the Spirit of Muldoon community picnic to share information about the Master Plan process and to gather input from local residents. Park Advisory Committee members also distributed over 500 flyers to neighborhood residents. Information and project updates were posted online and through social media.

Park Advisory Committee: A fifteen member Parks Advisory Committee (PAC) served as an advisory group to the planning team throughout the development of the Master Plan. The PAC was comprised of members from both the Northeast and Scenic Foothills Community Councils. The committee was tasked with providing insight, information, recommendations and feedback to help guide the planning team through the development of the Master Plan. The PAC also served as a sounding board for the citizens of the Muldoon area, ensuring that improvements identified in the plan align with the desires of the broader community. The committee actively participated in the public meetings, a PAC design charrette, and review and refinement of design alternatives to develop the preferred alternative site plan. The committee's most important task was to help build consensus on a preferred alternative site plan.

Public Workshops: The Planning Team facilitated two public planning workshops at Begich Middle School to gather input and inform the development of the Master Plan. Each workshop began with a presentation on the planning process and timeline, included a review of existing site conditions and featured interactive small group discussions and park planning exercises. Relevant displays, fact sheets and multiple ways to provide comments and feedback were provided throughout each workshop.

Agency Coordination: Planning for the development of Muldoon Town Square Park required the coordination of multiple state and local agencies in the early stages of the process to ensure that development identified in the Master Plan will be compatible with the surrounding area. The planning team facilitated an agency coordination meeting to revise and advance alternatives that were responsive to existing conditions, agency-planned projects, and important technical input. The Agency Coordination meeting was attended by 21 people and included representatives from AKDOT&PF; MOA Planning, Project Management & Engineering, Non-motorized Transportation, Traffic, Transit, Watershed Management, and AMATS, as well as members of the Park Advisory Committee.

Student Participation The youth of today are the stewards of tomorrow. To better understand the question of "what young people want", the planning team worked with students and administrators at Begich Middle School and Bartlett High School. Approximately 80 students at Begich Middle School completed the "Power of Ten" worksheets. Students at Bartlett High School were presented the planning process and alternatives, with a lengthy dialogue about community open space needs and what types of recreational opportunities students desired at Muldoon Town Square Park. The student feedback was thoughtful, creative, and reflected the desires of the community input received to date.

Online Survey The planning team administered an online survey to gather additional feedback from members of the public. The survey was made available on the project website and was circulated through the Community Council email system and social media. A total of 223 individual responses were collected. Survey responses were used to identify priorities and inform the development of the Master Plan

THE MASTER PLAN

The Muldoon Town Square Park Master Plan provides a 20-year vision for the development of the park. The plan is the product of extensive public engagement and collaboration with the Park Advisory Committee, Parks & Recreation Department, area middle and high school students, and a small team of planning and design consultants. The Master Plan embodies the community's vision to provide active and healthy recreational opportunities to the residents of Muldoon and East Anchorage.


Vision: *"Muldoon Town Square Park is a gathering place and destination for East Anchorage and the greater community where families and people of all ages and abilities can access and participate in healthy park activities in a safe, clean, comfortable environment in a unique and beautiful natural setting."*

Values: The recommendations provided in the plan are based on the following community values, observations and identified needs:

- Develop Muldoon Town Square Park as a community destination in East Anchorage for all ages and abilities.
- Provide safe and accessible connections to the park, and within the park.
- Encourage year-round community and neighborhood use by developing flexible use areas that accommodate large organized events and promote daily use.
- Celebrate the unique natural features of the park, including; the South Fork of Chester Creek, remnant native birch/spruce forest, and the spectacular views of the Chugach Mountains.
- Improve food security and public health by offering community garden space and integrating edible landscapes into park improvements.
- Activate the park by developing year-round recreational and social opportunities for a variety of different interests, user groups, ages, abilities, and skill levels.
- Ensure user safety by improving visibility, incorporating lighting, and activating spaces.
- Maintain the natural characteristics of the park to serve as areas of respite, inspiration, reflection, and connection.
- Manage the park as important habitat with a variety of ecosystems that support native flora and fauna.
- Celebrate local cultures, communities, and diversity with public and performance art.
- Implement green infrastructure as best management practices to improve water quality, encourage biodiversity, and limit off-site impacts.
- Coordinate investment in infrastructure and facilities to maximize available resources.
- Engage local, state, and federal partners to fund park improvements and advance the community vision.

Recommendations:

Muldoon Town Square Park is comprised of three distinct use areas defined by the key characteristics within, or adjacent to the park. From west to east, the park transitions from a high-use, community destination fronting a major arterial road (Muldoon) to a contemplative, natural landscape suitable for both active (Core) and passive (Chugach) recreation. Within the park, a network of trails will connect use areas. As envisioned, the park will provide a safe and healthy place to connect with nature, recreate with friends and family, and gather as a community.



The following recommendations are listed by defined use area and include a description of the space and facilities to be developed.

Muldoon: The Muldoon Area is the furthest west portion of the park, visible and accessible from Muldoon Road, and is desired to be a welcoming, year-round destination. It is intended to be the most active space in the park; hosting community-wide events and highly desired activities that draw daily users in safely from Muldoon Road. Visitors will be encouraged to enter and explore further into the park with crossings over Chester Creek that extend towards the forested hill, a flexible open space, and sloped lawn. The hill and Chugach Mountains will serve as an exceptional backdrop for the iconic park as viewed from Muldoon Road.

The Muldoon Area will include developed access to Chester Creek, a destination inclusive playground, a parking lot with 40 spaces, community event space that can support the Muldoon Farmers Market and Spirit of Muldoon Picnic, flexible open space, a pavilion, restrooms, and a ribbon that be used for ice skating in the winter and community events and kiddie bike loop in the summer.

Core: The Core Area lies in the heart of the park and is an active space that includes a mix of developed facilities and natural areas intended for use by the larger community and neighborhood residents. The Core is served by a parking lot at the intersection of East Debarr Road and Boston Street. This parking lot provides a necessary means for area residents to commute to the park while limiting traffic impacts to the surrounding neighborhood to the north. Numerous paths link the Core to adjacent roads and neighborhoods as well as other areas within the park.

The Core Area will include a bicycle pump park, a boulder play area, a community garden, a community orchard, a fenced dog park, open recreation space, a parking lot with 50 spaces and space for a park host, view points of the Chugach Mountains, a mix of hard and soft surface trails, and access to Windsong Park.

Chugach: The Chugach Area is the easternmost area of the park and is the least developed area proposed in the Master Plan. It is connected to the Core Area by a wide pedestrian Spine. Open recreation areas and forested wilderness define the Chugach Area. Numerous multi-use paths meander through existing natural areas and lead users to expansive views of the Chugach Mountains. Bridge and boardwalk connections over Chester Creek are planned to improve access to adjacent neighborhoods and Windsong Park.



Draft Master Plan
Muldoon Town Square Park

STAFF RECOMMENDATION

The Anchorage Parks and Recreation Department recommends approval of the Muldoon Town Square Park Master Plan. The Master Plan is the product of a public involvement process which included outreach and presentations at the Northeast and Scenic Foothills Community Councils, two public planning workshops, monthly meetings with the Park Advisory Committee, an online survey, agency coordination meeting, and work with local students.


The Master Plan has received broad support by the Northeast and Scenic Foothills Community Council. The Department recommends that the Parks and Recreation Commission pass the proposed resolution in support of the Muldoon Town Square Park Master Plan.

MUNICIPALITY OF ANCHORAGE


ANCHORAGE PARKS & RECREATION



Muldoon Town Square Park – Legal Description



Muldoon Town Square Park
Parcel ID



Parcel: 006-401-07-000
Muldoon Estates Subdivision Tract A

Parcel: 006-401-08-000
Muldoon Estates Subdivision Tract B

Parcel: 006-401-09-000
Muldoon Estates Subdivision Tract C

Parcel: 006-401-10-000
Muldoon Estates Subdivision Tract D

Parcel: 006-401-05-000
Muldoon Estates Subdivision Lot 3

WMS Archive File Name: 16 Muldoon Sq Park

WMS WATERCOURSE MAPPING SUMMARY

Per the requirements for watercourse verification outlined in Project Management and Engineering Operating Policy and Procedure #8 and Planning Department Operating Policy and Procedure #1 (effective June 18, 2007), MOA Watershed Management Services has inspected the following location for the presence or absence of stream channels or other watercourses, as defined in Anchorage Municipal Code (21.35).

- Project Case Number or Subdivision Name: Muldoon Town Square Park Master Plan
- Project Location, Tax ID, or Legal Description: 1301 Muldoon Rd, SE corner of Debarr Rd and Muldoon Rd
5 parcels (006-401-07-000; 006-401-10-000, 006-401-08-000, 006-401-09-000, 006-401-05-000)
- Project Area (if different from the entire parcel or subdivision): _____

In accordance with the requirements and methods identified, WMS verifies that this parcel, project area, or application:

_____ **DOES NOT** contain stream channels and/or drainageways, as identified in WMS field or archival mapping information.*

X **DOES** contain stream channels and/or drainageways **AND** these are located and identified on submittal documents in general congruence with WMS field and archival mapping information.

*New or additional mapping **IS NOT REQUIRED**.**

_____ Contains stream channels and/or drainageways **BUT** one or more streams or other watercourses:

- are **NOT** shown on submittal documents, or
- are **NOT** depicted adequately on submittal documents for verification, or
- are **NOT** located or identified on submittal documents in general congruence with WMS field and archival mapping information.

*New or additional mapping **IS REQUIRED** and must be re-submitted for further review and verification.**

_____ Presence of stream channels and/or drainageways is unknown **AND** field verification is not possible at this time. WMS will verify as soon as conditions and prioritized resources allow.

* Streams omitted in error by WMS or others remain subject to MOA Code and must be shown in new mapping upon identification of the error.

ADDITIONAL INFORMATION:

☐ Y ☒ N	WMS written drainage recommendations are available.	☐ Preliminary	☐ Final
☒ Y ☐ N	WMS written field inspection report or map is available.	☐ Preliminary	☐ Final
☒ Y ☐ N	Field flagging and/or map-grade GPS data is available.		

Inspection Certified By:

Date:




Kyle G. [Signature]

1/22/16

Line #	Length	Duration
120000	27.51	407.01 177°
120001	27.79	537.11 30°
120002	18.43	505.20 54°
120003	15.47	506.20 337°
119998	6.47	544.92 27°
120004	47.77	545.16 50°
120005	28.40	558.14 117°
120006	12.14	558.40 17°
120007	19.27	559.23 497°
120008	19.77	569.25 307°
120009	28.42	570.34 37°
120010	20.10	584.46 50°
120011	30.48	591.17 27°
120012	17.49	597.07 47°
120013	16.48	627.00 53°
120014	8.12	627.21 10°
120015	27.43	650.21 10°


Line #	Length	Direction
1	20.82	42° 27' E
2	44.83	46.5° E
3	44.43	51° 16' 42" E
4	17.35	53° 21' 33" E
5	89.53	53° 25' 24" E
6	58.82	54° 30' 43" E
7	15.41	54° 37' 12" E
8	75.52	54° 34' 10" E
9	43.80	60° 1' 23" E
10	31.73	53° 35' 23" E
11	44.90	50° 17' 27" E
12	12.83	50° 09' 18" E
13	110.08	53° 38' 10" E
14	100.17	53° 41' 10" E
15	24.63	53° 41' 10" E
16	30.83	53° 41' 27" E
17	100.22	53° 41' 27" E

Stream Protection Easement Line Table	Line #	Begin	Direction
	1	36.38	N01°48'44"E
	2	21.77	N01°46'23"E
	3	14.88	N01°38'46"E
	4	26.68	N01°35'37"E
	5	23.64	N03°47'25"E
	6	21.48	N03°38'54"E
	7	24.65	N07°05'30"E
	8	33.24	N07°05'30"E
	9	37.68	N04°06'37"E
	10	25.81	N16°31'30"E
	11	46.78	N03°18'28"E
	12	77.87	N00°05'54"E
	13	91.23	S30°27'12"E
	14	33.58	N12°42'33"E
	15	73.23	N44°44'25"E
	16	500.55	N31°31'30"E



Legend

(71)	Record from Pstl 2007-18
(72)	Record from Pstl 77-248
(73)	Record from Pstl 77-298
(74)	Record from Pstl 82-437
(75)	Record from Pstl 84-427
(76)	Computed by Slope/Rearranging Information
(77)	Computed by Rating/Distance Information
(78)	Dedicated This Map
(79)	Measured
(80)	Field
(81)	Proportion





**CRW
ENGINEERING GROUP, LLC**

10000 Hwy. 101, Suite 200
 Fort Worth, TX 76155
 Phone: 817.350.0000
 Fax: 817.350.0001
 Email: info@crweng.com

CRW Engineering Group, LLC
 3940 Westgate Blvd., Suite 300
 Arlington, Texas, 76010

Submitted by: Chair of the Assembly at the
Request of the Mayor
Prepared by: Real Estate Services
For Reading: OCTOBER 24, 2006



CLERK'S OFFICE

APPROVED

Date: 10-24-06
IMMEDIATE RECONSIDERATION
FAILED 10-24-06

ANCHORAGE, ALASKA

AO NO. 2006 - 149(S)

1 AN ORDINANCE APPROVING THE ACQUISITION OF REAL PROPERTY
2 DESCRIBED AS TRACT B, MULDOON ESTATES SUBDIVISION, AND THE
3 APPROPRIATION OF AN AMOUNT NOT TO EXCEED FOUR MILLION
4 DOLLARS (\$4,000,000.00).

5
6 WHEREAS, Tract B, Muldoon Estates Subdivision, also known as the former Alaska
7 Greenhouse property, consists of approximately 29.20 acres; and

8
9 WHEREAS, Joe Bryant and the Estate of Thomas Michael Cody IV submitted a
10 preliminary plat application, dividing Tract B into three smaller parcels, including
11 proposed Lot 3 consisting of 12 acres on the backside of Tract B; and

12
13 WHEREAS, on June 6, 2006, the Assembly approved Anchorage Ordinance (AO) No.
14 2006-84, attached hereto, authorizing the purchase and acquisition of proposed Lot 3,
15 and appropriating an amount not to exceed \$1,308,000.00 to fund the 12-acre purchase;
16 and

17
18 WHEREAS, prior to completing the acquisition of proposed Lot 3, and prior to the
19 recording of the final plat for Tract B, the United State of America commenced an
20 action in the United States District Court for the District of Alaska on May 19, 2006,
21 case no. 3:06-CV-118 RRB, seeking forfeiture of all of Tract B, pursuant to 21 USC
22 §881, 18 USC §981, and other federal laws; and

23
24 WHEREAS, thereafter the holder of the first Deed of Trust filed a Notice of Default and
25 Sale of Deed of Trust Foreclosure on July 28, 2006, for the benefit of Alaska
26 Greenhouses, Inc., and a foreclosure sale is scheduled for October 26, 2006; and

27
28 WHEREAS, at this time, there are outstanding delinquent taxes, penalties and interest
29 due to the Municipality exceeding \$78,900.00; and

30
31 WHEREAS, in order to protect the Municipality's contract rights to the 12 acres
32 described in AO 2006-84, the Municipality's tax lien position, and other municipal and
33 public benefits described in the accompanying Assembly Memorandum, the
34 Municipality offered to purchase all of Tract B for the sum of FIVE MILLION
35 DOLLARS (\$5,000,000.00), plus closing costs, based upon an appraisal, after deducting
36 unpaid taxes, of \$5,040,000.00; and

37
38 WHEREAS, the Municipality received verbal approval of its offer to purchase all of
39 Tract B, Muldoon Estates Subdivision, from all interested parties; and

WHEREAS, the Municipality must complete its purchase by recording and transferring fee title to the property not later than close of business on October 25, 2006 in order to avoid a sale at foreclosure or, in the alternative, the Municipality must be prepared to bid and pay for the Property at the foreclosure sale; and

WHEREAS, when combined with AO 2006-84, the authorization and appropriation of general obligation bond funds from the Anchorage Parks and Recreation Service Area Capital Improvement Program (CIP) Fund (461) for purchase of 12 acres (proposed Lot 3), the total purchase price including closing costs for all of Tract B, Muldoon Estates Subdivision, does not to exceed \$5,308,000.00; now, therefore,

THE ANCHORAGE ASSEMBLY ORDAINS:

Section 1. The purchase of 29.20 acres, known as Tract B, Muldoon Estates Subdivision (including the 12 acres approved by AO 2006-84), by purchase or foreclosure bid, is hereby approved.

Section 2. The appropriation of an amount not to exceed FOUR MILLION DOLLARS (\$4,000,000.00) is approved.

Section 3. The Municipality is authorized to purchase Tract B, Muldoon Estates Subdivision, for an amount not to exceed \$5,308,000.00 (including closing costs), by combining the NTE \$1,308,000.00 appropriated under AO 2006-84 and the NTE \$4,000,000.00 appropriated in Section 2 above.


Section 4. The Municipality is authorized to appropriate the funds in Section 2 above by inter-fund loan from ML&P net assets (Fund 530) to Heritage Land Bank, Real Estate Services, capital purchase account (Fund 401), pursuant to the terms and conditions set out in the accompanying AM.

Section 5. This ordinance shall take effect immediately upon passage and approval.

PASSED AND APPROVED by the Anchorage Assembly this 24th day of October, 2006.


Chair of the Assembly

ATTEST:


Municipal Clerk

Attachment: AO 2006-84

G:\mat\open matters\Muldoon Estates - Property Acquisition\Tract B - final AO2006-149(S).doc

MUNICIPALITY OF ANCHORAGE
Summary of Economic Effects -- General Government

AO Number: 2006-149(S) Title: AN ORDINANCE APPROVING THE ACQUISITION OF REAL PROPERTY DESCRIBED AS TRACT B, MULDOON ESTATES SUBDIVISION, AND THE APPROPRIATION OF AN AMOUNT NOT TO EXCEED FOUR MILLION DOLLARS (\$4,000,000.00).

Sponsor: MAYOR
Preparing Agency: Heritage Land Bank, Real Estate Services Division
Others Impacted:

CHANGES IN EXPENDITURES AND REVENUES:

(In Thousands of Dollars)

	<u>FY06</u>	<u>FY07</u>	<u>FY08</u>	<u>FY09</u>	<u>FY10</u>
Operating Expenditures					
1000 Personal Services					
2000 Non-Labor					
3900 Contributions					
4000 Debt Service					
TOTAL DIRECT COSTS:	<u>\$ -</u>	<u>\$ -</u>	<u>\$ -</u>	<u>\$ -</u>	<u>\$ -</u>
Add: 6000 Charges from Others					
Less: 7000 Charges to Others					
FUNCTION COST:	<u>\$ -</u>	<u>\$ -</u>	<u>\$ -</u>	<u>\$ -</u>	<u>\$ -</u>
REVENUES:		<u>\$ (48)</u>	<u>\$ (48)</u>	<u>\$ (48)</u>	<u>\$ (48)</u>
CAPITAL:	<u>\$ 4,000</u>				
POSITIONS: FT/PT and Temp					

PUBLIC SECTOR ECONOMIC EFFECTS:

Use of previously appropriated Park bond fund (461) monies of \$1.308 million, with an inter-fund loan of \$4 million contained in this AO request. Result of purchases will add land to Municipal inventory for public park use and site control for creek relocation and restoration. At a minimum, 12 acres of privately held land will no longer be taxed and the remainder of the parcel (17.2 ± acres) would not be taxed for up to five years.

PRIVATE SECTOR ECONOMIC EFFECTS:

No anticipated major economic impact.



MUNICIPALITY OF ANCHORAGE

ASSEMBLY MEMORANDUM

AM No. 799 -2006

Meeting Date: October 24, 2006

1 **From: MAYOR**

2
3 **Subject: AO No. 2006-149(S): AN ORDINANCE APPROVING THE**
4 **ACQUISITION OF REAL PROPERTY DESCRIBED AS**
5 **TRACT B, MULDOON ESTATES SUBDIVISION, AND THE**
6 **APPROPRIATION OF AN AMOUNT NOT TO EXCEED FOUR**
7 **MILLION DOLLARS (\$4,000,000.00).**
8

9 AO 2006-149(S) seeks approval for the Municipality to purchase real property,
10 legally described as Tract B, Muldoon Estates, Subdivision, consisting of
11 approximately 29.20 acres, including 12 acres (AO 2006-84) for a future park
12 site, land for extension of DeBarr Road, and control of up to 8 acres in the
13 front of the tract to move and restore the creek. Tract B is currently zoned R-
14 2M and B3.
15

16 The Assembly approved Anchorage Ordinance (AO) No. 2006-84 authorizing
17 the purchase and acquisition of 12 acres of Tract B, Muldoon Estates
18 Subdivision and appropriated an amount NTE \$1,308,000.00 to fund the
19 purchase on June 6, 2006. AO 2006-84 assumed the preliminary plat creating
20 proposed Lot 3 would be recorded prior title transfer. However, the
21 transaction was not completed because the sellers did not meet the stipulated
22 conditions, the tract was not re-platted and the preliminary plat was not
23 recorded. In addition, the outstanding property taxes were not paid. As a
24 result, Tract B remains whole as one parcel containing 29.20 acres, and
25 negotiations were reopened for purchase and acquisition of all of Tract B.
26

27 Simultaneously, the Federal government is proceeding on the court action for
28 forfeiture.¹ The holder of the first Deed of Trust on the property, Alaska
29 Greenhouses, Inc. (AGI), scheduled a foreclosure sale for October 26, 2006.²
30 A foreclosure sale eliminates interests in the property, except property taxes,
31 and the Municipality could lose the contract to purchase the 12 acres,
32 intended for use as a future park, as well as control and over the site as a
33 whole.
34

35 Additionally, gaining site control of the entire parcel allows the front seven (7)
36 acres to accommodate the moving and restoration of the creek to the south
37 boundary of the property. Municipal site control also provides for the

¹ The United States of America commenced an action in the United States District Court for the District of Alaska on May 19, 2006, case no. 3:06-CV-118 RRB, seeking forfeiture of the entire 29.20 acre parcel (Tract B) pursuant to 21 USC 881, 18 USC 981, and other federal laws.

² A Notice of Default and Sale of Deed of Trust Foreclosure was filed on July 28, 2006 for the benefit of Alaska Greenhouses, Inc.; the foreclosure sale is scheduled for October 26, 2006.

extension of DeBarr Road, from Muldoon Road to Boston Street, without ROW purchase from a private owner, reducing the project cost. Any surplus property, after creek relocation and right-of-way extension, will be platted out and recommended for disposal. Funds received from sale of surplus property will be dedicated to repayment of the inter-fund loan, proposed as the funding source for this acquisition.

Based upon appraisal (summary attached), the Municipality proposes to purchase price all of Tract B, including the 12-acre parcel approved by AO 2006-84, for an amount not to exceed \$5,308,000.00, including closing costs. Due to the pending foreclosure sale, funding for the purchase of Tract B is proposed in through 2 combined Assembly actions:

1. The appropriation approved by AO 2006-84 of an amount not to exceed \$1,308,000.00, from general obligation bond funds in the Anchorage Parks & Recreation Service Area Capital Improvement Program (CIP) Fund (461); and
2. The appropriation requested by AO 2006-149(S) of an amount not to exceed \$4,000,000.00, from an inter-fund loan from ML&P Net Assets Fund (530) to Heritage Land Bank, Real Estate Services Fund (401).

The general terms of the inter-fund loan include:

Term: Not To Exceed Five (5) years; and
Annual Interest: Based upon the Cash Pool Earnings Rate plus 50 basis points.

THE ADMINISTRATION RECOMMENDS APPROVAL OF AN ORDINANCE AUTHORIZING THE ACQUISITION OF REAL PROPERTY DESCRIBED AS TRACT B, MULDOON ESTATES SUBDIVISION, AND THE APPROPRIATION OF AN AMOUNT NOT TO EXCEED FOUR MILLION DOLLARS (\$4,000,000.00) FROM AN INTER-FUND LOAN FROM ML&P TO HERITAGE LAND BANK, REAL ESTATE SERVICES DIVISION.

Prepared by: Heritage Land Bank, Real Estate Services Division
Approved by: Robin E. Ward, Executive Director
Concur: Mary Jane Michael, Executive Director
Economic & Community Development
Fund Certification: Jeffrey E. Sinz, Chief Fiscal Officer
401-1253-5101-125301-BY 2006 \$4,000,000.00
Concur: James Reeves, Municipal Attorney
Concur: Denis LeBlanc, Municipal Manager
Respectfully submitted: Mark Begich, Mayor

OUTLOOK VALUATION SERVICES

An Independent State Certified Real Estate Appraiser & Real Estate Consultant

3825 Lynn Drive
Anchorage, Alaska 99503

Telephone: (907) 441-2162 Facsimile: (907) 337-5494 E-mail: resco@gci.net

October 23, 2006

Ms. Robin E. Ward
Executive Director
Heritage Land Bank and Real Estate Services
Anchorage Community Development Authority
P.O. Box 196650
Anchorage, Alaska 99519-6650

Re: Restricted Use Appraisal of Tract B, Muldoon Subdivision, Anchorage, Alaska — OUR FILE #06-50

Dear Ms. Ward:

Per our telephone conversation on October 9th, 2006, I have performed a Restricted Use Appraisal of the above referenced property for the purpose of estimating the "as is" market value of its fee simple estate. The following report is a brief recapitulation of my investigations, the appraisal techniques applied, and the analyses of data leading to the following value conclusions.

Based upon the physical inspection of the property, the analyses undertaken, and subject to the special and general assumptions and limiting conditions set forth in the report, the "as is" market value of the fee simple estate in the Subject property, as of October 10, 2006, was estimated to have been:

FIVE MILLION AND FORTY THOUSAND DOLLARS

*****\$5,040,000**

According to the Municipal Treasure, \$78,971 in delinquent taxes, penalties and interest are outstanding. These charges have been deducted to arrive at the "as is" market value estimate.

The attached report is a "Restricted Appraisal" report prepared to comply with the requirements of USPAP applicable to such reports. Per your request, I have reviewed the two appraisal reports that you have provided. I reserve the right to amend my value conclusion, if information extracted from those reports and used in my analysis is found to be incorrect.

It is an express assumption of this report that the Subject is environmentally "clean" and no problems exit. Thank you for the opportunity to be of service and if you have any questions, please call.

Sincerely,



Jerry G. Smith
State Certified General Appraiser AA48

Submitted by: Chair of the Assembly At
the Request of the Mayor
Prepared by: Real Estate Services on behalf
of the Parks Department
For Reading: May 23, 2006

CLERK'S OFFICE

ANCHORAGE, ALASKA

APPROVED

AO NO. 2006- 84

Date: 6-6-06

1
2 AN ORDINANCE APPROVING THE PURCHASE AND ACQUISITION OF REAL PROPERTY
3 LEGALLY DESCRIBED AS LOT 3, MULDOON ESTATES SUBDIVISION, FOR FAIR
4 MARKET VALUE NOT TO EXCEED ONE MILLION THREE HUNDRED EIGHT THOUSAND
5 DOLLARS (\$1,308,000.00).

6
7
8 WHEREAS, the administration desires to acquire property in East Anchorage on behalf of the
9 Municipality for use as a municipal park; and

10
11 WHEREAS, Anchorage Municipal Code sections 25.20.010 and .020 authorize the Municipality to
12 acquire land for any public purpose, upon approval by the Assembly; and

13
14 WHEREAS, Joe Bryant and the Estate of Thomas Michael Cody IV are owners of a large parcel
15 that was the former Alaska Greenhouse site, legally described as Tract B, Muldoon Estates
16 Subdivision, and;

17
18 WHEREAS, Joe Bryant and the Estate of Thomas Michael Cody IV have submitted a preliminary
19 plat application creating a new tract of land encompassing the eastern twelve acres of the subject
20 site with a proposed new legal description of Lot 3, Muldoon Estates Subdivision, and;

21
22 WHEREAS, the location of this twelve-acre parcel proposed as Lot 3 corresponds with the
23 recommended acquisition of a new park in the draft Anchorage Bowl Parks, Natural Resource and
24 Recreation Facilities Plan; and

25
26 WHEREAS, on September 8, 2005, the Parks and Recreation Advisory Commission unanimously
27 approved PRC Resolution 2005-08, recommending purchase of the subject parcel; and

28
29 WHEREAS, the Municipality seeks authorization to purchase proposed Lot 3, Muldoon Estates
30 Subdivision for the amount \$ 1,307,000.00 plus closing costs, with previously appropriated general
31 obligation bond funds in the Anchorage Parks and Recreation Service Area Capital Improvement
32 Program (CIP) Fund (461); Now therefore,
33

1
2 **THE ANCHORAGE ASSEMBLY ORDAINS:**

3
4 **Section 1.** The purchase of Lot 3, Muldoon Estates Subdivision, zoned R3 and containing 12
5 acres±, for ONE MILLION THREE HUNDRED EIGHT THOUSAND Dollars (\$1,308,000.00), is
6 hereby authorized.


7
8 **Section 2.** This ordinance shall take effect immediately upon passage and approval.

9
10 PASSED AND APPROVED by the Anchorage Assembly this 6th day of
11 June, 2006.
12
13
14

15 *Daniel A. Sullivan*
16 Chairman of the Assembly
17

18 ATTEST:

19 *Bonnie E. Muench*
20 Municipal Clerk
21



MUNICIPALITY OF ANCHORAGE

ASSEMBLY MEMORANDUM

AM No. 384-2006

Meeting Date: May 23, 2006

1 From: Mayor

2
3
4 Subject: An Ordinance Approving the Purchase and Acquisition of Real Property
5 Legally Described as Lot 3, Muldoon Estates Subdivision, for Fair Market
6 Value Not to Exceed One Million Three Hundred Eight Thousand Dollars
7 (\$1,308,000).
8

9 The accompanying ordinance seeks approval for the Parks and Recreation Department
10 to purchase real property and acquire it for a future park site. The subject parcel is an
11 eastern portion of Tract B, recently replatted and awaiting recording as Lot 3, Muldoon
12 Estates Subdivision. It is zoned R-3 and is approximately twelve acres in size (see
13 attached map, Appendix A).
14

15 The Parks and Recreation Department has recently completed a draft Anchorage Bowl
16 Parks, Natural Resource and Recreation Facilities Plan. A part of that plan has been to
17 determine locations for future park and recreation sites that will be needed in the next
18 twenty years. Those locations for future park site purchases have been prioritized and
19 the Muldoon Estates Subdivision site is a priority on that list.
20

21 The subject property was identified in 2005 after the entire former Alaska Greenhouse
22 parcel was contracted for purchase by Joe Bryant and Thomas Cody. Their agent
23 approached the MOA with a proposal to subdivide from the originally platted tract (Tract
24 B) the eastern twelve acres of the property, now described as Lot 3, for a park. A
25 contract with Joe Bryant and the Estate of Thomas Michael Cody IV for the named
26 purchase amount has been signed, contingent upon the recording of the plat creating a
27 new parcel containing the east twelve acres of the property (Lot 3) and approval of the
28 purchase by the Anchorage Assembly.
29

30 At their regular meeting on September 8, 2005, the Parks and Recreation Advisory
31 Commission unanimously approved Resolution #2005-08, recommending the
32 Administration endorse and approve the purchase of the east twelve acres of Tract B,
33 Muldoon Estates Subdivision (Appendix B). This action also comports with the
34 "Anchorage Bowl Parks, Natural Resource and Recreation Facilities Plan"
35 recommendation to acquire new park land in east Muldoon (Appendix C).
36

37 Funding for the \$1,308,000 purchase of proposed Lot 3, Muldoon Estates Subdivision,
38 shall come from previously appropriated general obligation bond funds in the Anchorage
39 Parks and Recreation Service Area CIP Fund (461).
40

1
2
3 THE ADMINISTRATION RECOMMENDS ASSEMBLY APPROVAL OF THE
4 PURCHASE AND ACQUISITION OF THE PROPOSED LOT 3, MULDOON ESTATES
5 SUBDIVISION NOT TO EXCEED ONE MILLION THREE HUNDRED EIGHT
6 THOUSAND DOLLARS (\$1,308,000) FROM THE ANCHORAGE PARK BOND FUND
7 (461).
8
9

10 Prepared by: Robin E. Ward, Executive Director of Heritage Land Bank & Real Estate
11 Services

12 Concur: Mary Jane Michael, Executive Director, Economic & Community Development


13 Concur: Jeff Dillon, Executive Director, Parks & Recreation Department
14

15 Fund Certification: Jeffrey E. Sinz, Chief Fiscal Officer
16

17	461-5435-5101-543512-BY1999	\$ 157,413
18	461-5436-5101-543602-BY2000	\$ 125,911
19	461-5436-5101-543623-BY2000	\$ 56,910
20	461-5436-5101-543624-BY2000	\$ 354,800
21	461-5436-5101-543658-BY2001	\$ 237,500
22	461-5436-5101-543660-BY2001	\$ 118,750
23	461-5436-5101-543666-BY2001	\$ 114,366
24	461-5490-5101-549058-BY1998	\$ 38,949
25	461-5490-5101-549062-BY1998	\$ 10,000
26	461-5492-5101-549236-BY1998	\$ 93,400
27	Anchorage Park Bonds Fund Total	\$1,308,000

28
29 Concur: Denis C. LeBlanc, Municipal Manager
30 Respectfully submitted: Mark Begich, Mayor

Appendix A



Appendix A

MUNICIPALITY OF ANCHORAGE
Summary of Economic Effects - General Government

AO Number: 2006- 84 Title: Purchase of Lot 3, Muldoon Estates Subdivision
Sponsor: Parks & Recreation
Preparing Agency: Real Estate Services
Others Impacted:

CHANGES IN EXPENDITURES AND REVENUES:		(Thousands of Dollars)				
		FY06	FY07	FY08	FY09	FY10
Operating Expenditures						
1000 Personal Services						
2000 Supplies						
3000 Other Services						
4000 Debt Service						
5000 Capital Outlay		1,308				
TOTAL DIRECT COSTS:		1,308				
6000 IGCs						
FUNCTION COST:						
REVENUES:		(2,000)				
CAPITAL:						
POSITIONS: FT/PT and Temp.						
PUBLIC SECTOR ECONOMIC EFFECTS:						
Use of previously appropriated Park bond fund (461) monies to add land to municipal inventory for public park use. Acquisition of this property will remove it from the tax rolls, resulting in a loss of tax revenue of approximately \$2,000 per year.						
PRIVATE SECTOR ECONOMIC EFFECTS:						

Prepared by: <u>Robin E. Ward, HLB/RES Director</u>	Telephone: 343-4337
Validated by OMB: <u>Janet Mitson, Office of Management & Budget</u>	Date: _____
Approved by: <u>Robin E. Ward, Executive Director, HLB & RES</u>	Date: <u>April 17, 2006</u>

CLERK'S OFFICE
AMENDED AND APPROVED
Date: 7-14-15

Submitted by: ASSEMBLY MEMBER PETERSEN
Assembly Member Honeman
Assembly Member Starr
Prepared by: Assembly Counsel
For reading: June 23, 2015

**ANCHORAGE, ALASKA
AO NO. 2015-77**

AN ORDINANCE OF THE ANCHORAGE MUNICIPAL ASSEMBLY DEDICATING CERTAIN MUNICIPAL LAND IDENTIFIED AS PARCELS 006-401-03-000 AND 006-401-04-000, LOT 1 AND LOT 2, MULDOON ESTATES, LOCATED AT 1301 MULDOON ROAD, FOR PERMANENT PUBLIC PARK AND RECREATIONAL PURPOSES.

WHEREAS, the Anchorage Bowl Park, Natural Resource, and Recreation Facility Plan adopted by AO No. 2005-122 identified the Northeast Anchorage area as being deficient in the amount of parks and recreational facilities; and

WHEREAS, on October 24, 2006 the Assembly adopted AO No. 2006-149(S) authorizing the purchase of the former site of the Alaska Greenhouse in the Muldoon neighborhood of Northeast Anchorage; and

WHEREAS, prior to purchase by the Municipality of Anchorage, the Alaska Greenhouse operated a private park on this site; and

WHEREAS, this land, often referred to as the old Alaska Greenhouse property, has remained undeveloped and local residents use it for numerous recreational purposes including jogging, cross country skiing, and dog walking; and

WHEREAS, the old Alaska Greenhouse property is located within the boundaries of the North East Community Council, and the Scenic Foothills Community Council is the closest neighboring community council; and

WHEREAS, the location of the old Alaska Greenhouse property in the center of the Muldoon community makes it uniquely suited for park dedication to serve as a community focal point and help reestablish Muldoon as a viable neighborhood, countering development blight and easing the commercialization that hampers neighborhood balance; and

WHEREAS, the eastern portion of this property has been designated as park land and without inclusion of the western parcels, access, park usage, and neighborhood balance would be restrictive; and

WHEREAS, on October 15, 2009 the North East Community Council unanimously passed a resolution urging the Municipality of Anchorage to dedicate the entirety of the old Alaska Greenhouse property as parkland and to develop this land into a municipal park; and

WHEREAS, on July 9, 2010, the Governor Sean Parnell signed into law Chapter 43, SLA 2010, which included an appropriation of \$1,000,000.00 to the Municipality of Anchorage for the purpose of developing a park on the property, and this grant is scheduled to lapse on

July 1, 2016 if the park funding is not timely encumbered and utilized for its intended purpose; and

WHEREAS, on January 5, 2012, the Scenic Foothills Community Council unanimously voted to support the efforts to create a park on the old Alaska Greenhouse property, and the North East Community Council has unanimously confirmed its position by resolution on February 16, 2012, again urging the Municipality of Anchorage to dedicate the entirety of the old Alaska Greenhouse property as parkland and to timely develop this municipal park; and

WHEREAS, on May 1, 2014, the Anchorage Parks and Recreation Commission adopted Commission Resolution 2014-15 supporting using the whole old Alaska Greenhouse property for a park; and

WHEREAS, on December 2, 2014 the Anchorage Assembly unanimously approved AO 2014-139(S) adopting the East Anchorage District Plan which confirms utilization of the entirety of the old Alaska Greenhouse property as municipal parkland; and

WHEREAS, use of the old Alaska Greenhouse property for any purpose other than a park is contrary to historical use, community preference and priority, conscientious municipal land use, neighborhood balance, and would deprive the residents of Muldoon and greater Anchorage of a restorative recreational asset; and

WHEREAS, formal dedication to permanent public park and recreational purposes requires Assembly action by ordinance; and

WHEREAS, dedication will not interfere with Chester Creek restoration and supports the Chester Creek Watershed Plan, approved by the Anchorage Assembly in AO 2015-46 on May 14, 2015; and

WHEREAS, after formal dedication, and with recommendations from the planning and zoning commission and the parks and recreation commission under AMC 25.10.080C, additional municipal land use for purposes supporting the community may be allowed by ordinance to further the vision of the community and special accommodations reflected in the East Anchorage District Plan, except as otherwise prohibited by law or by conditions of ownership; now, therefore,

THE ANCHORAGE ASSEMBLY ORDAINS:

Section 1. As provided by Anchorage Municipal Code section 25.10.080, the municipally-owned real property identified in this section, **by its legal description prior to its re-platting in 2014** is hereby dedicated as permanent park land, subject to right-of-way and other easements of record:

Municipal Parcel Numbers 006-401-03-000 and 006-401-04-000, known as Muldoon Estates Subdivision, Lot 1 and Lot 2, located at 1301 Muldoon Road, Anchorage, Alaska and consisting of approximately 15.65 acres (approximately 681.877 square feet).

Section 2. Use of these parcels in the Chester Creek Restoration Project is hereby acknowledged and reserved as compatible use to support the community. This site is available for incorporation in a formal park use plan, subject to future community planning review, planning and zoning commission review, parks and recreation commission review, as appropriate.


Section 3. This ordinance shall become effective immediately upon passage and approval by the Assembly.

PASSED AND APPROVED by the Anchorage Assembly this 14th day of July, 2015.




Chair of the Assembly

ATTEST:



Municipal Clerk



MULDOON PARK MASTER PLAN

PUBLIC HEARING DRAFT

JANUARY 2016





TABLE OF CONTENTS

ACKNOWLEDGEMENTS

The Municipality of Anchorage Parks and Recreation Department and the Planning Team would like to recognize and thank all the individuals and organizations who have worked to create Muldoon Town Square Park and its Master Plan. A special thanks to the members of the Park Advisory Committee for their dedication, insight and assistance in generating this Park Master Plan, with additional thanks to the technical advisors and agency representatives who have shared their expertise and have provided input along the way.

MUNICIPALITY OF ANCHORAGE

John Rodda, Director of Parks & Recreation
Josh Durand, Parks Superintendent

STAKEHOLDER ADVISORY GROUP: PARK ADVISORY COMMITTEE

Kristi Wood (Chair)
Betsy Chivers
Stu Grenier
Genevieve Holubik
Kendra Kloster
Nickel LaFluer
Jerrienne Lowther
Carla McConnell
Selina Metoyer
Kevin Smestad
Dave Ulmer

PLANNING TEAM

MOA Parks & Recreation

Steve Rafuse, Project Manager
Taylor Keegan, Park Planner

Bettisworth North

Mark Kimerer, Principal
Jonny Hayes, Landscape Architect
Mélisa Babb, Designer
Alyssa Golden, Graphic Designer

R&M Consultants

Van Le, Planner
Taryn Oleson, Planner

TECHNICAL ADVISORS & AGENCY STAKEHOLDERS

Municipality of Anchorage

Randy Bergt, Transit

Sharon Ferguson, Current Planning

Francis McLaughlin, Current Planning

Stephanie Mormilo, Traffic

Jennifer Noffke, Project Management & Engineering

Russell Oswald, Project Management & Engineering

Lori Schanche, Non-Motorized Transportation

Vivian Underwood, AMATS Transportation Planning

Jeff Urbanus, Watershed Management

Alaska Department of Transportation & Public Facilities

Jonathon Knowles, Traffic

Scott Thomas, Traffic



"THANK YOU FOR ALL THE
WORK YOU HAVE PUT INTO
MAKING THIS PARK A REALITY."

* Quotations provided throughout the
document reflect public input recorded
during the planning process.



CHAPTERS

01 INTRODUCTION

OVERVIEW	1
BACKGROUND	2
HISTORY	4
PROJECT PURPOSE	7
GUIDING PRINCIPALS	7
COMMUNITY PROFILE	8
PLANNING AND POLICY DOCUMENTS	12

02 PLANNING & PUBLIC INVOLVEMENT

PUBLIC INVOLVEMENT	17
PLAN DEVELOPMENT AND APPROVAL PROCESS	24

03 EXISTING CONDITIONS

EXISTING CONDITIONS	27
SITE CONSIDERATIONS	39
PARK AS A RESOURCE	42
PUBLIC SAFETY	42
OPPORTUNITIES AND CONSTRAINTS	43

04 MASTER PLAN

MASTER PLAN	47
MULDOON AREA	52
CORE AREA	60
CHUGACH AREA	66
COMMON ELEMENTS	70


05 IMPLEMENTATION

IMPLEMENTATION.....	77
REGULATORY CONTROLS-TITLE 21	77
LAND USE REGULATIONS	77
DESIGN CRITERIA	79
FUNDING STRATEGIES	80

APPENDICES

A MEETING MINUTES

B RESOLUTIONS



01

INTRODUCTION



OVERVIEW

Muldoon Town Square Park is a newly dedicated Community Use Park located in the heart of East Anchorage at the southeast corner of the Muldoon and DeBarr Road intersection. The park encompasses 26.74 acres of natural and previously developed areas, with features that include the South Fork of Chester Creek, outstanding views of the Chugach Mountains, as well as upland forests and open meadows.

The park is defined by East DeBarr Road Right-of-Way (ROW) to the north; Muldoon Road to the west; East 14th Avenue ROW, residences and Windsong Park to the south; and Joint Base Elmendorf-Richardson (JBER) to the east.

The Muldoon Town Square Park Master Plan is a 20 year vision for the park. The Master Plan envisions a park that provides active year-round recreation and community event space for residents of East Anchorage. The Master Plan identifies current and future community needs and provides a framework for the development, management, and maintenance of the park. More than a guiding document, this Master Plan actualizes the community's vision for a destination park in East Anchorage that provides a gathering place for all residents to participate in healthy activities in a safe, clean, and beautiful natural setting.



Location of Muldoon Town Square Park

Stakeholder Advisory Group: Park Advisory Committee

- » Kristi Wood (Chair)(NECC)
- » Nicki LaFluer (NECC)
- » Jerrianne Lowther (SFCC)
- » Genevieve Holubik (NECC)
- » Dave Ulmer (NECC)
- » Selina Metoyer (NECC)
- » Stu Grenier (NECC)
- » Kendra Kloster (NECC)
- » Betsy Chivers (NECC)
- » Kevin Smestad (NECC)
- » Carla McConnell (NECC)

Technical Advisors + Agency Stakeholders


- » Municipality of Anchorage (MOA)
- » Watershed Management
- » Anchorage Metropolitan Area
- » Transportation Solutions Transportation
- » Planning (AMATS)
- » MOA Non-Motorized Transportation
- » Planning
- » MOA Project Management and
- » Engineering (PM&E)
- » MOA Current Planning
- » MOA Traffic
- » MOA Transit
- » Alaska Department of Transportation &
- » Public Facilities (AKDOT&PF) Traffic

Public Outreach Program:

See Chapter 2: Planning and Public Involvement

Planning Team

- » Stephen Rafuse
- » Taylor Keegan
- » Mark Kimerer
- » Jonny Hayes
- » Melisa Babb
- » Alyssa Golden
- » Van Le
- » Taryn Oleson



BACKGROUND

The creation of Muldoon Town Square Park has long been a priority for East Anchorage residents and decision makers. Since the


Municipality of Anchorage purchased the property in 2006, the local community has advocated for a park and public gathering space where residents can enjoy and experience nature in an increasingly urban environment. Community members have consistently voiced a strong desire for a shared public space and destination fronting Muldoon Road that is reminiscent of the character, uniqueness and popularity of the former Alaska Greenhouses, a popular commercial nursery operation located on the site and owned by the late Mann Leiser.

After the Alaska Greenhouses closed in the 1990's, commercial and residential development in the area continued. However, little to no development occurred

on site. Over the years, various studies of the site were completed for commercial and institutional development, but with poor soils and limited access from Muldoon Road the site remained undeveloped.

In 2014, the *East Anchorage District Plan (EADP)* was adopted. The *EADP* identified the need for a small area planning process to determine appropriate development and use of the site. During the *EADP*'s public process, the community clearly stated a strong desire to protect and enhance the large undeveloped site as a park and open space.

Following the adoption of the *EADP*, the Anchorage Assembly in 2015 officially dedicated the property as a municipal park. With the formal dedication of the property as parkland, the Municipality of Anchorage Parks and Recreation Department began the Master Planning process.



The Muldoon Town Square Park Master Plan is the formal resolution of the second priority action of the *East Anchorage District Plan*: “Initiate a small area planning process for the old greenhouse site at Muldoon and Debarr and complete a development plan for appropriate uses of this site, including a park. Secure a formal park dedication upon completion” (p 32, *EADP*).

The *EADP* outlines a small area plan process and recommends the inclusion of a stakeholder advisory group, a technical advisory group, and a public outreach program. The *EADP* also recommends that the small area planning process include discussions of the “benefits of a full park parcel versus partial commercial, retail or service frontage on Muldoon” and acknowledges that “traditional strip commercial land use ins not an option at this location.” (p 33, *EADP*).

Chester Creek Realignment Project and Property Re-Plat

As the East Anchorage District Plan was being completed, a major construction project to realign Chester Creek at Muldoon Road was beginning. The realignment project was led by MOA Project Management and Engineering (PM&E) and included numerous federal, state, local, and non-profit partners. The goal of the project was to realign Chester Creek east of Muldoon Road to improve fish passage, water quality and flood capacity.

The project included a re-plat of parcels prior to becoming a park. The re-plat included a reconfiguration of parcels to include a single parcel (Tract D) that wholly contains the newly aligned creek as it flows downstream of Windsong Park. The re-plat also dedicated a 30 foot wide strip at the southwest property line with a 55 foot radius cul-de-sac terminus as right-of-way for a future East 14th Avenue, decreasing the total acreage of the park to 26.74 acres. In addition to the newly minted plats, the new alignment of Chester Creek bisects the park in the north/south direction and physically separates Tract B (“The Hill”) from Tract A, the westernmost parcel accessed from Muldoon Road.



HISTORY

To the Dena'ina Athabascan people, “Chanshtnu” (meaning Grass Creek), was an important fishing site. Coho salmon spawn in the headwaters of the creek east of Muldoon Road and south of DeBarr. “Chanshtnu” was long ago anglicized and today is more commonly known as Chester Creek.


The late Mann Leiser’s Alaska Greenhouse, though privately owned, in its heyday was among the most beloved “parks” in town. East Anchorage residents came there year around to marvel at fish and ducks swimming in the creek, next to nursery stock shrubs and trees. During that time, Mann Leiser had built a greenhouse over Chester Creek.

The Leiser family home was located on a hill behind the greenhouses. The middle and back portion of the property, which extends to the JBER/Fort Richardson boundary, was used as a dump for fill as neighboring areas developed. With the deposition of fill, peat soils and the location of Chester Creek, wetlands and floodplains, the site has long been considered problematic for development. These assumptions were confirmed in the early 2000’s, when the Anchorage School District explored the site as a potential location for the “Muldoon Middle School” or what is now Begich Middle School.

After Mann Leiser’s death, the Alaska Greenhouse property was sold and later seized from its then owners by the U.S. government in a drug case. The Municipality of Anchorage bought it from the federal government in 2006 and designated the easternmost 12 acres as the yet-



Calendar cover image published by
the Alaska Greenhouses, Inc. (1990)



to-be-developed Muldoon Community Park; the Muldoon Road frontage was to be sold for commercial development to recoup the Municipality's investment.

The Northeast Community Council had long sought the entire property, including the frontage, for a "Muldoon Park Strip" to bring needed green space to Anchorage's most densely populated area. A large park fronting Muldoon Road would help define a Muldoon "Town Center," as envisioned in the Anchorage 2020 Comprehensive Plan.

The East Anchorage District Plan, initiated in March 2012 and adopted by the Anchorage Assembly December 2, 2014, recognized the community's desire to dedicate all the parcels for a community use park. On July 14, 2015, the Anchorage Assembly voted to dedicate the entire old Alaska Greenhouse site as parkland.

Area Legislators secured two state grants totaling \$1.5 million to plan and develop this new community park.

Park History courtesy of the Muldoon Town Square Park Advisory Committee members Jerrienne Lowther, Kristi Wood, and David Ulmer.



"I AM SO GLAD A
PARK IS GETTING


ESTABLISHED HERE.


MANN LEISER

WOULD APPROVE."



"HEALTHY PARKS,
HEALTHY PEOPLE."





PROJECT PURPOSE

This Master Plan is intended to provide a long range vision for the Muldoon Town Square Park over the next 20 years. It identifies community needs, addresses public expectations and establishes a framework for future development of the park. More specifically, the purpose of the Master Plan is to:

- » Identify and prioritize improvements consistent with desires of the East Anchorage community
- » Develop a “small area plan” for the Muldoon Road frontage as prescribed in the EADP
- » Provide a park that encourages positive use and discourages undesirable activities
- » Develop the park in a manner that balances new facilities with existing natural areas
- » Create a tool for future fundraising

GUIDING PRINCIPLES

The mission of the Anchorage Parks and Recreation Department is to ensure that Anchorage parks are well maintained and safe for the public. This mission is embodied in the motto “Healthy Parks, Healthy People”. To fulfill this mission, the Anchorage Parks and Recreation Department is guided by a set of eight strategies or core values. These strategies guide the Parks and Recreation Department in the management of Municipal parklands and were established in the *Anchorage Bowl Park, Natural Resource, and Recreation Facility Plan (2006)*.

Core Values & Strategic Goals

1. Improve Maintenance and Stewardship of What We Have
2. Private-Public Partnership
3. Parks as Community Building Blocks
4. Parks as Economic Engines
5. Balanced Services & Facilities for a Diverse Community
6. Access and Connections
7. Stewardship of Natural Resources
8. Creating a Strong Parks and Recreation Organization

These eight strategies serve as the basis for future action and decision-making and are the product of a comprehensive and on-going public engagement process.




Photo Credits: Jerrienne Lowther


COMMUNITY PROFILE CONTEXT AND LAND USE

East Anchorage is a diverse and dynamic area of Anchorage that has long-established pioneer, homesteading and original settlement roots that is experiencing growth and change. As a gateway to Joint Base Elmendorf Richardson (JBER), Tikahtnu Commons retail lifestyle center, the Alaska Native Heritage Center, Chugach Foothills recreation areas and the Glenn Highway connection to Chugiak-Eagle River and the Matanuska-Susitna Valley, the Muldoon area in East Anchorage is well positioned to be a complete community within the Anchorage Bowl.

Muldoon Road serves as the north-south corridor through Muldoon and carries an average of 30,000 vehicles a day (AK DOT&PF, 2015), including locally serving traffic and commuters from Chugiak-Eagle River and Mat-Su Valley via the Glenn Highway. Muldoon Road supports the Muldoon Town Center commercial district and also serves as a transportation link for surrounding neighborhoods.

A public transit transfer station at Muldoon and Debarr Road, a public library, community services, and commercial, retail, and restaurant development have increasingly made East Anchorage a complete community, nearly independent from the rest of Anchorage. As Anchorage builds out its housing and commercial land supply, the Eastside has been an opportunity area for redevelopment; increasing housing diversity and densities, town center commercial development, and Big Box retail such as the new Super Walmart near the Muldoon Town Square Park site. Plans for higher density residential and commercial development north of the existing Fred Meyer's store on Muldoon and Debarr Road will supplement the mixed used development currently built at the Grass Creek neighborhood to the south.

To compliment this growth is the Muldoon Town Square Park, a community gathering space that residents have passionately and tirelessly worked to preserve within the context of development pressures all around. An old and unique space with a well-known history tied to the original pioneers of the Muldoon area, the Park embodies the potential of what residents have wanted for Muldoon; a destination and escape from the everyday urbanism of a modern, last-frontier city. The Park is expected to change and mature with area residents, meeting new demands for public open space and recreation.






Photo Credit: Jerrianne Lowther

POPULATION AND DEMOGRAPHICS

Anchorage's population as estimated by the US Census was 301,010 in 2014. The Northeast Subarea population, including the Northeast Community Council area and Scenic Foothills Community Council area, had a total of 56,300 residents (2010 Census, EADP 2014), and is home to approximately 20 percent of Anchorage's population. Of that population, 17,486 people reside within the immediate Muldoon Town Square Park Area which includes Northwest Muldoon (Census Tract 7.02), Northeast Muldoon (Tract 7.03), and Muldoon (Census Tract 17.31). The map to the right shows the tract locations. The increase in population from 2010 census indicates 1.1% of growth, and generally supports data recognizing East Anchorage as a growing community within the Municipality of Anchorage. Segments of the population between 20-40 years old and 60 and older are expected to increase over the next 20 years. The median age for the three census tracts is 31.4 years of age (EADP 2014).

Schools within the Muldoon area are representative of the diverse and cultural aspects of the neighborhoods they serve. Muldoon Elementary has one of the more diverse makeups within the Anchorage School District, with the student population ethnicity falling into the following Census defined groups: 16% White, 7% African American or Black, 13% Alaska Native or American Indian, 38% Asian or Pacific Islander, 20% Two or More Races, 6% Hispanic or Latino (of any race)(ASD, Oct 2015). Begich Middle School, which draws population from five schools within the Muldoon area consists of students who are 25% White, 11% African American or Black, 10% Alaska Native or American Indian, 27% Asian or Pacific Islander, 18% Two or more races, 9% Hispanic or Latino (of any race) (ASD, Oct 2015).


"OUR DIVERSITY.

I WOULD LIKE
THAT SHOWCASED,


RECOGNIZED AND
CELEBRATED."

Ethnicity: Percent Population


Muldoon Elementary School
Data: Anchorage School District Oct. 2015



Begich Middle School
Data: Anchorage School District Oct. 2015



Census Tracts 7.02, 7.03, 17.31
Data: U.S. Census Bureau 2010



Asian or Pacific Islander

White or Caucasian

Alaska Native or American Indian

African American or Black

Other

Two or More Races

Snapshot

Data: U.S. Census Bureau 2010

Census Tract 7.02

5,107 population
1,853 households
\$72,883 median income

Census Tract 7.03

5,706 population
2,051 households
\$44,567 median income


Census Tract 17.31

5,823 population
2,064 households
\$63,404 median income


Population: Age


Census Tracts 7.02, 7.03, 17.31

Data: U.S. Census Bureau 2010



Median Age: 31.4





¹ Municipality of Anchorage. (2001). *Anchorage 2020 – Anchorage Bowl Comprehensive Plan* (AO 2000-119S). Anchorage: Municipality of Anchorage.



² Municipality of Anchorage. Department of Community Planning and Development. (1997). *Area-wide Trails Plan*. Anchorage: Municipality of Anchorage.



PLANNING AND POLICY DOCUMENTS

ANCHORAGE 2020 – ANCHORAGE BOWL COMPREHENSIVE PLAN¹

Anchorage 2020 is the comprehensive plan for the Anchorage Bowl. Adopted in 2001, Anchorage 2020 provides land use policies and specific actions to guide decision makers over the twenty-year life of the plan. The Muldoon Town Square Park Master Plan supports the *Neighborhood Identity and Vitality, Natural Open Space, and the Parks, Trails, and Recreation* goals of the Anchorage 2020 Comprehensive Plan.

The Comprehensive Plan recognizes the area of Muldoon Road and DeBarr Road as a “Town Center”. According to the plan, “town centers are designed to function as a focal point for community activities. Their core is to be a mix of community-serving retail, public services, and public/civic facilities, including and/or surrounded by medium- to high-density residential development” (page 54). Additionally, the Plan states that “unique public spaces should be created within each of these town centers to create a distinctive identity and sense of place. These can take various forms, such as linear parks centered along a creek or wetland, community parks, enhanced street environments, or unique architectural features” (page 55). The Muldoon Town Square Park will provide the area’s Town Center with an attractive local and open natural space, enhancing the mixed use in the area with a much needed public recreational and gathering place.

ANCHORAGE AREA-WIDE TRAILS PLAN²

The Anchorage Area-wide Trails Plan was adopted by the Anchorage Assembly on April 8, 1996 and is a component of the Anchorage Bowl Comprehensive Development Plan as well as the Long-Range Transportation Plan. Because Muldoon Town Square Park is a relatively new park, the Trails Plan does not include specific recommendations for the site. However, the Area-wide Trails Plan map shows a planned/proposed multi-use trail extending east from DeBarr Road and continuing along Chester Creek in what is now the Muldoon Town Square Park site, north of Windsong Park. This trail is shown connecting with a planned/proposed north-south multi-use trail along the MOA/JBER property boundary, and identified as the “Muldoon Perimeter Trail” in the *East Anchorage District Plan*. Additionally, the Trails Plan provides relevant information on recreation and trails in the area as well as design standards.

EAST ANCHORAGE DISTRICT PLAN³

The *East Anchorage District Plan (EADP)* was adopted by the Anchorage Assembly on December 2, 2014. It is an element of the *Anchorage 2020 – Anchorage Bowl Comprehensive Plan*. The plan is intended to enhance the quality of life for present and future residents by anticipating and planning for future population growth and changes within the District.


The *East Anchorage District Plan* identifies several “Priority Actions” for near-term implementation. One of those priority actions is to “Initiate a small area planning process for the former greenhouse site at Muldoon and DeBarr and complete a development plan for appropriate uses of this site, including a park. Secure a formal park dedication upon completion” (page 32).

The Muldoon Town Square Park Master Plan fulfills the *EADP*’s recommendation for a “small area planning process”. The process used to develop this Master Plan included a Park Advisory Committee, which served as the stakeholder advisory group identified in the *East Anchorage District Plan*, agency coordination with public agencies that have an interest in the park area, and an intensive public involvement program which is discussed in further detail in *Chapter 2: Planning and Public Involvement*. Through extensive community engagement, an appropriate level of development was determined. The Master Plan provides site specific recommendations that support both the community’s desire for green space and active recreation, as well as neighboring Town Center development, meeting the intent of the “Priority Action” of the *East Anchorage District Plan*.


The *East Anchorage District Plan* identifies a Muldoon Perimeter Trail aligned with the neighborhood-JBER boundary, and connecting to Muldoon Town Square Park at its eastern edge (pages 65-66). This Master Plan recognizes the opportunity to connect the park to the larger regional trail network and incorporates recommendations to support the development of a future connection/trailhead.

ANCHORAGE PEDESTRIAN PLAN⁴


The *Anchorage Pedestrian Plan* was adopted by the Assembly in 2007 and establishes a 20-year framework for pedestrian improvements in Anchorage. The Plan identifies deficiencies in pedestrian infrastructure and provides recommendations for future investment. Within the plan, the intersection at Muldoon Road and DeBarr Road was identified as one of the top 5 intersections for pedestrian-vehicle crashes, having 10 from 1998-2002 (page 23).



³Municipality of Anchorage. (2014). *East Anchorage District Plan* (Public Hearing Draft) (AO 2014-1395). Anchorage: Municipality of Anchorage.



⁴Municipality of Anchorage. Traffic Department. *Anchorage Metropolitan Area Transportation Solutions*. (October 2007). *Anchorage Pedestrian Plan* (AO 2007-96). Anchorage: Municipality of Anchorage.



⁵ Municipality of Anchorage, Planning Department and Parks and Recreation Department. (April 2006). *Anchorage Bowl Park, Natural Resources, and Recreation Facilities Plan* (AO 2005-122). Anchorage: Municipality of Anchorage.




Figure 24 Anchorage Bowl Park Districts



ANCHORAGE BOWL PARK, NATURAL RESOURCES, AND RECREATION FACILITIES PLAN⁵

The *Anchorage Bowl Park, Natural Resource, and Recreation Facility Plan (Park Plan)* is an element of the *Anchorage 2020 – Anchorage Bowl Comprehensive Plan*. The *Park Plan* establishes standards for levels of service, and makes specific recommendations based on the needs of park districts in the Anchorage Bowl.


The *Park Plan* categorizes parks, facilities, and open space by size, function and use. Muldoon Town Square Park is classified as a Community Use Area (CU). These parks are larger in size and serve a larger population than neighborhood parks. Types of CU parks include “Community Parks” and “Town Center Parks”. CU parks focus on meeting the needs of several neighborhoods. According to the *Park Plan*, CU parks “meet the specialized needs of a broader community: have higher technical design requirements; provide a sense of community; and increase economic development potential”.

The Northeast Park District (NE) is one of the older regions in the Anchorage Bowl and has the largest concentration of parks, recreation facilities and natural resources totaling 2,578 acres. The area is home to 30 athletic fields, 25 playgrounds, and 13 picnic shelters.

The Northeast Park District is also the most populous region in Anchorage with 69,779 residents. At present, the NE District is able to meet most of the Level of Service needs for parks. However, projected population growth of up to 20% (83,443 people) by 2020 will leave the District deficient in several aspects of the park system. The 2006 *Park Plan* identifies that the NE District will have a shortage of up to 57 acres of Community Use (CU) areas by 2020. This will require 1 to 2 new CU parks. Areas identified as deficient in CU Parks within the NE District are the “Muldoon and DeBarr” and “University” areas.

Based on an assessment of needs for CU Parks in the NE District, the *Park Plan* recommends that a Community Use Park be developed at Muldoon and DeBarr as part of a new town center.

The *Park Plan* recommends that the Municipality acquire and develop a new park at the Creekside Town Center, more specifically, the plan states “acquire new parkland in east area as part of town center for community use”. The plan also recommends that a new community center be developed “in partnership with Muldoon/Creekside Town Center development within the vicinity of Muldoon Road and DeBarr Road” (pages 80-83).



⁶Anchorage Waterways Council. Municipality of Anchorage. Municipal Planning Department and Watershed Management Services. (2014). Chester Creek Watershed Plan (Draft, Revision 5, November 7, 2014). Anchorage: Municipality of Anchorage.

<http://anchoragewatershed.com/ChesterCrkWatershedPln.pdf>




Figure 3.19 Community Councils in Chester Creek Watershed



CHESTER CREEK WATERSHED PLAN⁶

The Muldoon Town Square Park site is located in the Chester Creek Watershed, with Chester Creek and Chester Watershed Wetlands occupying portions of the site. The draft update to the *Chester Creek Watershed Plan* includes plan implementation strategies that shall be considered and supported by the Master Plan and future park development. Implementation goals within the draft document address water quality, water quantity, wildlife habitat, fish habitat, social and economic opportunity, communication and coordination, and data acquisition. The seven goals of the plan are as follows:

- » Meet State standards for water quality in Chester Creek.
- » Return Chester Creek to a more natural hydrologic scheme.
- » Provide habitat for diversity of wildlife along Chester Creek.
- » Provide for healthy fish and other aquatic organism populations in Chester Creek.
- » Foster a high degree of social and economic opportunities.
- » Have a highly motivated and dedicated community and Municipality in maintaining the health of Chester Creek.
- » Improve our understanding of the watershed.

Specific goals of the *Draft Chester Creek Watershed Plan* for the South Fork of Chester Creek at, and upstream of, Muldoon Road that may influence the Master Plan and Park development (CSF-19, CSF-20, CSF-21) can be found in Appendix 6.1 “Restoration Priority Locations for Chester Creek Watershed” on page 70 of the draft document. Action items include a review of the recently completed Chester Creek Realignment Project design, creation of a more natural creek, alignment to Hill with a 100-foot corridor, and removal of debris from the creek.


MUNICIPALITY OF ANCHORAGE CODE OF ORDINANCES

- » AO 2001-182 Anchorage Ordinance amending a 9.54 acre portion of Section 21, T13N, R3W, S.M., AK parcels along Muldoon Road to B-3 with Special Limitations to allow tire repair, wheel alignment and brake service as permitted uses.
- » AO 2006-149 (S) approved the acquisition of 29.20 acres making up Muldoon Estates Subdivision for a future park site and for control of the creek parcel to enable its future realignment.
- » Plat 2007-18: Recorded plat of Muldoon Estates Subdivision into three parcels after initial purchase of land by the Municipality of Anchorage.
- » Plat 2014-30 provided the mechanism to tract out the Park into separate parcels for the Chester Creek realignment and creek restoration (Tract D).
- » AO 2015-77 formally dedicated the parcels that make up Muldoon Town Square Park in 2015 to ensure its future permanent use as parks and recreation.

02

PLANNING & PUBLIC
INVOLVEMENT





PUBLIC INVOLVEMENT

Public involvement is essential to a successful planning process. The Muldoon Town Square Park Master Plan process placed significant emphasis on meaningful public engagement to ensure the Master Plan meets the needs and expectations of the community. The public involvement process was led by the Anchorage Parks and Recreation Department with support from Bettisworth North and R&M Consultants (the planning team). The planning team facilitated a public involvement process that included monthly meetings with the Park Advisory Committee, two public workshops, an online survey, and work with students at Begich Middle and Bartlett High Schools.

East Anchorage residents have long advocated for a Muldoon Town Square Park, leading first to the acquisition of the property in 2006, later to the identification of the park as a priority in the East Anchorage District Plan in 2014, and finally the dedication of parkland by the Anchorage Assembly in 2015. The EADP revealed diverse opinions, strong values and vested interests in development of the area. Public engagement for this Master Plan was focused on building consensus and allowing the character, uses and features of the park to be largely determined by the community that had advocated for its establishment. The Master Plan contains the expressed community needs, desires, and expectations identified throughout the planning process. The following narrative summarizes the planning and public involvement components of the Master Plan and includes a description of the approval process.

OUTREACH

The planning team kicked off the project with a meeting of the Park Advisory Committee and a presentation at the Scenic Foothills Community Council. Parks and Recreation staff also attended the Spirit of Muldoon community picnic to share information about the Master Plan process and to gather input from local residents. Park Advisory Committee members distributed over 500 flyers to neighborhood residents. Information and project updates were posted online and through social media.




Park Advisory Committee members participating in a site walk-through

PARK ADVISORY COMMITTEE

An eleven member Parks Advisory Committee (PAC) served as an advisory group to the planning team throughout the development of the Master Plan. The PAC was comprised of members from both the Northeast and Scenic Foothills Community Councils. The committee was tasked with providing insight, information, recommendations and feedback to help guide the planning team through the development of the Master Plan. The PAC also served as a sounding board for the citizens of the Muldoon area, ensuring that improvements identified in the plan align with the desires of the broader community. The committee actively participated in the public meetings, a PAC design charrette, and review and refinement of the concept design alternatives to develop the preferred site plan design. The committee's most important task was to help build consensus on a preferred alternative site plan.

At the project's beginning in September of 2015, the PAC joined members of the project team for a site walk-through to identify key features and areas and share ideas about desired activities, characteristics of the park, and the community's vision. Committee members shared their first-hand knowledge and helped the planning team better understand the history of the park and existing site conditions. The committee met monthly from August to December, during the most intensive community involvement and alternative design phase of the process.

Using information from the site visit, public workshop #1, and ongoing investigations and research into the site, the Planning Team facilitated a three hour design charrette with the Park Advisory Committee. This exercise empowered the PAC to develop a series of concept design alternatives for the park based on the public's input and feedback from the first workshop. Small groups worked together to create their ideal park, resulting in four concept design alternatives. The results of each group's concept design alternatives were presented to the larger group for additional feedback and discussion about how each team approached the process and arrived at important decisions. A fifth concept alternative was electronically generated with notes by a Park Advisory Committee member unable to attend the design charrette and shared with the Planning Team for insight and consideration. The planning team then identified common themes and activities shared by the concept alternatives and summarized them in a simple diagram. This summary, and each refined concept design alternative, were presented back to the PAC and at the second public workshop.



"I'D REALLY LIKE
TO SEE THINGS WE
DON'T ALREADY HAVE
ON THE EAST SIDE
OR CLOSE BY TO
SPUR INTEREST."




PUBLIC MEETINGS

The Planning Team facilitated two public planning workshops at Begich Middle School to gather input and inform the development of the Master Plan. Each workshop began with a presentation of the project process and timeline, included a review of existing site conditions and featured interactive small group discussions and park planning exercises. Relevant displays, fact sheets and multiple ways to provide comments and feedback were provided throughout each workshop. See appendices, Public Meeting Minutes and Public Input for workshop materials and results.

PUBLIC WORKSHOP #1

Approximately 48 people attended Public Workshop #1 hosted by the Planning Team to gather input from area residents, community members, and stakeholders. The workshop focused on visioning as well as what areas and existing features of the park were most desired, or problematic. Following a large group vision exercise, participants broke into small groups and completed a "Power of Ten" exercise that challenged individuals and groups to generate ten or more uses or activities that they, or their community desired, then identify their short-term and long-term priorities for development at the park. Each group then reported their top three priorities back to all workshop attendees.

With the results of the two workshop exercises, the Planning Team set to align the desired activities with spatial requirements and standards to better understand what physical opportunities and constraints may be expected to influence the Master Plan and its implementation. A series of concept design alternatives were then generated by the Park Advisory Committee during a facilitated design charrette which were then refined by the Planning Team to present at the second workshop.

The image is a full-page photograph of a scenic autumn landscape. A paved road curves through a forest with trees displaying vibrant yellow and orange foliage. In the foreground, there is a grassy area with some fallen leaves. A large, semi-transparent chevron graphic is overlaid on the left side of the image, pointing towards the right. The text is centered horizontally and overlaid on the road and trees.

"WE ARE GOING TO
WORK TOGETHER
AND MAKE THIS A
DESTINATION PARK."



AGENCY COORDINATION

Planning for the development of Muldoon Town Square Park required the coordination of multiple state and local agencies in the early stages of the process to ensure that development identified in the Master Plan will be compatible with the surrounding area. The planning team facilitated an agency coordination meeting to revise and advance concept design alternatives that were responsive to existing conditions, agency-planned projects, and important technical input. One such revision to the concept alternatives included increasing on-site parking to support development of the park, which was not adequately represented in earlier drafts of the concept design alternatives. The agency coordination meeting was attended by 21 people and included representatives from AKDOT&PF; MOA Planning, Project Management & Engineering, Non-motorized Transportation, Traffic, Transit, Watershed Management, and AMATS, as well as members of the Park Advisory Committee.

The planning team sought to address the following topics:

- » Site vehicle and non-motorized access and circulation
- » East DeBarr Road and East 14th Avenue Right-of-Way considerations
- » Anticipated Muldoon Road traffic and/or safety improvements
- » Muldoon Road and East DeBarr Road intersection options
- » Anticipated parking requirements
- » Access to public transit
- » Zoning and platting requirements
- » Park and facilities maintenance
- » Neighboring "Town Center" development
- » Compatibility of park development with Chester Creek and mapped wetlands

Valuable feedback was obtained at the agency meeting and subsequent follow-up discussions, with several questions answered and issues being resolved. Following the meeting, the draft design charrette concept alternatives were refined to reflect input and were prepared for presentation at Public Workshop #2.



PUBLIC WORKSHOP #2

The second Public Workshop had approximately 29 people in attendance and focused on alternative development scenarios assembled from information gathered at the first workshop and concept design alternatives generated by the Park Advisory Committee and refined base on agency input. Workshop participants worked in groups to assemble a preferred alternative from the design options provided using a mix and match approach.

The design exercise identified distinct alternatives for each of the three main areas of the Park: an inviting destination at the western Muldoon Road frontage (Muldoon), a nature-focused trail and recreation area at the far eastern area of the park (Chugach), and an active community and neighborhood Core in the middle area of the park (Core). For each area participants had four concept design alternative options to choose from, totaling 12 different design pieces. Participants were asked to work in groups to organize the various pieces into a cohesive community park. Each group reported their preferred design back to the larger group. Results of the exercise demonstrated overwhelming support for a master plan representative of a single Muldoon section that included a play area, ice skating ribbon, and event space; an active Core with community gardens, bicycle pump park, and open recreation; and a less developed Chugach section limited to multi-use paths, loops, and connections, prominent viewpoints, and open recreation. Numerous groups revised locations of activities between sections and alternatives. Commonly shifted items included the addition, or relocation, of a dog park to the Core section, and the addition of creek access to the Muldoon section.


Following the workshop, the planning team developed three alternatives representative of the results and modifications presented by the public. The three alternatives were presented to the Park Advisory Committee for consideration, discussion, and resolution. Decisions focused on the inclusion and location of a dog park, access and configurations of the ice ribbon loop and play area, anticipated parking requirements, and the initiation of a shared-use parking agreement. Each decision point was discussed and a single preferred alternative was advanced.

STUDENT PARTICIPATION

The youth of today are the stewards of tomorrow. To better understand the question of “what young people want”, the planning team worked with students and administrators at Begich Middle School and Bartlett High School. Approximately 80 students at Begich Middle School completed the “Power of Ten” forms (see appendices, Public Input). Students at Bartlett High School were presented the planning process and alternatives, followed by dialogue about community open space needs and what types of recreational opportunities students desired at Muldoon Town Square Park. The student feedback was thoughtful, creative, and was consistent with the community input.

ONLINE SURVEY


The planning team also administered an online survey to gather additional input from members of the public. The survey was made available on the project website and was circulated through the Community Council email system and social media. A total of 223 individual responses were collected. Survey responses were used to identify priorities and inform the development of the Master Plan (see appendices, Public Input). The charts to the right show results from some of the questions asked in the survey.



Rate your priorities for future investments and improvements at Muldoon Town Square Park?
Data: Online Survey, Parks & Recreation Nov. 2015


What is the preferred way you will travel to or access the park?


Data: Online Survey, Parks & Recreation Nov. 2015



What is your biggest concern when visiting a park?

Data: Online Survey, Parks & Recreation Nov. 2015





PLAN DEVELOPMENT AND APPROVALS


The planning team worked closely with the Park Advisory Committee to develop the Muldoon Town Square Park Master Plan. The graphic above outlines the process.

Presentations to both the Northeast Community Council and the Scenic Foothills Community Council resulted in unanimous signed resolutions of support for the Master Plan. Following the resolutions, the planning team presented the Master Plan at a public hearing at the Parks and Recreation Commission. The Master Plan was unanimously supported and approved by the Parks and Recreation Commission. The plan has been submitted to the Municipality of Anchorage Planning Department for review and will then be presented at a public hearing at the Planning and Zoning Commission for final approval.

Concurrent with implementation of the Master Plan, the park parcels fronting Muldoon Road are recommended for re-zone to PR (Parks and Recreation District) from their current designations of B-3 SL (General Business District, Special Limitations) and R-2M (Residential, Multi-Family). Re-zone to a single PR district will provide continuity in planning development of the park and serve as a long-term mechanism to ensure that development of the park is consistent with Anchorage Municipal Code Title 21, Land Use Planning (Title 21).

Additionally, implementation of the Master Plan will include design, site plan development, and construction of public facilities requiring review and approval of the Urban Design Commission in accordance with the requirements of Title 21.


Plan Development



Student Surveys



Revised
Concept Design
Alternatives



Public
Workshop #2



Draft Preferred
Alternative



Park Advisory
Committee
Review Meeting



Preferred
Alternative

Approvals




Northeast & Scenic
Foothills Community
Council Resolutions
of Support



Park and
Recreation
Commission
Approval



Planning
and Zoning
Commission
Approval



Draft Concept Design Alternative Example



Revised Concept Design Alternative Example




Draft Preferred Alternative Example

REQUIRED APPROVALS

1. NORTHEAST COMMUNITY COUNCIL RESOLUTION OF SUPPORT
2. SCENIC FOOTHILLS COMMUNITY COUNCIL RESOLUTION OF SUPPORT
3. PARKS AND RECREATION COMMISSION APPROVAL
4. PLANNING AND ZONING COMMISSION APPROVAL


03


EXISTING CONDITIONS



EXISTING CONDITIONS

This chapter summarizes the existing physical features and characteristics of the Muldoon Town Square Park site. The information presented is based on publicly available data and numerous site observations by the Planning Team in the summer and fall of 2015, with significant assistance provided by the Parks Advisory Committee. Existing site conditions were summarized and presented at both public workshops for feedback and additional input.





Muldoon Estates Subdivision Tract A
Area: 2.492 Acres
Zoning: B3-SL

Easements: 10' Slope and Stabilization Easement adjacent to Tract D. 25' Stream Maintenance & Protection Easement is vacated by the completion of the Chester Creek Realignment Project. 10' Telephone & Electrical (T&E) easement and 15' Selback easement at north property line (15' total). 10' T&E easement and 8' Arterial Landscaping easement (18' total) is located at west property boundary. 20' radius DTP to R.O.W. and 15' x 30' Water easement at northwest corner of parcel.

Muldoon Estates Subdivision Tract D
Area: 3.659* Acres
Zoning: B3-SL

Easements: 30' Sanitary Sewer & Trail Easement connecting Tract C with Tract F. 25' Stream Maintenance & Protection Easement, based on true location of creek, measured from centerline of creek per record Plat 2007-18. 10' T&E easement at north property line. 10' T&E easement and 8' Arterial Landscaping easement (18' total) at the west property boundary, along Muldoon Road.

Muldoon Estates Subdivision Tract B
Area: 1.720 Acres
Zoning: R2-M

Easement: 10' T&E easement along south property line.

Muldoon Estates Subdivision Tract C
Area: 7.398 Acres
Zoning: R2-M

Easements: 10' T&E easement at east and north property lines. 15' Trail easement (DTP) borders the south and west property lines.

Muldoon Estates Subdivision Lot 3
Area: 11.47 Acres
Zoning: R2-M

Easements: 10' T&E easement at west, north, and property lines. 25' Stream Maintenance & Protection Easement. 33' Section Line easement at east property line.

* The area notations for Tract D on Plat 2014-30 includes an area calculation discrepancy; 159,407 square feet as noted in the plat is consistent with survey and equals 3.659 acres, not 3.359 acres as described on the plat.


OWNERSHIP

All parcels are owned by the Municipality of Anchorage Parks & Recreation Department.

Total Park Area: 26.74 Acres

Boundaries:

- » North: East Debarr Road Right-of-Way
- » East: Joint Base Elmendorf-Richardson
- » South: Private Residences, Early View Drive Right-of-Way, Tract F, East 14th Avenue Right-of-Way, Windsong Park
- » West: Muldoon Road, Private Commercial



TOPOGRAPHY

Muldoon Town Square Park lies at the base of the Chugach foothills along the South Fork of Chester Creek. The topography of the park is relatively flat with subtle changes in elevation resulting primarily from the deposition of fill from development in the surrounding areas. Within the 26.74 acres encompassing the park, there is approximately 67 feet of vertical change as elevations generally slope from east to west and north to south consistent with the flow of water into Chester Creek.

The high point, at 308 feet elevation is located near the eastern edge of the park in an open space and former fill site. The low point is located at the base



of the recently constructed Chester Creek box culvert at Muldoon Road, and is approximately 241 feet in elevation (GAAB 72 Vertical Datum, Anchorage Bowl).

A notable high point (elevation 282 feet) is observed at the inside bend of the Chester Creek oxbow, atop a forested hill south of Arnold Muldoon's original homestead site. The hill rises 20 to 30 feet above surrounding areas with moderate to steep forested slopes.

Also notable are the steep slopes found along the streambank of Chester Creek. East of the oxbow, the topography rises to a prominent bluff 15-20 feet above the creek

and beaver pond directly north of Windsong Park. While limiting direct access to Windsong Park, the bluff provides numerous vantage points of the Chugach Mountains.

Along the park's northern boundary, the park sits slightly higher in elevation than the existing Debarr Road right-of-way and gradually rises in elevation (up to 10-15 feet) east of Boston Street to the JBER boundary.



Anchorage Area, Alaska (A000)			
Map Unit Symbol	Map Unit Name	Area in A00	Percent of A00
406	Cryptanthus and Urban land, 0 to 5 percent slopes	117.8	54.7%
407	Cryptanthus and Urban land, 5 to 20 percent slopes	51.9	24.1%
411	Deciduous-Estimate-Kichikina slopes, 12 to 20 percent slopes	7.8	3.6%
414	Deciduous-Estimate-Kichikina complex, undulating and hilly	3.4	1.6%
417	Deciduous forest, 0 to 7 percent slopes	28.9	13.4%
428	Kichikina-Kichikina complex, 0 to 3 percent slopes	5.5	2.5%
Totals for Area of Interest		215.2	100.0%

Custom Soil Resource Report Retrieved from:
 USDA Natural Resources Conservation Service
<http://websoilsurvey.nrcs.usda.gov>


SOILS

Preliminary soil and geotechnical investigations for Muldoon Town Square Park reveal a wide range of subsurface conditions across the site. These present day conditions are primarily the result of two factors: the site's pre-development condition as a natural wetland and the deposition of unusable fill material from surrounding development.

Information presented in a Shannon & Wilson Preliminary Geotechnical Report (2000) for the Muldoon Middle School (now Begich Middle School) includes bore hole locations and information from site studies performed in 1996, 1998, and 2000. The information is further summarized in a Design Study Memorandum prepared by HDR Alaska, Inc (2008).

Data presented in the Preliminary Geotechnical Report describes significant areas of organic fill south of Boston Street east to the property line abutting JBER. Fill depths range from 2 feet to more than 20 feet. Boring records indicate that the fill layer generally rests atop organic and peat materials ranging in depth from 3 feet to 15.5 feet. Combined, the total depth of organics (organic fill on top of organic subgrade) ranges from 8 feet to more than 30 feet.

An analysis of historical aerial imagery indicates that significant quantities and depths of fill located on the eastern half of the Muldoon Town Square Park site can be attributed to development between 1970 and 2002. Aerial imagery indicates a dramatic increase of clearing and fill operations occurring from 1980 to 1990.



The presence and depth of the organic layers requires additional considerations when developing structural foundations for permanent facilities (Shannon & Wilson, Inc., 2000). No records exist describing what material, or mix of materials, were deposited on site. Additional explorations are encouraged to understand the potential for encountering inorganic debris, contaminants, or organic material in varying states of decay before construction of park improvements as discovery of material that requires additional testing or treatment may have significant impact on a project's scope and budget. Considerations may include the additional cost of removing organic material from the site (excavation) and/or using pile construction foundations.

The Alaska Department of Environmental Conservation (ADEC) lists Muldoon Estates Tract A as being issued a Cleanup Complete Determination from its Contaminated Site Program dated October 13, 2014 (ADEC File No. 2100.57.016, Hazard ID No. 25859). It was determined by ADEC that with the information available there is no risk to human health or the environment from contamination. ADEC identifies in the Cleanup Complete Determination that off-site soil disposal shall be in accordance with 18 AAC 75.325(i), with any movement or use of contaminated soils that results in a violation being punishable by law. Specific information regarding samples and contaminants can be found on the Alaska Department of Environmental Conservation, Division of Spill Prevention and Response Contaminated Sites Program webpage (<http://dec.alaska.gov/Applications/SPAR/PublicMVC/CSP/SiteReport/25859>).

SOURCES

HDR Alaska, Inc. (August 2008). Chester Creek at Muldoon Road Channel Restoration Design Study Memorandum (Final, 8-5-2008). Anchorage: Municipality of Anchorage.

Shannon & Wilson, Inc. (October 2000). Preliminary Geotechnical Report, Muldoon Middle School, Alaska Greenhouse Site, Anchorage Alaska. Anchorage: Shannon & Wilson.



CHESTER CREEK

The South Fork of Chester Creek is an Anadromous Stream that flows through Muldoon Town Square Park. The stream flows east to west, across JBER property at the base of the Chugach foothills through the park and continuing under Muldoon Road through a recently completed open-bottom box culvert.

At the park's eastern boundary, Chester Creek transitions from the Upper South Fork of Chester Creek to the Lower South Fork of Chester Creek Sub-Watershed (page 16, Anchorage Waterways Council, 2014). The creek arches slightly north into park property and flows west for approximately 1,800 ft. before making a sharp bend north. The stream bends west for a short distance before continuing south along the newly realigned and reconstructed channel creating the large 'oxbow' that surrounds the existing forested hill. As the creek flows south towards East 14th Avenue R.O.W. it bends west, continuing on towards Muldoon Road.


In 2015, the South Fork of Chester Creek was re-aligned to improve water quality and fish passage. The Muldoon Realignment and Channel Improvements Project was completed fall of 2015, reconstructing a portion of the stream stretching south from East Debarr right-of-way to connect with the existing channel of Chester Creek west of Muldoon Road. Historic aerial imagery indicates past changes to the alignment of Chester Creek due to residential neighborhood development to the south of the park. Channelization and straightening of the creek along the south edge of the parcel are visible from aerial imagery taken in 1970 and 1980. Water quality and stream capacity were addressed with the development of a sedimentation basin at Windsong Park sometime between 1990 and 2002.

The stream was observed to be clear and free flowing during site observations in August, September, and October of 2015, including spawning salmon in the upstream sections near Windsong Park. Moderate amounts of litter such as plastic bags, cans and other debris were observed in and around the stream in areas near informal paths and crossings. Regardless, the Alaska Department of Environmental Conservation (ADEC) does not list the Upper or Lower South Fork of Chester Creek as an impaired water or area.

Specific analyses and records of water quality data collected from 1998-2001 can be found in the National Water-Quality Assessment Program, Scientific Investigations Report 2006-5229 (Water-Quality Conditions of Chester Creek, Anchorage, Alaska, 1998-2001). <http://pubs.usgs.gov/sir/2006/5229/pdf/SIR2006-5229.pdf>

SOURCE

Anchorage Waterways Council, Municipality of Anchorage, Municipal Planning Department and Watershed Management Services. (2014). Chester Creek Watershed Plan (Draft, Revision 5, November 7, 2014). Anchorage: Municipality of Anchorage. <http://anchoragewatershed.com/ChesterCrkWatershedPlan.pdf>



Chester Creek Watershed Plan
Figure 3.4 Chester Creek Subwatersheds

WATERSHED AND DRAINAGE BASINS

Drainage basins and subbasins are important to consider when developing stormwater infrastructure on sites that connect to high-value streams such as Chester Creek. Watershed drainage subbasins identify localized conditions to ensure proper treatment of stormwater and runoff prior to connecting to stream corridors or waterbodies with outlets or outfalls.

The Muldoon Town Square Park site is located in the upper sections of the Chester Creek Watershed, and includes areas within five (5) drainage subbasins of the Upper South Fork of Chester Creek as defined by maps made available by Anchorage Watershed Management Services (Municipality of Anchorage, 2016). Only four subbasins are assigned an identification number (ID No.) and documented with publicly available data. The fifth subbasin is shown on maps generally upstream of the site on JBER property and encompasses wetland areas.

The majority of the park site is located within a 20.32 acre subbasin with an outlet at Chester Creek south of the East Debarr Road and Boston Street intersection (ID No. 550). Southeast portions of the site are located within a much larger 493.71 acre subbasin with a major outlet located where the Windsong Park sedimentation basin flows north into Chester Creek (ID No. 598). A small triangle of park land is located in a 10.84 acre subbasin with an outfall located west of Windsong Park where Chester Creek makes a sharp bend north (ID No. 559). The

SOURCES

Anchorage Waterways Council. Municipality of Anchorage. Municipal Planning Department and Watershed Management Services. (2014). Chester Creek Watershed Plan (Draft, Revision 5, November 7, 2014). Anchorage: Municipality of Anchorage. <http://anchoragewatershed.com/ChesterCk/WatershedPlan.pdf>

Municipality of Anchorage. Watershed Management Services. (2016). Anchorage [WMS Drainage Map]. Retrieved from <http://moapw.maps.arcgis.com>


PROJECT AREA

remaining subbasin includes portions of the park west of the hill and bordering Muldoon Road (ID No. 496, 31.46 acres).

Limited stormwater infrastructure exists within the park. A storm pipe is located within an existing easement and drains two structures located in Carolyn Circle ROW into Chester Creek (pipe ID No. 519-1-1). The only other stormwater structure located on site is a catch basin that connects to a catch basin manhole located within Muldoon Road ROW (ID No. 31,441,048) (Municipality of Anchorage, 2016). No other stormwater infrastructure is recorded or observed to be within the park property.

SOURCE

Municipality of Anchorage. Planning Division. Department of Community Development. (July 2014). *Anchorage Wetland Management Plan* (AO2013-132S). Anchorage: Municipality of Anchorage.



WETLANDS

Municipal mapped wetlands occupy low areas adjacent to the South Fork of Chester Creek, east of the beaver dam along the south, southeast and east boundaries of the site. The existing wetlands at the south and east edges of the site were observed to provide bird and beaver habitat.



Muldoon Town Square Park includes approximately 2.5 acres of a 3.31 acre Class "A" Wetland, defined by the Anchorage Wetlands Management Plan as Wetland Site Number 9 (page 113, Municipality of Anchorage [MOA], 2014), characterized as "Muldoon Estates Subdivision, North of Turf Ct." The *Anchorage Wetlands Management Plan* recognizes the wetland as valuable for flood attenuation, water quality and habitat; identifies a storm drain detention system (adjacent sedimentation basin); and describes a 65 foot stream setback encompassing the remaining wetlands, which warrants Class "A" designation (page 44, MOA, 2014).

Class "A" Wetlands have the highest wetland resource values and perform at least two, often more, significant wetland functions. Wetlands are considered most valuable in an undisturbed state. Any activity that includes placement of fill in Class "A" wetlands requires an Individual Section 404 Permit from the Army Corps of Engineers prior to development (page 26, MOA, 2014). Informal or soft-surface trails may travel parallel to the stream outside the protection setback, or a 15 foot minimum measured from the centerline of the stream.



SOURCE

U.S. Department of Homeland Security.
Federal Emergency Management Agency
[FEMA]. National Flood Insurance Program.
Number 020005 Panel 0778D [Map].
Revised September 25, 2009. 1"=500'.
Flood Insurance Rate Map [FIRM].
Anchorage: U.S. Department of Homeland
Security. Effective 9/25/2009.



Flood Insurance Rate Map (FIRM) Mapped Floodplain

FLOODPLAIN

Floodplain mapping identifies areas in the south and east portion of the park as occupying both the 500-year Floodplain (Zone X, 0.2% Annual Chance Flood Hazard), and 100-year Floodplain (Zone AE, 1.0% Annual Chance Flood). The entirety of the Chester Creek channel is located within a mapped floodway. It is important to note that the stream improvements completed as part of the Realignment of Chester Creek at Muldoon Road Project are not reflected in the FIRM Panel dated September 25, 2009.

Stream section "DR" located immediately to the west of Muldoon Road identifies a base flood elevation (BFE) of 245.8 Feet. A BFE of 256 Feet is located near the tie-in location for the Chester Creek Realignment project. For reference, a BFE of 280 Feet is located just south of the park, east of Early View Drive, indicating an approximate 34.2 foot vertical difference in base flood elevations across the 26.74 acre site.


Municipality of Anchorage Watershed Management should be consulted prior to design and engineering for any improvements near or impacting the mapped Chester Creek Floodway or Floodplain. Additionally, Chester Creek requires a 25 foot stream protection setback per Anchorage Municipal Code (AMC 21.45.210) limiting the types and levels of development that can occur near the waterway.



EXISTING VEGETATION

A review of historic aerial imagery shows a significant portion of the existing site is occupied by pioneer and successional forest. Today, existing vegetation is largely a mix of mature evergreen and deciduous trees with dense understory. Forested areas are interspersed with clearings, transitional areas consisting of devil's club and cow parsnip, and open, grassy meadows. Trees include birch and spruce, with the predominant species consisting of alder and cottonwood in fill areas, on slopes, and in wet areas. Understory growth is a mix of woody shrubs and perennials including: willow, devil's club, raspberry, fireweed, yarrow, and various grasses.


The west portion of the property includes recently installed landscape and revegetation plantings associated with the Chester Creek Realignment Project, including immature birch, spruce, alder, willow, aspen, and native shrubs, such as common prickly rose and highbush cranberry.




Observations during site visits identified *Prunus padus* (Mayday, Bird Cherry) saplings, an invasive species, along the oxbow's east segment. It is expected that populations of *Prunus padus* exist along the stream in other areas of the park, more easily identified during leaf-out and full bloom.

WILDLIFE

Muldoon Town Square Park provides important green space for local residents and wildlife in a rapidly urbanizing area of Anchorage. Site visits included abundant sightings of birds, including geese and ducks within the stream corridor and various species of birds in the wetland areas north of Windsong Park. Depressed grass and piles of scat show evidence of recent moose activity in the area. A deconstructed beaver lodge was observed at the northwest corner of Windsong Park. Numerous Park Advisory Committee members described the recurrence of beaver dams in the area, causing localized flooding and impacting nearby residents. Bear scat was found along informal trails within the site. Spawning salmon were observed in both the newly realigned section of stream as well as in upper reaches in protected areas created by the deconstructed beaver dam.





Existing Site Access and Circulation Diagram

ACCESS

Access into Muldoon Town Square Park is currently limited to pedestrian foot traffic. There are unimproved gravel driveways on East Debarr Road at Boston Street and a driveway curb cut on Muldoon Road. A gravel-paved single lane drive at East 14th Avenue (south of the creek) served as construction access for the Chester Creek Realignment Project.

Vehicle access into the park from a Debarr Road extension was evaluated during this planning process and was deemed unlikely to be developed in the near term. Conversations with MOA Traffic and AKDOT indicated that, at present, agencies do not have plans to extend Debarr Road to Boston Street, as there is not a projected need

for the road segment. They also indicated that the addition of a fourth segment to the Muldoon-Debarr Road intersection would be expensive and have negative impacts to current traffic patterns along Muldoon Road which currently exceed 30,000 trips (ADT).

A narrow segment of Tract A extends along the East Debarr Road R.O.W. providing pedestrian access to the controlled intersection at Muldoon Road and Debarr Road.


The existing hill area can also be accessed from East 14th Avenue via an existing single lane dirt drive. The existing dedicated right-of-way for East 14th Avenue is 30 feet. An additional 25 feet of right-of-

way is to be dedicated as a condition of approval for development of the two parcels currently for sale immediately south of East 14th Avenue, which would bring the dedicated right of way to a total of 55 feet.


Early View Drive right-of-way terminates at the southeast corner of Muldoon Town Square Park, providing for a connection to the neighborhood to the south. Windsong Park and a dedicated 10' easement connect to Carolyn Circle, providing potential pedestrian access along the south boundary.



Existing informal footpath



Existing East Debarr ROW at Cross Pointe Loop looking east



Soft-surface trail along Chester Creek

CIRCULATION

While no formal or developed trails exist on site, the park is home to many informal footpaths. Existing routes help to identify what areas and destinations are most desired, such as viewpoints. Informal footpaths traversing the site also identify park areas that are problematic by leading to hidden gathering places for undesirable activities such as alcohol and drug use, and unauthorized camping.

A single-lane compacted earth vehicle drive serves as a main pedestrian trail corridor extending south from Boston Street through the site to the large open space area at the east end. Local community members have cleared and maintained an informal loop-trail connection that links the former service drive to the south bluff with views overlooking Windsong Park and adjacent wetlands. Existing informal paths provide an intimate nature experience, but do not meet the 2010 ADA Standards for Accessible Design.

A recently developed soft-surface trail weaves along Chester Creek at the western end of the park, constructed as part of the Chester Creek Realignment Project. The path is shallow gravel topped with wood chips and connects the Park with the Muldoon Mall to the north.

Off-trail foot traffic leaves the new soft surface trail in areas along the creek, compacting streambank soils and inhibiting vegetative growth, and likely creating long-term erosion issues. A foot path was observed descending from The Hill area and across a log set in the creek as a convenient access to the north, disrupting revegetation efforts along the creek and in upland areas.

UTILITIES

At present, there are no developed utilities located on site. However, electric, telephone, water, stormwater, and fiber optic cable lines run along East Debarr Road directly north of the park. Street lights are located on the south side of East Debarr Road from Boston Street to Cross Pointe Loop. A natural gas main line and high-pressure gravity water main run parallel to the east property line, offset approximately 40 feet. Utilities available at Muldoon Road include electric, stormwater, sanitary sewer and natural gas. Water and sewer are available south of the site along East 14th Avenue right-of-way.

SITE CONSIDERATIONS

ACCESS

Muldoon Road

Muldoon Road is a Class III Arterial that abuts the site at the west property line and offers direct access to the Park.

Alaska DOT&PF strongly recommends providing maximum distance from the Debarr-Muldoon intersection to the north for safety, queuing, and improved access to and from the park. Currently, a dedicated left-turn lane extends north to the Debarr Road intersection. Based on current configurations a drive located south of the turn lane would allow for southbound traffic to enter the park across Muldoon Road during off-peak traffic hours. Anticipated growth in traffic volume along Muldoon Road due to increased development in the area may require extension of the turn lane or installation of separation median for safety, eliminating southbound access to the park from Muldoon Road. Visitors arriving by vehicle would enter the park via right-in, right out access and egress.

East Debarr Road

Impacts to local neighborhoods should be considered when determining vehicle access into the park. Driveways and access points into the park along East Debarr Road east of Boston Street should be aligned with existing intersections to minimize the impacts of traffic on the local neighborhood and to support vehicle and pedestrian safety.

Pedestrian Connections

The Muldoon Perimeter Trail connecting Centennial Park with Scenic Foothills and points south along the JBER boundary was identified in the East Anchorage District Plan. While no specific priority or design has been identified by the Municipality at this time, accommodations should be made to support access and connections between the park and a future trail.

At present, the park is absent of wayfinding, signage, and formally developed access points. This creates confusion and is disorienting to visitors unfamiliar with the park. The absence of formal trails also means that there are no ADA accessible routes for visitors with mobility challenges or other disabilities. Throughout the planning process, residents indicated that improved access to the park from the neighborhoods south of Chester Creek was desirable.





RIGHT OF WAY (ROW)

Chester Creek occupies a short section of the vacant East Debarr Road ROW north and east of the recently completed realignment project. The presence of the creek is expected to make permitting any potential future extension of Debarr Road challenging and subject to Army Corps of Engineers, Alaska Department of Fish and Game, and MOA Watershed permit processes and review. Additionally, it was suggested at the agency coordination meeting that cost-prohibitive upgrades to the existing major intersection, challenging topography, and adequate level of service of existing neighborhood roads may ultimately eliminate the need for a Debarr Road Extension. In the event that MOA Traffic and ROW designate the Debarr Extension as not serving a public need, there may be options to incorporate the Municipality-owned Right-of-Way as additional Muldoon Town Square Park property.

Right-of-way was dedicated for a short segment of East 14th Avenue as a result of a 2014 replat of park parcels (Anchorage Recording District Plat No. 2014-30). The same plat identifies a future dedication of 25 feet for right-of-way immediately south of the dedicated portion for a total of 55 feet. The additional 25 feet is anticipated to be dedicated upon development of one or both of the two parcels in question (MacLaren Subdivision, Block 1, Lots 1 and 2).

East Debarr Road includes undeveloped right-of-way east of Cross Pointe Loop. There are no plans to develop the existing right-of-way. There is no stated support or objection to providing park access or parking in this section of unused right-of-way, currently a single-lane gravel paved service drive accessing utilities at the JBER property line.

Prominent Muldoon Presence

The community desires a prominent and welcoming "face" to the Park at Muldoon Road. Visible features and spaces characterized by Park Advisory Committee members and Public Workshop participants as "iconic", "identifiable", and "unique" should be considered to serve as community reference points year-round. Numerous strategies for establishing prominence were discussed and included: development of public art, architectural pavilions, unique landscapes and features, and active uses located within view of Muldoon Road.



PARKING

Vehicle parking for park visitors was a significant issue identified through the public process. There is a strong desire within the community to minimize the impacts of traffic in adjacent neighborhoods and to limit parking on-site in an effort to retain natural areas, open space and recreational opportunities. Concerns were also shared that the burden of parking should not be the responsibility of the adjacent neighborhoods. Specific issues raised in many of the discussions included two recurring topics; 1) where to locate parking on-site, and 2) how many spaces are needed to balance requirements for daily use and during the peak hours during community events.

On-street parallel parking exists on Boston Street, north of East Debarr Road. Development of additional on-street parking should be considered with improvements to undeveloped right-of-way at East 14th Avenue and east of Cross Pointe Loop in East Debarr Road right-of-way. On street parking would minimize the need for parking within the park. Preliminary discussions with Municipality of Anchorage (MOA) Traffic Department indicated that on-street parking in undeveloped right-of-way may warrant additional exploration, as both locations identified in the Master Plan are dead-end with no current driveways or access served. Parking is subject to MOA Traffic and Right-of-Way approvals and would be required to meet dimensional standards and provide clearance for maintenance, service and emergency access.



"I RECOGNIZE ADEQUATE

PARKING IS A HUGE

CONCERN, BUT PLEASE KEEP

THE FRONT OF THE PARK

FREE OF STRUCTURES AND

PARKING LOTS THAT BLOCK

VIEWS OF GREEN SPACE."





PARK AS A RESOURCE

The community voiced a desire for a park that balances new development with the preservation of existing natural areas. Residents whom remember the as a greenhouse and nursery operation noted a desire to return portions of the park to uses consistent with botanical and horticultural links, such as an arboretum or a community orchard. Workshop attendees and Park Advisory Committee members identified a limited supply of community garden space, with broader issues related to food security and availability within the community. Input included considerations for programming and management of community garden spaces; what they look like, what infrastructure and amenities are required, and how they interact with adjacent uses.

PUBLIC SAFETY

Throughout the planning process, “safety” was consistently identified as one of the main concerns among members of the community. Of the 221 survey participants who answered the question “What is your biggest concern when visiting a park?” - 67% of respondents indicated that they were “very concerned” about safety. Of the issues and concerns raised, most comments focused on safety as it relates to homeless camps and the presence of illicit activity.

In fall of 2015, five unauthorized encampments were observed in the center and eastern portions of the park. These camps were located in areas with limited lines of sight and often included illegal campfires, tents, and trash. Visibility into and through the existing site is a major concern of the Park Advisory Committee and the Parks and Recreation Department. Many areas of the park are dense with pioneer forest and understory vegetation that obstructs vision and sound and eliminates the ability to anticipate user and wildlife conflicts. Providing visibility in the park is important to improve safety by recognizing and responding to negative behavior or potential wildlife conflicts. Additionally, lighting should be considered along main trails and in areas of developed facilities to provide for a safe park experience.

The park’s abundant greenspace and proximity to largely undeveloped JBER land also allows for human-wildlife interactions. While some interaction with wildlife can make for an enriching experience, interactions with moose and bear can be dangerous. Food sources found in Chester Creek or affiliated with illegal camps are particularly attractive to wildlife and pose a greater potential for conflict.

OPPORTUNITIES AND CONSTRAINTS

CELEBRATE HISTORY AS DESTINATION

The Muldoon Town Square Park provides an opportunity to connect users with a unique destination that celebrates the site's history. The Hill area, now contained within the realigned oxbow area of Chester Creek, the location of a hand-built log cabin Arnold Muldoon constructed as his homestead. No remnants of the cabin physically exist today, but the presence of his homestead and the legacy he left behind may inspire features or elements of the park.

Throughout the planning process, individuals recounted their experiences visiting the Alaska Greenhouses once owned and operated by Mann Leiser. Residents grew up visiting the Alaska Greenhouses year-round, as it served as a plant nursery and eclectic destination for community events and seasonal celebrations. The public described the warmth of the greenhouses, of paths winding along Chester Creek, and beautiful vegetation and arrangements that provided memories lasting a lifetime.


The Park also provides an opportunity to connect the Dena'ina Athabascan culture to the site. Specific suggestions included creation of art and interpretive features, providing celebration spaces, and designation of the Park as a strategic node located halfway between the Alaska Native Heritage Center and the Alaska Native Medical Center campus.



Arnold Muldoon's homestead cabin was located on the Park site. Photo Credit: Bruce Novinska



School Children visit Alaska Greenhouses which was located on the Park site. Photo Credit: Anchorage Garden Club records, Archives and Special Collections, Consortium Library, University of Alaska Anchorage.




Calendar cover image published by the Alaska Greenhouses, Inc. (1990)




CELEBRATE CHESTER CREEK

Chester Creek plays a prominent role in the Park, with opportunities for visitors to engage and celebrate its presence. There is a strong desire to provide creek access in the realigned section of stream to serve as a public interface, similar to Campbell Park. Access to the creek may include spaces for observation, interpretive education, and play. A visible, accessible route should be considered to limit habitat destruction and impacts to streambanks by accommodating desired and anticipated activities. The realigned stream near Muldoon Road includes a wider basin for improved flood management and more gentle slopes that provide convenient access to the stream.



Pedestrian bridges over Chester Creek should connect the park, improve access, and increase activity. Bridges should consider unobtrusive fall protection barriers that allow trail users to see the creek from directly above. Informal, soft surface trails are permitted to be constructed within the 25' streambank protection setback, but at a minimum distance of 10' from the centerline. Trails along the stream are strongly desired to create an intimate nature experience. Implementation of trails should consider impacts to sensitive streambank habitat and segments of creek susceptible to long-term damage from users tempted to veer off-trail.

Chester Creek is a natural asset with salmon present during site observations. Opportunities to inform park users about the significance of Chester Creek (“Chanshtnu”) as a food source and the importance of fish habitat protection should be complimented with regulatory information clearly defining this section of stream closed to fishing, punishable by law. Interpretive signage may include themes regarding impacts of area development on water quality, the relationship of the site to the Chester Creek watershed, or the aquatic ecosystem restoration efforts on site in support of education and outreach goals set in the Chester Creek Watershed Plan.



SIZE AND ORIENTATION OF PARK

The size of the park allows for numerous highly desired community uses to fit in a single public space with convenient access and circulation. The long, rectangular shape of the park permits residents from the north and south to view and observe park activities from adjacent roadways, parks and yards. The length of the park also allows for incremental development of activities along multi-use paths and loops to encourage exercise and healthy lifestyles. Buffer spaces within the park should be considered to separate and transition between activities and uses without compromising connectivity. The east-west orientation of the park, elevated topography, and adjacency to existing low-rise residential development offers southern exposure and solar access to create year-round enjoyable outdoor experiences in one of Anchorage's colder microclimates.

04

MASTER PLAN



MASTER PLAN



The Muldoon Town Square Park Master Plan provides a 20-year vision for the development of the park. The plan is the product of extensive public engagement and collaboration with the Park Advisory Committee, Parks & Recreation Department, area middle and high school students, and a small team of planning and design Consultants. The Master Plan embodies the community's vision to provide active and healthy recreational opportunities to the residents of Muldoon and East Anchorage.

VALUES

The recommendations provided in this plan are based on the following community values, observations and identified needs:

- » Develop Muldoon Town Square Park as a community destination in East Anchorage for all ages and abilities.
- » Provide safe access and connections to the park, and within the park.
- » Encourage year-round community and neighborhood use by developing flexible use areas that accommodate large organized events and promote daily use.
- » Celebrate the unique natural features of the park including; the South Fork of Chester Creek, remnant native birch/spruce forest, and spectacular views of the Chugach Mountains.
- » Improve food security and public health by offering community garden space and integrating edible landscapes into park improvements.
- » Activate the park by developing year-round recreational and social opportunities for a variety of different interests, user groups, ages, abilities, and skill levels.
- » Ensure user safety by improving visibility, incorporating lighting, and activating spaces.
- » Maintain the natural characteristics of the park to serve as areas of respite, inspiration, reflection, and connection.
- » Manage the park as important habitat with a variety of ecosystems that support native flora and fauna.
- » Celebrate local cultures, communities, and diversity with public and performance art.
- » Implement green infrastructure as best management practices to improve water quality, encourage biodiversity, and limit off-site impacts.
- » Coordinate investment in infrastructure and facilities to maximize available resources.
- » Engage local, state, and federal partners to fund park improvements and advance the community vision.

VISION



MULDOON TOWN SQUARE PARK IS A GATHERING PLACE AND DESTINATION FOR EAST ANCHORAGE AND THE GREATER COMMUNITY WHERE FAMILIES AND PEOPLE OF ALL AGES AND ABILITIES CAN ACCESS AND PARTICIPATE IN HEALTHY PARK ACTIVITIES IN A SAFE, CLEAN, COMFORTABLE ENVIRONMENT IN A UNIQUE AND BEAUTIFUL NATURAL SETTING.




PREFERRED ALTERNATIVE

MULDOON TOWN SQUARE PARK IS
COMPRISED OF THREE DISTINCT USE AREAS
DEFINED BY THE KEY CHARACTERISTICS
WITHIN, OR ADJACENT TO THE PARK.



From west to east, the park transitions from a high-use, community destination fronting a major arterial road (Muldoon Area) to a contemplative, natural landscape suitable for both active (Core Area) and passive (Chugach Area) recreation. Within the park, a network of trails will connect use areas. As envisioned, the park will provide a safe and healthy place to connect with nature, recreate with friends and family, and gather as a community.



OUTDOOR RECREATION AND REFLECTION

NATURE AND WILDERNESS EXPERIENCE

RESTRICTED AREA

SPECTACULAR VIEWS



MULDOON AREA

The Muldoon Area provides a welcoming, year-round destination in the highly visible western portion of the park along Muldoon Road. The area is intended to be the most active space in the park; hosting community-wide events and providing a range of facilities that will serve the diverse needs of the community. The Muldoon Area will also serve as an inviting gateway that encourages visitors to explore further into the park with trails and bridges over Chester Creek that extend throughout the park, rewarding visitors with outstanding views of the Chugach Mountains.

The Muldoon Area will include developed access to Chester Creek, a destination inclusive playground, a parking lot with 40 spaces, community event space that can support the Muldoon Farmers Market and Spirit of Muldoon Picnic, flexible open space, a pavilion, restrooms, and a ribbon that can be used for ice skating in the winter and community events/kiddie bike loop in the summer.





CREEK ACCESS

The realigned segment of Chester Creek offers a unique opportunity to celebrate the presence and importance of one of Anchorage's prized waterways. With the development of facilities in the Muldoon Area of the park, it will be important to manage access to Chester Creek to minimize the potential negative impacts of widespread use. The Master Plan proposes improvements to the existing soft-surface trail along with the development of a designated access point to create an attractive and safe location for park users to enjoy the creek and to minimize stream bank erosion.

- » Minimize the impacts to stream bank habitat by providing a formal path and a designated access point to the creek
- » Develop interpretive information that educates the public about Chester Creek, the watershed, and riparian ecosystems within the park
- » Monitor and manage public use of the creek to minimize potential negative impacts to the stream bank or fish habitat
- » Work with agency and organizational partners to ensure the long-term health of Chester Creek



EVENT SPACE

Throughout the planning process, the public voiced a strong desire for a visible space suitable for hosting large community events such as the Spirit of Muldoon Picnic and the Muldoon Farmers Market. The Master Plan recommends development of a flexible community event space that can support a variety of popular community wide events while providing valuable open space for daily use.

- » Develop a large, open event space that includes a mix of durable, accessible surfaces to facilitate vehicle travel, setup of temporary shelters or stalls, as well as heavy pedestrian traffic during community-wide events
- » Integrate the event space with other park improvements to support daily use of the Park, such as; activity spaces, green spaces, and picnic areas
- » Provide controlled vehicle access to the event space with a gated drive from the parking area
- » Install lighting and power infrastructure to support events and year-round use



FLEX AREA

Located within the oxbow of the newly realigned Chester Creek, the flex area provides a mix of hardscapes, open space and sloped lawn to support a range of activities from picnicking to small performances. The flex area also links the Muldoon and Core Areas of the park via two pedestrian bridges and provides additional space to support larger community events.

- » Provide a space that supports temporary shelters or stage structures for community events
- » Develop a mix of hardscapes, open space and lawn to support a range of activities
- » Reshape the north slope of the Hill into a maintained, sloped lawn
- » Visually integrate the Flex Space with adjacent multi-use paths and green spaces
- » Provide a gated vehicle drive that connects to East 14th Avenue for service and emergency access
- » Provide clear lines of sight and lighting to discourage negative activity and ensure user safety



THE HILL

Visible from Muldoon Road, the hill provides a distinctive backdrop to the western area of the park. Mature stands of birch and spruce combined with subtle changes in topography create a valued natural area and unique vantage point within the park. The master plan recognizes these qualities and recommends that the hill be managed and maintained to preserve those natural qualities and characteristics most valued by the community.


- » Manage existing forest health through the removal non-native species
- » Provide clear lines of sight to deter negative activities through the selective thinning of trees and brush
- » Prevent damage to existing trees during regular maintenance operations by visually defining the edge of forest from maintained areas
- » Provide tree protection during construction and maintenance activities to ensure long-term viability of the existing native forest
- » Develop interpretive information that educates the public about the site history and native forest ecosystems



PAVILION

An iconic community-use pavilion is a highly desired feature intended to support daily park use, community-wide events, and further define the park as a welcoming destination. The Master Plan recommends that a pavilion structure be centrally located near the playground, parking lot, restrooms, ribbon and event space. As envisioned, the pavilion will serve as a visible reference point for East Anchorage residents traveling along Muldoon and Debarr Roads.

- » Construct a pavilion structure, preferably with unique architectural features, visible from Muldoon Road that facilitates year-round use by individuals, groups, and community organizations
- » Discourage negative activity and ensure user safety by providing clear lines of sight from adjacent roadways and use areas
- » Provide lighting and access to electrical outlets to support community events
- » Provide amenities such as picnic tables, benches, and trash cans to support public use



The Hill

Remnants of native paper birch and white spruce forest exist on “The Hill,” the elevated area generally contained within Tract B and surrounded on the east, north and south by Chester Creek. The elevation and stand of forest are clearly visible from Muldoon Road and were identified by Park Advisory Committee members as an important existing asset that should be retained to visually reinforce the function of the park as a natural space. Preservation of the forest is strongly desired to ensure its long-term presence while improving tree health and visibility into, and within, the forest area for safety.



Shared Use Parking Agreements

Muldoon Town Square Park is located adjacent to commercial properties with community service organizations, restaurants and commercial uses. Shared Use Parking Agreements can be mutually beneficial by supporting businesses and institutions adjacent to the Park, maximizing use of existing parking during off-peak hours, and preserving green space within the Park.

The Muldoon Mall parking lot north of the Park has approximately 250 parking spaces with peak demand Monday through Friday. The property was identified as a potential opportunity for supplementing on-site parking with a Shared-Use Parking Agreement.

Shared Use Parking Agreements are contingent upon negotiations with adjacent property owners and subject to approval by MOA Traffic Department.

PARKING

Muldoon Road will serve as the primary access point for the Muldoon Area of the park. The Master Plan recommends a combination of three strategies to accommodate vehicle parking:

- 1) Develop Off-Street Parking in the Park;
- 2) Develop On-Street Parking on East 14th Avenue; and
- 3) Develop Shared Use Parking Agreements. The Park Advisory Committee and public identified shared use parking as a high priority and an opportunity to advance the Muldoon Town Center vision.

Strategy 1: Develop Off-Street Parking in the Park

- » Construct a parking lot that accommodates up to 40 vehicles north of Chester Creek
- » Locate a single vehicle access drive on Muldoon Road at a maximum distance from the Debarr Road intersection
- » Provide lighting and clear lines of sight from adjacent roadways to deter negative activity
- » Minimize impacts to Chester Creek by directing stormwater away from the stream to Low Impact Development (LID) treatment areas

Strategy 2: Develop On-Street Parking on East 14th Avenue

- » Work with MOA Traffic and ROW to develop up to 25 on-street parking spaces on East 14th Avenue

Strategy 3: Develop Shared Use Parking Agreements

- » Supplement on-site parking with shared parking at adjacent commercial developments during off-peak business hours, on weekends, and during events
- » Initiate discussions with future developers of currently vacant parcels south of East 14th Avenue to consider Shared Use Parking Agreements
- » Develop accessible pedestrian connections to shared parking areas to encourage use and support adjacent commercial development



PLAY AREA

The Master Plan identifies a destination Play Area with highly visible features to attract year-round visitors. The Play Area should be accessible, inclusive, and incorporate unique features, configurations, or themes that celebrate the park and East Anchorage. The Play Area should also complement other facilities developed in the Muldoon Area, providing enriching park experiences for all.

- » Locate the Play Area in close proximity to complementary uses such as the Pavilion, Ribbon, and Event Space
- » Maintain clear lines of sight into and through the Play Area to minimize hiding spaces, discourage vandalism and allow for easy supervision and monitoring
- » Install perimeter controls, such as fencing and landscaping, to improve safety and child supervision, and to prevent conflicts with adjacent active uses
- » Work with partner organizations to identify, fund, and incorporate inclusive play features for all ages and abilities



RESTROOMS

Restroom facilities are important to support positive and healthy use of the park. The Master Plan recommends that restrooms be located adjacent to the Pavilion and near the parking lot for ease of maintenance and servicing.

- » Develop permanent restroom facilities or portable toilet facilities, if a permanent facility is not feasible
- » Install a decorative screen to house portable toilet facilities to maintain the visual aesthetic of the park
- » Incorporate area lighting and maintain clear lines of sight from adjacent roadways to discourage misuse and vandalism



Permanent Restroom Considerations


Permanent public restroom facilities are the preferred approach for Community Use Parks; however in recent years, decreasing budgets combined with the high cost of maintaining such facilities have prevented the Parks and Recreation Department from developing new and maintaining existing permanent restroom facilities. If public demand and future funding scenarios support the installation and maintenance of permanent restroom facilities, they should be developed on site.



Flat, Stable Development Location

The former parking area and greenhouse site at the west end of the park sits atop flat, stable soils with immediate access to Muldoon Road, making the west end of the park the most appropriate and cost-effective area for development.

Other areas of the park have significant organic and fill soils and varying topography, indicating that additional subgrade preparations or more costly foundation systems may be necessary to develop more intensive uses.



RIBBON

A key takeaway from the planning process is the importance of the park as a year-round destination. The Ribbon is envisioned to serve as a simple but extraordinary feature that captures the imagination of youth and invites all generations to participate in fun, healthy recreation. The Master Plan recommends the development of a year-round ribbon that can be used for ice skating in the winter, and community events and kiddie bike loop in the summer.

- » Construct a smooth, paved, continuous loop defined by a serpentine layout and sized to allow multiple uses to safely circulate, including: ice skating, junior cycling, running, and roller skiing
- » Manage and maintain ice for winter use
- » Integrate the Ribbon with the Event Space by providing accessible and durable surfaces that meet minimum vehicle maneuvering requirements to allow for expansion of large community-wide events
- » Locate the Ribbon in proximity to the Pavilion, Play Area, Event Space and parking as a complimentary use with shared access to amenities and infrastructure
- » Install lighting for safe winter use
- » Maintain site lines into and through the Ribbon to minimize user conflicts, promote child supervision, and discourage negative behavior
- » Partner with community organizations to program events and encourage active use of the Ribbon
- » Consider offering on-site equipment rentals for programmed activities



BIRD'S EYE VIEW OF MULDOON AREA LOOKING SOUTH



CORE AREA

The Core Area lies in the heart of Muldoon Town Square Park and includes a mix of developed facilities and natural areas intended for use by the larger community and neighborhood residents. The Core Area is served by a parking lot at the intersection of East DeBarr Road and Boston Street. Numerous paths link the Core Area to adjacent roads and neighborhoods as well as other areas within the park.

The Core Area will include a bicycle pump park, a boulder play area, a community garden, a community orchard, a fenced dog park, open recreation space, a parking lot and space for a park host, view points of the Chugach Mountains, a mix of hard and soft surface trails, and access to Windsong Park.





BICYCLE PUMP PARK

Communities thrive when youth and teens have opportunities to engage in meaningful outdoor recreation. Throughout the planning process, members of the community cited a growing demand for alternative sport facilities such as skateboard parks and bicycle pump parks. The Master Plan recommends development of a Bicycle Pump Park in the Core Area. The Bicycle Pump Park should be of good design and include a mix of features to accommodate beginners and challenge skilled riders.

- » Develop a small to medium sized bicycle pump park approximately 20,000-40,000 sq. ft. size (with future expansion possible depending on public demand)
- » Develop features for riders of all ages and abilities that allows for skills development and rider progression
- » Clearly define, manage, and enforce rules and regulations to ensure a clean, functional, and safe Bicycle Pump Park
- » Maintain site lines into and through the Bicycle Pump Park to allow passive monitoring and discourage undesirable activities



BOULDER PLAY AREA

Kids love to climb and today's boulder play equipment is highly sophisticated. Climbing features are visually aesthetic and can be customized to the preferences of a community. The Master Plan recommends a Boulder Play Area to provide active recreation for all ages and abilities, and to complement other programmed uses in the Core Area. The Boulder Play Area provides one of many options for individual and family recreation in the Core Area.

- » Develop a Boulder Play Area that includes a variety of challenging climbing features and/or structures
- » Locate the Boulder Play Area in a highly visible area, near other facilities for easy supervision
- » Design for and incorporate natural features to reinforce the wilderness and natural characteristics of the park
- » Maintain sight lines into and through the Boulder Play Area to minimize hiding spaces and discourage vandalism
- » Provide accessible fall surface to ensure user safety
- » Install signage to reinforce rules and support safe public use



COMMUNITY GARDEN

With a high demand for limited community garden plots, members of the public voiced a strong desire for new community garden space in East Anchorage. The Master Plan proposes that a community garden be located in the Core Area. A new community garden would increase activity within the park, and provide access to local, healthy food options for an increasingly dense and populated area of Anchorage.

- » Develop a community garden with individual, publicly available plots adjacent to the parking area
- » Provide fencing for the community garden that considers park aesthetics and adequately protects the garden from wildlife and vandalism
- » Provide access to water and amenities to facilitate growth, health, maintenance, and function of the community garden
- » Partner with local organization(s) to assist with education and fundraising
- » Program, manage, and enforce regulations to ensure a clean, healthy environment while minimizing conflict, barriers and maintenance needs



DOG PARK

Access to public open space is becoming increasingly important as East Anchorage continues to urbanize, particularly for dog owners who live in dense multi-family residences. The Master Plan includes a fenced off-leash area for residents to exercise and socialize with their pets. As envisioned, the off-leash area is intended to protect and improve the health of the park by minimizing the dispersal of dog waste throughout the park as well as in sensitive riparian areas.

- » Construct an off-leash dog area approximately $\frac{3}{4}$ - 1 acre in size
- » Enclose the off-leash area with a minimum 5' height fence
- » Develop the off-leash area near the parking lot to promote responsible use by dog owners and minimize the occurrences of off-leash dogs loose in the park
- » Provide formal double entrances for leash transition areas
- » Install mutt-mitts, signage and bear-proof trash receptacles
- » Enforce regulations to ensure a clean, functional, and healthy off-leash area
- » Partner with local organization(s) to assist with education and fundraising
- » Monitor the health of Chester Creek to ensure off-leash activity does not negatively impact water quality

OPEN RECREATION

Open recreation areas offer park users ultimate flexibility for leisure and recreation. The Master Plan proposes open recreation areas be developed in the Core and Chugach Areas. Space for open recreation should be centrally located and take advantage of existing meadows. Open recreation areas should be designed to complement natural areas and newly developed facilities, and to maximize solar access.

- » Develop a well-drained, flat, and maintained lawn area south of the Spine in the Core area of the park
- » To the extent possible, frame and extend desirable views across open recreation areas to encourage users to venture further into the park
- » Provide amenities to support use such as benches and bear-proof trash cans

South Facing Slopes w/ Solar Access and Views

The park site is generally at a higher elevation than its immediate neighbors as a result of significant fill imported and distributed on site during nursery operations of the past. The elevated areas rise to the east and north with a short bluff landform encircling the south, east and north edges. South facing slopes and areas atop the bluff offer ample solar access for park users and visitors. Existing, intermittent open areas scattered throughout the site also offer ideal areas for year-round solar access. As a northern city, and with limited public open space available in East Anchorage, careful considerations shall be made to maintain and increase solar access while balancing the desire to maintain forest and natural areas.



ORCHARD

For many East Anchorage residents, the identity of the park has long been tied to the Mann Leiser greenhouse and nursery. When combined with the community's desire to develop public spaces for food cultivation, an orchard or edible forest presents a unique opportunity to activate parkland for community health. The Master Plan recommends developing an orchard or programmed edible forest in the Core Area of the park that provides publicly available, locally grown food and offers seasonal social harvest opportunities.

- » Develop an Orchard or Edible Forest near or adjacent to the Community Garden
- » Layout plantings to maintain clear lines of sight and adequate spacing to reduce the risk of encounters with bear and moose
- » Work with local nursery, horticulture, and arboriculture professionals to identify proper management strategies to ensure the long-term health of plant material
- » Utilize hardy plant materials that are less susceptible to moose browse
- » Incorporate aesthetically pleasing and minimally visible barriers or fencing to protect plant materials from wildlife or vandalism
- » Identify and engage community partners to assist with installation, management and maintenance of the Orchard
- » Engage community partners to organize and celebrate planting and harvesting as community-wide events

PARK HOST

User safety and negative behavior in the park were identified as major concerns during the public process. In combination with other efforts included in the Master Plan, provisions for accommodating an on-site park host should be considered as the park Core Area builds out. A Park Host would provide a visible presence in the park that will discourage undesirable behavior and encourage positive use.

- » Consider a Park Host to provide continuous supervision in the park, similar to existing programs at Centennial Park and area schools, to ensure user safety and deter negative activity in and around the park during off-peak hours
- » Provide a parking space to accommodate a recreational vehicle (RV) in the Core parking area near the Community Garden with shared access to water and power utilities

"A FOOD FOREST WOULD BE NEAT. THERE ARE SEVERAL APPLE TREES THAT DO WELL UP HERE AS WELL AS OTHER FRUITS AND VEGETABLES. DO SOMETHING DIFFERENT & UNIQUE, SOMETHING TO DRAW PEOPLE IN."



PARKING

A parking lot accessed from the intersection of Boston Street and E Debarr Road with approximately 50 spaces serves uses within the Core Area. Development of a parking lot in this location provides the most direct access to the Core Area while minimizing the impacts of traffic on the surrounding neighborhood. The Master Plan recommends construction of a vehicle access drive and parking lot to adequately serve the Core Area activities and support uses in other areas of the park.

- » Construct a parking lot north of the Spine in the Core Area, adjacent to the Community Garden, and near the Dog Park that accommodates approximately 50 vehicles
- » Provide a single vehicle access drive and gate connecting the parking lot to the intersection of East Debarr Road and Boston Street
- » Install lighting and landscaping as required by Title 21
- » Provide clear lines of sight into the parking lot from adjacent roadways to deter negative activity
- » Install a park standard sign at park entrance
- » Consider providing space and utilities for a Park Host

RESTROOMS

Public input supports development of public restroom facilities in the Park to service the basic needs of visitors. The Master Plan recommends providing an accessible public restroom facility in the Core Area to meet the needs of park users.

- » Develop permanent restroom facilities with shared utility access and storage near the parking lot for ease of servicing
- » Provide portable toilet facilities with visual screens if a permanent facility is not feasible
- » Incorporate area lighting and maintain clear lines of sight from adjacent roadways to discourage misuse and vandalism

VIEWPOINT

The Core Area offers spectacular views of Chester Creek and the Chugach Mountains. Prominent viewpoints are located along the bluff at the south edge of the site above the beaver pond. The Master Plan recommends developing a formalized viewing area near the open recreation space that is easily accessible from trails within the park.

- » Develop a destination viewpoint on the bluff above the beaver pond with lighting, interpretive features, and basic amenities
- » Locate the viewpoint to maximize solar gain during winter months
- » Provide a visible marker or feature that can be seen from across the open recreation area and, if possible from Windsong Park, to serve as a reference point for park visitors

"WE ARE IN THE

CONTINUOUS PRESENCE OF
MOUNTAINS. I LOVE THAT!"




CHUGACH AREA

The Chugach Area is the easternmost area of the park and is the least developed area proposed in the Master Plan. It is connected to the Core Area by a wide pedestrian Spine. Open recreation areas and forested wilderness define the Chugach Area. Numerous multi-use paths meander through existing natural areas and lead users to expansive views of the Chugach Mountains. Bridge and boardwalk connections over Chester Creek are planned to improve access to adjacent neighborhoods and Windsong Park.





"I HAVE WALKED IN THE
PARK FOR THE PAST TEN
YEARS. MY RELATIONSHIP
WITH THIS LAND HAS
INSPIRED ME TO WORK TO
PROTECT IT. MY WISH IS
THAT SOME OF THE LAND
BE LEFT UNTOUCHED SO
OTHERS CAN BE INSPIRED BY
IT IN A SIMILAR WAY."



OPEN RECREATION

The Master Plan locates a second open recreation space in the Chugach Area. The open recreation area should assume the same general footprint as the existing meadow area.


- » Locate a well-drained, flat, and maintained lawn area at the east terminus of the Spine with views of the Chugach Mountains
- » To the extent possible, frame and extend desirable views of the Chugach Mountains to the east across the open recreation area and at the terminus of the Spine
- » Provide amenities to support use such as benches and bear-proof trash cans

Forest as a Valued Natural Resource

Existing forest areas were identified as important natural assets to the Park Advisory Committee and public. The native birch/spruce forest atop The Hill is considered the most highly valued stand of forest on site.

Large portions of the park is pioneer forest with pockets of mature cottonwood, aspen, birch and alder mixed with brush, meadow and understory. Alder and Cottonwood are the dominant species along bluffs and low areas, with the invasive *Prunus padus* (Mayday, Bird Cherry) observed along riparian areas.

Historical aerial imagery indicates the existing forest is recently established, with fill operations lasting into the 1990's. The forests serve important wildlife habitat and ecological functions. Though the forests are identified as important features in the park, a balance must be made to provide for safe use and activities on site.



VIEWPOINT

Muldoon Town Square Park has some of the best views of the Chugach Mountains in Anchorage. At the eastern end of the Chugach Area, visitors are rewarded with breath-taking views of the Chugach Front Range and low-lying wetlands on JBER property to east. The Master Plan recommends developing a formal viewing area at the top of the eastern bluff in the Chugach Area.

- » Develop a viewpoint destination at the east end of the park along a multi-use path with trail lighting, interpretive features, and basic amenities
- » Provide a visible marker or feature that can be seen from the terminus of the Spine to serve as a visual connection for park users



**"I HOPE THIS PARK WILL
HELP FOSTER NEIGHBORHOOD
CLOSENESS."**

Establish Neighborhood Connections to the Park

Public input and Park Advisory Committee feedback described a strong desire to provide safe and sustainable access to the park from the surrounding neighborhoods.

Improving access from the south neighborhoods will require crossing Chester Creek with bridges, culverts appropriate for fish passage, and/or boardwalk. Elevated structures such as bridges and boardwalks are costly but offer an opportunity to provide observation areas, education, and aesthetic park features. Culverts are not desired and may be difficult to permit. Pedestrian bridges should be constructed to meet or exceed emergency and service vehicle loading requirements so police, ambulance, fire or municipal maintenance staff can easily access developed areas of the park.

The existing unpaved vehicle access drive at the T-intersection of Boston Street and East Debarr Road presents the opportunity to limit vehicle traffic impacts further east and provide safe access and egress near the midpoint of the park. Pedestrian-only, multi-use path connections to the north neighborhoods should align with street intersections on East Debarr Road as the park extends east.



COMMON ELEMENTS AMENITIES

The Master Plan recommends providing park amenities in high-use locations consistent with those found throughout the Anchorage park system. Park amenities should support uses within the park while enhancing park user's experience. The following amenities are anticipated for Muldoon Town Square Park:

- » Benches and Seating
- » Picnic Tables
- » Bear-Proof Trash Cans
- » Dog Waste Stations
- » Signage including: Interpretive Panels, Rules and Regulations, and Wayfinding Signage; including entry sign(s), kiosks, directional signs and markers
- » Bicycle Racks

ACCESS AND CIRCULATION

Safe and convenient access to Muldoon Town Square Park is important to the Park's success as an active public space. The Master Plan recommends a mix of trails, bridges, and vehicle access to support uses within the park. The following list describes recommended infrastructure to facilitate access and circulation at Muldoon Town Square Park.

BRIDGES + BOARDWALKS

Chester Creek is an important natural feature that physically defines different use areas within the park. To facilitate circulation, pedestrian-scale bridges are proposed at five locations. Two bridges link the Muldoon and Core Areas, two bridges provide access between the park and neighborhood to the south, and one bridge/boardwalk connects the park to Windsong Park.

Bridges should be designed to accommodate service and emergency vehicles and allow for observation of stream or wetland features below. A boardwalk traversing the existing wetland area may be considered for the connection to Windsong Park in lieu of a single span bridge, but must similarly meet pedestrian and bicycle loading, fall protection, and floodway/wetland requirements.

- » Construct bridges and boardwalks with materials that are durable, safe, and minimize impacts to the adjacent wetland and stream ecosystems; such as light-penetrating decking
- » Incorporate wayfinding and interpretive features to educate the public about features viewable from the deck

MULTI-USE PATHS

Bicycle and pedestrian paths are highly desired by the community for active recreation and leisure uses. The Master Plan identifies a network of paved multi-use paths that connect users to various destinations within the park.

- » Construct a series of 8-10 foot wide accessible paved paths
- » Implement a wayfinding signage program with consistent theme, identity and sign hierarchy to clearly lead users to activity areas and adjacent neighborhoods
- » Install distance markers along multi-use paths to support the wayfinding program, and encourage healthy exercise and physical training
- » Install trail lighting and manage vegetation in forested areas to improve visibility and minimize human-wildlife conflicts

NATURE TRAILS

In addition to the Multi-Use Paths, the Master Plan identifies soft-surface nature trails in less developed areas of the park. Nature trails provide opportunities for quiet contemplation and a more intimate park experience. Through thoughtful design, nature trails should serve to protect sensitive ecosystems, particularly along Chester Creek, by focusing foot traffic to designated trails and minimize trampling.

- » Identify and develop Nature Trails in locations of already existing social trails to improve access and minimize widespread trampling
- » Develop trails with a minimum 10' "stream protection" setback as required by Anchorage Municipal Code Title 21 Land Use Code
- » Engage community partners and volunteers to fundraise, seek donations and build soft-surface trails
- » Develop soft-surface trails to meet ADA accessibility requirements to the extent possible

"TRAILS, PAVED AND UNPAVED, FOR SEPARATED USERS
AND YEAR-ROUND ACTIVITIES, WITH CONNECTIONS TO THE
COMMUNITY AND OTHER TRAILS ARE HIGHLY DESIRED."



Example of a soft
surface nature trail



Example of a lighted multi-use path as a pedestrian spine

THE SPINE

A clearly defined central corridor runs east to west unifying the Chugach and Core Areas. The Spine is a pedestrian promenade that links activities and use areas within park while providing access for service and emergency vehicles.

- » Develop a 12-16 foot wide promenade that accommodates numerous users and modes of travel through the center of the park, stretching east-west from the Muldoon area to the Chugach area
- » Locate features and activities along the Spine in the Core area of the park to encourage social interaction
- » Install lighting along the walkway for safe winter use
- » Provide access for emergency and service vehicles
- » Incorporate wayfinding signage to allow visitors to easily navigate the park
- » Maintain areas along the Spine for high visibility

MULDOON PERIMETER TRAIL CONNECTION

Identified in the East Anchorage District Plan, the north-south Muldoon Perimeter Trail is anticipated to serve as a major transportation and recreation corridor. The Master Plan acknowledges the potential future development of this trail and identifies phased improvements and connections between the park and trail.

- » Locate a key trail intersection with amenities, wayfinding, and parking at the terminus of the existing East Debarr ROW at the northeast corner of Muldoon Town Square Park
- » Invite Muldoon Perimeter Trail users into the Park by providing multi-use path access points along the existing separated path extending along East Debarr Road; which is anticipated to be the primary connection serving the Muldoon Town Center

VEHICLES

Public vehicle access and parking is provided at parking lots located along the periphery of the park. Gated access to event space is provided from the parking lot in the Muldoon Area to support events. Internal vehicle access is limited to emergency and service vehicles. Where feasible, the Master Plan recommends combining emergency and maintenance access with multi-use paths and the Spine, to improve safety and provide convenient access to park use areas.

- » Provide gated vehicle access for maintenance and emergency vehicles at two parking lots
- » Limit on-site vehicle circulation, to the extent possible, to retain the park's natural character and support use of the park as an active recreation and community use destination



“... LIGHTING OVER ALL

AREAS OF THE PARK, SO

IT CAN BE USED IN THE

WINTER EVENINGS.”



Muldoon Perimeter Trail

A future Muldoon Perimeter Trail as outlined in the *East Anchorage District Plan* would provide a highly desired north-south trail connection along JBER property on the Eastside. The existing multi-use path along East Debarr Road is envisioned as the primary connection for linking Perimeter Trail users to the Muldoon Town Center with a possible future trailhead developed at the terminus of East Debarr Road.

Pedestrian connections to the Perimeter Trail and existing multi-use path are intended to invite people into the Park to participate in outdoor recreation and community activities.

UTILITIES

The development of improvements at Muldoon Town Square Park will require coordination with local utilities to connect and install desired infrastructure currently unavailable on site. The Master Plan recommends the installation of service tie-ins for power, water, and sewer utilities to support various features and amenities within the Park. It is recommended that each phase of development properly plan for the installation of utilities to maximize implementation funding.

ELECTRIC

Electricity should be supplied to provide power and lighting to support park activities. Power and lighting installations should adhere to the latest approved standards and design criteria and comply with Title 21 requirements for specific uses, such as parking. The Master Plan recommends that lighting is installed along multi-use paths and within active use areas to enhance year-round use, ensure public safety and visibility, and discourage vandalism and other illegal activities.

- » Install a lighting system consistent with Municipal and Parks Department standards with fixtures and poles at heights appropriate in scale and character for intended uses
- » Incorporate high efficient LED lighting to minimize long-term maintenance and operations costs
- » Design lighting to minimize the impacts of light pollution on surrounding neighborhoods
- » Specialty lighting may be considered for use in design features or for specific uses or activities on site if determined to provide added value
- » Provide power supplies in high-use areas of the park to support events
- » Integrate power supplies with lighting systems or structures where possible, or as standalone features that are protected, lockable, and weatherproof

SANITARY SEWER

Installation of sanitary sewer service lines are intended to be constructed in the Muldoon and Core areas to support the development of permanent restroom facilities.

- » Coordinate sanitary sewer service tie-in locations and installation with Anchorage Water and Wastewater Utility (AWWU)

WATER

Water service lines should be constructed in the Muldoon and Core Areas to support the development of facilities on site. The Master Plan describes several activities and uses that would benefit from shared access to water including the event space, restroom facilities, ribbon, pavilion, community garden, dog park, and park host.

- » Coordinate water service tie-in locations and installation with Anchorage Water and Wastewater Utility (AWWU)



Example of low impact
development stormwater
management

PUBLIC ART

Public art was identified as a place-making strategy that would create a unique identity for Muldoon Town Square Park. The concept of public art was supported during the planning process with input describing a desire to establish the Park as an icon that celebrates the community's diversity and the park's distinctive natural features.


The Master Plan recommends an independent process to identify, design and implement public art projects. Public art proposals should be evaluated prior to approval to safeguard the character and visual aesthetic of the park. The Master Plan identifies potential locations for public art installations; however, specific locations should be determined at a future time, as proposals are submitted, to determine the suitability of art and location.

- » Identify and engage local, state, and national agencies and organizations as partners to initiate public art projects, identify funding opportunities, and provide technical support
- » Encourage local and multi-cultural artist participation in public art projects at the Park
- » Develop criteria for evaluating public art projects at Muldoon Town Square Park and outline the process for public involvement and approvals
- » Locate art in highly visible locations and provide lighting to deter vandalism and damage

STORMWATER MANAGEMENT

Development of parking lots and hardscapes will require stormwater conveyance and treatment infrastructure to address runoff from impervious surfaces. Because of the prominence of Chester Creek, it is important that stormwater is effectively managed to minimize any potential impacts to water quality. The Master Plan recommends stormwater infrastructure that meets or exceeds water quality and treatment requirements by employing strategies, technologies, and techniques consistent with Low Impact Development (LID) Best Management Practices (BMP), otherwise known as Green Infrastructure.

- » Partner with MOA Watershed Management to identify, prioritize and fund Green Infrastructure projects at Muldoon Town Square Park
- » Utilize Low Impact Development Best Management Practices, to the greatest extent possible, to manage stormwater and water quality
- » Combine landscape plantings and LID stormwater management techniques to maximize efficiencies in funding and physical space
- » Provide education and outreach on the benefits of Green Infrastructure and watershed health
- » Monitor and evaluate installed LID BMPs to advance successful implementation strategies and proactively identify necessary improvements



“KEEP THE

PARK NATURAL

WITH WOODED

AREAS, RESIST

OVERBUILDING TO

MAINTAIN GREEN

SPACE.”



LANDSCAPE AND VEGETATION


As East Anchorage continues to urbanize, access to greenspace and urban forest remain a high priority within the community. The Master Plan recommends management of native vegetation within the park to achieve an aesthetic appearance and support natural functions. Management of forest vegetation should include routine maintenance; such as selective thinning and clearing of brush to increase visibility and improve overall forest health.

New landscape areas and plantings should be appropriate to USDA Hardiness Zone 4a, with preference given to native species, edible, and traditional medicinal plants to enhance the public use and purpose of the park.

- » Prioritize the preservation and enhancement of existing native vegetation through best management practices to improve forest health
- » Install landscape plantings to be compatible with adjacent uses; such as play areas, trails, event space and open recreation
- » Design landscape areas to be easily maintained by volunteers and Parks and Recreation staff
- » Manage vegetation and thin brush along the periphery of activity areas to improve safety and visibility
- » Manage vegetation along, and adjacent to, multi-use paths and informal trails to maintain clear lines of sight and minimize human-wildlife encounters
- » Establish partnerships with local arborists, horticulturists, master gardeners, landscape contractors, and other plant and soils specialists to implement beautification projects
- » Partner with area residents, volunteers, agencies, and non-governmental organizations to remove invasive species within the park and along the Chester Creek corridor

05

IMPLEMENTATION



IMPLEMENTATION

This Master Plan is the blueprint for use and development of the Muldoon Town Square Park for the next 20 years. The following implementation section describes the steps necessary to actualize the preferred alternative identified in this Master Plan. Implementation mechanisms for the Master Plan include regulatory controls, such as zoning, platting, and development standards from Title 21 and adopted plans such as the *Anchorage Bowl Park, Natural Resource, and Recreation Facility Plan* and the recently adopted *East Anchorage District Plan*.


Timeframes are approximate and based on the information, knowledge and priorities of the community at the time of Master Plan development. Over time priorities may shift and time frames may change.


An estimated cost is associated with each projected phase of implementation to help further define priorities. As this Master Plan is expected to be implemented and achieved over the 20 year horizon, cost estimates should be updated and evaluated in response to changes in economic conditions, permit and regulatory requirements, and construction climate.

REGULATORY CONTROLS - TITLE 21 LAND USE REGULATIONS

As with all public facilities, Muldoon Town Square Park will be implemented through site development standards as set forth in zoning and land use regulations in Anchorage Municipal Code, Title 21 Land Use Planning. As each area of the Park is implemented through site design, on-site development shall adhere to all required property setbacks, stream setbacks, landscape requirements, parking requirements, allowable uses and dimensional standards to ensure a quality facility for all users.








DESIGN CRITERIA

- » **Amenities:** The Master Plan shall be implemented with equipment, materials and construction types consistent with MOA Parks and Recreation Department design standards. The greater Anchorage park system benefits from the installation of standardized amenities by maintaining a consistent appearance, ensuring efficient maintenance and replacement, and accurately anticipating capital, operations, and maintenance budgets. Desired variances from the provision of standard equipment shall be identified, justified, and reviewed for approval by the Parks Superintendent.
- » **Design and Construction:** Park improvements shall be completed in accordance with the latest version of the Municipality of Anchorage Standard Specifications (MASS), to ensure products and construction on-site are consistent in quality, quantity and cost.
- » **Safety and Regulatory:** Muldoon Town Square Park is a public facility and is required to meet or exceed all codes, standards, design criteria and regulations for development. Park development shall also identify and adhere to use-specific design standards, including but not limited to *ASTM Standards for Playground Safety and Design*, *AASHTO Guide for Development of Bicycle Facilities*, and the *2010 ADA Standards for Accessible Design*.
- » **Inclusive Play:** This Master Plan identifies a park that is intended for use by visitors of all ages and abilities. Inclusive Play and Inclusive or Universal Design shall be a priority for development, especially for high-use areas such as community event spaces and play areas. Design of all park features and amenities shall strive to meet the following goals:
 - » Visible and Safe,
 - » Free of Obstacles, Obstructions or Barriers,
 - » Considers a Broad Spectrum of Abilities and Needs,
 - » Flexible, Adaptable, and Fun,
 - » Simple and Intuitive,
 - » Encourages Social, Physical and Educational Growth
 - » Appropriately Spaced and Sized for Approach and Use
- » **Green Infrastructure:** Muldoon Town Square Park is considered an important natural resource and shall be developed in accordance with the strategies and standards outlined in the *Anchorage Stormwater Manual*, *Design Criteria Manual*, Chapter 2 – Drainage¹, prioritizing Low Impact Development Best Management Practices (Green Infrastructure) for Stormwater Management. Additionally, opportunities to advance public awareness including participation in technical research or citizen science, to improve air, water and soil quality should be explored.

¹Municipality of Anchorage. Project Management and Engineering Division. (March 2015). *Anchorage Stormwater Manual* (Draft Version 1.0). Anchorage: Municipality of Anchorage.



Chester Creek Realignment at Muldoon Road Project

The Chester Creek Realignment at Muldoon Road Project completed in 2015 is evidence of a successful stream and site improvements project completed as a result of partnerships between federal, state and local agencies and organizations.

The agencies involved in the project should be invited to participate in further development of the park by providing funding, technical expertise or other assistance specific to each project phase or need, as appropriate.

FUNDING STRATEGIES

Funding development of parks and recreation facilities can be challenging, especially with projected budget shortfalls identified for the State of Alaska and its communities beginning in 2016. A diverse mix of public and private funding sources are likely to be required to advance the implementation of this Master Plan.

A phased implementation cost estimate is provided as an Appendix to the Master Plan to establish base of reference costs for use in prioritizing and identifying potential funding sources over the long-term. Funding sources available to implement this Master Plan are anticipated to be: MOA Parks and Recreation Department Operations and Maintenance Budgets, Capital Improvements Programs, Municipal Park Bonds, Public-Private Partnerships, and additional funding sources.

Operations and Maintenance Budgets

Anchorage Parks and Recreation manages an annual budget for the operations and maintenance of parks determined by the Anchorage Assembly and Mayor. It is typical that O&M funding be made available for the upkeep, maintenance and rehabilitation of improvements throughout the life of the park. Development of the park should include considerations for both short- and long-term impacts to the operations and maintenance budget as funding priorities may change with administrations, or be subject to reductions due to economic downturn.



Capital Improvement Program (CIP)

The Municipality of Anchorage uses the Capital Improvement Program as an essential planning and budgeting instrument to identify desired public facilities and capital improvements over a six year cycle. Identified priorities under the annual Capital Improvement Program provide funding, cost, and time frames for priority projects, and is a useful mechanism to enable long-term investment. Park development projects are not typically considered high-priority projects due to greater infrastructure and safety needs, but do receive support and funding.

Municipal Park Bonds

Park improvement projects are funded in part by the passage of Municipal Park Bonds by Anchorage voters. In recent years, the Anchorage Park System has benefited from the passage of municipal bonds. Continued engagement with the public and successful implementation of park projects demonstrates the potential for bonds as a future funding source.

Public-Private Partnerships (P³)

Implementation of the Muldoon Town Square Park Master Plan will likely require funding from non-governmental funding sources. With assistance from volunteers, grants, or community organizations. In recent years, significant areawide park improvements have been made possible by building local support in collaboration with community partners, such as the Anchorage Park Foundation and the Rasmuson Foundation. These partnerships have proven successful in leveraging limited available funds with matching grants.



THE OVERWHELMING SUPPORT
EXHIBITED BY THE COMMUNITY
TO DESIGNATE THIS SITE AS

MULDOON TOWN SQUARE PARK
INDICATES THE POTENTIAL TO
ENGAGE THE LOCAL OR GREATER
ANCHORAGE COMMUNITY IN A
FUNDRAISING CAMPAIGN TO
IMPLEMENT PARK IMPROVEMENTS.



ADDITIONAL FUNDING SOURCES:

Federal Funding

National programs for improving communities may provide funding opportunities for implementing components of the Master Plan that advance non-motorized infrastructure, improve public health and safety, integrate or restore natural systems, or benefit public education through expression, learning, research and outreach.

Fundraising

The support exhibited by the community to designate this site as Muldoon Town Square Park indicates an opportunity to engage the greater Anchorage community in a fundraising campaign to implement park improvements. Additionally, national and local businesses who support the vision, interests and uses of the park may be inclined to contribute to park development to ensure long-term viability within their business' community.

IMPLEMENTATION TIMELINE





"THIS LAND HAS ALWAYS BEEN A DESTINATION FOR PEOPLE
AND WE WANT TO HAVE THAT HAPPEN AGAIN."



Mid-Term 5-10 Years				Long Range 10-20 Years				External + Illustrative Projects																																			
1	Iconic Pavilion	\$600,000	Donors, State Grant, Bonds, APE, P&R General Fund	P&R	2	Boardwalk Connection to Windsong Park	Grants, Wetland Mitigation Funds, APE, P&R Gen. Fund	P&R, ACOE, MOA Watershed Management	3	East 14th Avenue Right-of-Way Dedication	TBD	TBD	MOA Traffic, MOA Private Development	4	East 14th Avenue Parking	\$300,000	P&R General Fund, PM&E	P&R, PM&E, MOA Traffic	1	Install Community Public Art	\$1 Million	Grants, APE, Donors	P&R, Community Organizations	2	Connect to Muldoon Perimeter Trail	\$100,000	P&R General Fund	P&R, PM&E	A	Muldoon Pedestrian Crossing (Overpass/Tunnel)	\$1 Million	AKDOT, PM&E	AKDOT, PM&E	B	Trailhead at Muldoon Perimeter Trail	TBD	Grants, Bonds, P&R General Fund	P&R, PM&E	C	Vacate East Debarr Right-of-Way	TBD	TBD	MOA Right-of-Way, MOA Traffic



APPENDIX A

MEETING MINUTES

KICKOFF SITE MEETING

BETTISWORTH NORTH
ARCHITECTURE PLANNING LANDSCAPE INTERIORS

MEETING SUMMARY

DATE/TIME: September 17th, 2015
LOCATION: Boys and Girls Club (Northeast) and Muldoon Town Square Park Site, Anchorage
TOPIC: Muldoon Town Square Park Master Plan: Kickoff and Site Visit
PARTICIPANTS: Betsy Chivers, Parks Committee
Stu Grenier, Parks Committee
Jonny Hayes, Bettisworth North
Genevieve Holubik, Parks Committee
Kendra Kloster, Parks Committee
Nickel LaFleur, Parks Committee
Van Le, R&M Consultants
Jerrienne Lowther, Parks Committee
Steve Rafuse, MOA P+R
Kevin Smestad, Parks Committee
Dave Ulmer, Parks Committee
Jeff Urbanus, MOA Watershed Management

The goal of the Project Kickoff and Site Visit Meeting is to organize and establish the Park Committee within the framework of the Master Plan Project, identify roles and responsibilities, share the project schedule and identify critical paths, and perform initial investigations and analysis of the Muldoon Town Square Park site as a group.

The Kickoff and Site Visit summary that follows describes the discussions and activities of the meeting as they occurred within the confines of the larger group.

Park Committee Background
The Park Committee consists of 15 individuals representing both the Northeast Community Council and the South Anchorage Community Council. The Park Committee Members were established by their respective Community Councils and organized prior to the Muldoon Town Square Park Master Plan Project.

- The purpose of the Park Committee is to ensure that the interest and desires of the Muldoon community are represented in the park planning process.
- The Park Committee provides area and site history, experience that will assist the planning team in the development of the master plan
- The Park Committee will serve as conduits of communication with the larger network of residents, neighbors, businesses and organizations in the area and impacted by the Muldoon Town Square Park Master Plan project. The Park Committee is an organized and recognized Committee serving as advisors to the Park Master Plan design team.

Project Kickoff: 5:30p - 6:00p

The goal of the kickoff is to organize the Park Committee and Design Team as collaborators and contributors to the Park Master Plan Process. Project binders were distributed to attending Park Committee Members with schedules, background materials, schedules and other resources relative to park planning for use throughout the project.

- Meeting Participants
 - o Park Committee Members
 - o Jerrienne Lowther: Photographer, Artist + IlloveMuldoon web organizer
 - o Genevieve Holubik: Architect + Active on similar boards/committees

115 FRONT STREET ANCHORAGE, ALASKA 99501
PHONE >> (907) 465-9140 FAX >> (907) 465-9544
8400 DENALI STREET SUITE 710 ANCHORAGE, ALASKA 99503
PHONE >> (907) 664-9140 FAX >> (907) 664-9140
WWW.BETTISWORTHNORTH.COM

- o Dave Ulmer: Active Community Council Member + supporter of Park
- o Nickel LaFleur (spelling corrected): Arborist, Muldoon tree lover
- o Stu Grenier: NECC Secretary + Park Advocate
- o Kendra Kloster: Resident, NECC/PCC member, history w/ park Leg. Aide
- o Betsy Chivers: NECC/PCC member, Park Committee
- o Kevin Smestad: NECC member, Capital Improvement Project chair
- o Steve Rafuse: MOA Parks + Recreation, Owner Representative + Park Planner
- o Jonny Hayes: Bettisworth North, Project Manager + Master Plan Team Lead
- o Van Le: R&M Consultants, Public Involvement + Lead Planner
- o Jeff Urbanus: Technical Staff - MOA Watershed Management
- Discussion/General Comments:
 - o Stu announcement: Door to Door distribution of fliers for Sept. 28th Public Workshop begins this Friday after work, 9/19, and any assistance is welcome
 - Also announced on MOA parks website, Facebook, 'lovenuldoon', and others to spread the word.
 - o Stu noted that NECC voted to recommend 100'x100' lot (privately owned) to be included as part of Muldoon Town Square Park
 - o Stu noted Bike Trail @ East edge along JBER boundary from Centennial Park to Muldoon Town Square Park (MTSP) is in planning phase. Extension to Muldoon Curve for connection is desired. This project should reflect connection at east edge. (Planning Team to confirm status of bike trail project)
 - o Planning Team: Master Plan effort is next step, after years of hard work in making these parcels a dedicated park, with numerous challenges overcome
 - Expect Parks Committee attendance, input, open communication and feedback. It's a community park and we are technical staff to realize Parks Committee + community vision within the constraints of the site/context.
 - Access + History as Fill site described as examples of technical investigations underway by planning/design team.
 - Questions:
 - o How will planning/implementation contract maximize allocated funds (\$1 mil + \$500K)?
 - [SR]: Planning less than \$100K. Subsequent Engineering, Design, Permitting, etc. for implementation plan will have an additional cost. The goal is to maximize implementation funds for construction of planned elements.
 - o Will Planning Team do the work, how will implementation be managed
 - [SR]: Parks + TBC work through implementation typically. Next steps and required engineering dependent on the scope of work.

Site Visit: 6:05p - 7:10p

The goal of the site visit is for the planning team to listen to the experience and expertise of the Park Committee members in identifying potential opportunities and constraints of the Muldoon Town Square Park site and context. The site visit is a key component of the site investigation process. Park Committee Members were asked to lead the tour and identify interesting site features, describe opportunities and constraints, share history and experiences of the area, and offer any other input they pleased along the way.

- The site visit tour of Muldoon Town Square Park starts at northwest creek bend, working towards Muldoon, loop back to Boston Rd. and enter site heading south and east. Team and Park Committee take site photos. Park Committee provided input to team along the way and at intermittent stops. Poor weather conditions with light rain and wind during the tour. The tour was a success with good communication and shared information. Park Committee Members shared experiences of the numerous and sustained efforts of various active groups to establish the park and offered information about the variety of activities and uses recommended for inclusion in the park.

- Stu Leads Site Visit, recorded features and elements as follows:
 - Community for bike/path connection @ north edge from Boston to Muldoon Farm intersection (noted possible conflict of recently planted birch)
 - "The Hill"
 - Visible from west, including IntX
 - Great views, depending on level of clearing
 - Desired Identifiable and Functional feature
 - Pavilion discussion, similar to Abbott Loop Community Park for gatherings, including electricity
 - Visibility may allow for better security (passive surveillance)
 - Joimy noted fill areas and possible impacts on construction costs
 - "The Axis"
 - Pedestrian bridge at 60' bank to bank location in N/S midpoint of parcel to connect Muldoon road 'bad' area to The Hill
 - Desired a bridge with 'character', possible boulders or feature as special place
 - Already patis heading east into site, where old residence was, crossing creek again @ metal beams
 - Strong desire to provide bicycle + pedestrian access to 'back' of site
 - Creek Access @ West
 - Many noted sound of creek as great feature of park, masking noise of parking lot and road
 - Noted youth using creek for swimming
 - Homeless using the creek as sewer
 - Creek spills site creating possible access challenges
 - Fish in creek!
 - Discussion about how to interact with creek, views vs. physical access (steps, stairs, ADA path).
 - Note: erosion and fish habitat
 - Discussion of stream buffers (25' offset from *centerline* of creek)
 - Wood chip path convenient and enjoyable
 - West 'bad' @ Muldoon road
 - Great spot for gathering and desired Muldoon Farmer Market location
 - Parking
 - West End:
 - Possible Ideas: pavilion, Off-Leash dog area, nature/natural play area, Farmer's Market
 - Park Center:
 - Possible Ideas: Amphitheater at north east bend of creek, with sloped seating facing west/southwest
 - Bicycle + Walking paths along Creek
 - Bicycle pump park and/or Skate Park for area youth (west or center portion) as local business community hires police/security to discourage youth skateboarders + cyclists
 - Access across creek and to the east with patis, Difficult/No Access currently
 - Nature Play/Natural play area possibility to activate space
 - Possible community gardens at large opening at north edge, south facing
 - Possible community garden east and north of creek, with access to creek for water access
 - Homeless camps are common occurrence at mid-point of park, in the high forested area north of bisecting trail
 - Homeless camps observed in oxbow of Creek at the base of 'The Hill'

3

- Beaver Dam Overlook:
 - High embankment has community-cleared trail for accessing views across Windsong Park to Chugach Front Range.
 - Trail at higher elevation points at south boundary above beaver dam area offer southern exposure, access to sunlight and warmth in all seasons which is lacking in many N/S oriented residential
 - Difficult to see structures in area
 - Privacy concerns in area
 - Serious concern, especially when beaver dam breaks in wet seasons raise water level at existing wetland/sediment basin area
 - Sediment basin focuses on water quality, not quantity, opportunity to construct wetlands to help treat water (polishing wetlands) and continue to improve Chester Creek health
 - Active Beaver area, discussion of dog walks @ University Lake and aggressive beavers/dogs and conflicts, in tandem with flooding concerns from beaver dam construction
- East End:
 - Major fill site (5'-20' depth) is costly for developing and structures/permanent facilities
 - High + Dry, offers great views
 - Cottonwood @ east/south edge are fast growing and obstruct views/solar access
 - Bike path connection to N/S proposed trail @ JBER property line, from Centennial Park to Muldoon Curve
 - Off leash dog area for neighbors
 - Prime location for open recreation fields
 - Access to north neighborhood at street intersections
- General Observations/Suggestions:
 - New lighted path along north boundary is recent construction and amenity, can/should be extended to Muldoon IntX, especially if/when the N/S bike path @ JBER property edge is constructed
 - Discussion of year round caretaker (RV/structure) to improve safety
 - Homeless camps are typical
 - Wildlife discussion, bear are typical especially with fish in stream
 - Difficult navigation of informal trails during site walk
 - Variety of topography created interesting spaces and experiences, from north creek to up on the high flat area
 - Looking across to the mountains (overcast)
 - Predominantly cottonwood and pioneer species in center and east section. Birch spruce observed in areas along creek.
 - Many informal paths crisscross site with dilapidated 'bridges' stretching across creek in areas
 - Access easement at south edge at neighborhood is fenced off with ball wood screen/privacy fence

4

AREA CONTEXT




SITE ANALYSIS



ANNOTATIONS

- | | | | | |
|---|---|---|--|--|
| <ul style="list-style-type: none"> 1 Existing DOT Right-of-Way @ Muldoon Rd 2 Limited Access at Intersection (RDA R.O.W.) 3 100' x 100' Privately Owned Parcel (Undeveloped) 4 Privately Owned Commercial Parcel (Undeveloped) 5 Access Challenges: Creek, Wetland, Steep Slopes | <ul style="list-style-type: none"> 6 Forested Elevated Area / Unbuffered Camping 7 Recreational Bypass Dam Area 8 Significant Organic Fill Area (4'-30") 9 Cottonwood Obstructs View of Humintine 10 Steep Slopes w/ Vertical Separation | <ul style="list-style-type: none"> 1 Flat, Firm + Stable Soils w/ Muldoon Rd Access 2 10th Avenue Access 3 Chester Creek 4 Recreation Area w/ Path and Access 5 Narrow Location Suitable for Bridge/Crossing | <ul style="list-style-type: none"> 6 Access to Muldoon Trail and Debarr Rd R.O.W. 7 Accessible Sloped Area w/ Creek Access 8 Historic Residence Locations, Firm and Stable Soils 9 Highly Visible w/ Views, Possible Uses, Birch/Spruce 10 Easy Access Point, Slight Slopes, Stable, South Face | <ul style="list-style-type: none"> 1 Flat, Open Area w/ Solar Access 2 Identified Viewpoint Overlook, Solar Access 3 Flat, Open Area w/ Solar Access and Parking Views 4 Adjacent Park: Sheddling Hill, Loop Trail + Playground 5 Year-round Solar Access |
|---|---|---|--|--|



PUBLIC WORKSHOP #1



R&M CONSULTANTS, INC. | 9303 Vanguard Drive • Anchorage, AK 99507 • 907.522.1707
2100 E. Tudman Road • Anchorage, AK 99503 • 907.522.1707
9737 Muld Bay Road #401 • Kenai, AK 99550 • 907.220.9424

Public Workshop Summary

Project Number:	2320.01 (R&M)		
Project Title:	MOA Parks and Recreation Muldoon Town Square Park Master Plan		
Subject:	Muldoon Town Square Park Master Plan Public Workshop #1		
Author:	Van Le, AICP & Taryn Oleson, R&M Consultants, Inc.		
Meeting Location:	ASD Begich Middle School, Multi-Purpose Room		
Meeting Date:	Monday, September 28, 2015		
Meeting Outreach:	PARKS AND REC TO COMPLETE		
Meeting Materials:	Aerial Maps, Power of 10 Activities Handout, Meeting Agenda and Park History Handout		
Distribution Date:	Internal Review Version – Public Distribution TBD		
Meeting Attendance:	48 Attendees (sign in)		
Attendees:	Steve Rafuse Josh Durand Maevie Nevins Taylor Keegan Jonny Hayes, ASLA Mark Kimerer, ASLA Melissa Babb Van Le, AICP Taryn Oleson Beth Nordlund Andrew Mullins See also Sign In Sheet	Project Manager Parks Superintendent Park Planner Park Planner Landscape Architect Landscape Architect Landscape Designer Planner Planner/PI Coordinator Executive Director Project Manager	MOA Parks &Rec MOA Parks &Rec MOA Parks & Rec MOA Parks & Rec Bettisworth North Bettisworth North R&M R&M *APF *APF
(*Anchorage Park Foundation)			

(*Anchorage Park Foundation)

Meeting Information

The public workshop was advertised to start at 5:30 p.m. Several attendees arrived early and spoke with the Project Team about the Park. The meeting was Workshop style with a formal presentation.

The room was set up to allow for free movement of attendees with easels displaying aerial imagery of Muldoon Town Square park site and the surrounding area, and ten round tables with workshop materials that included an aerial map of the park site, handouts, markers and paper (see attached graphics).

A welcome table with sign-in sheets, handouts and refreshments was set up near the entrance of Begich Middle School's multi-purpose room. A second table was set up nearby with comment forms and a box for attendees to sit and submit written comments.

The following handouts were available to meeting attendees:

- Meeting Agenda and Park History Handout
- Aerial Maps
- Power of 10 Activities Handout

Workshop

The public workshop began with a presentation given by Steve Rafuse, Jonny Hayes and Van Le. The presentation covered the public process and purpose of the workshop, the history of development in the Muldoon area, and the history and existing conditions of the park parcel. Van Le led the large group through a brief Visioning exercise where attendees were encouraged to contribute their thoughts on what the Muldoon Town Square Park should be like in 20 years. Taryn Oleson recorded ideas as they were stated on large post-it notes which were then attached to a wall for review and reference throughout the rest of the workshop.

The following comments were gathered during the Visioning exercise:



- Community Gardens
- Trail by creek
- Off-leash dog park
- Universal access
- Playground
- Picnic areas
- Skateboard park
- Ice-skating rink
- North-South trail connection
- Community Center/Library
- Zip-line
- Separated pedestrian pathways (pedestrian-bike separation)
- Sense of freedom – a quiet, restful place
- Iconic Structure
- BBQ areas that are lighted for night-time use
- Multi-family gathering area
- Fire pits
- Neighborhood transition buffer
- Farmer's Market location
- Parking
- Caretaker's cabin/RV spot
- Boulder wall (rock climbing)
- Bridge connecting other parks (Windsong)
- Safe pedestrian access across Muldoon to park
- Chalet with running water and electricity for winter use
- Cross-country ski trails
- Amphitheatre
- Pump track



Following the large-group visioning exercise, attendees broke into small groups at their tables and worked through the Power of 10 Activity. A facilitator was present at each table to assist. Each group was tasked with coming up with ten short term "Clean and Green" things that they would do to improve the park right away without too much expense. They were then asked to share ten long-term "Dream Big" improvements for the park that would have greater impacts for the highest number of users. Each group wrote down their top three priorities on large post-it notes and reported their back to the whole group.

The following are the priorities reported by the small breakout groups:

1. Main gathering area- possibly a structure such as a pavilion
2. Destination viewpoint looking at the Chugach mountains
3. Community Gardens
1. Geocaching and orienteering activities
2. Farmer's Market
3. Community Gardens
1. Parking, access and lighting
2. Trails with bridges and signage (directional and educational) for improved connectivity

3. Formalized covered space for events such as the Muldoon Farmers Market
4. Place for families such as a playground or benches for picnics
1. Toilets
2. Walking trails with foot bridges over the creek
3. RV Camper spot for park host
5. Re-grade and remove existing fill to create views into the park
6. Bring Farmer's Market
1. Keep it natural- preserve waterway/health, connectivity for wildlife, limit light pollution
2. Access – provide meandering pathways and trails along waterways, connect to Windsong, Boston St, Cross point Loop, Early View Drive, Muldoon
3. For Children – provide playground in front/central area, destination playgrounds, basketball, other opportunities, conservation education
1. Destination Park – builds on park's history with destination green house, make people transition from orientating themselves with "How far from the Curve?" to "How far from the Park?"
2. Meeting or gathering space – possibly for farmer's market
3. Trails, paved and unpaved for separated users and year-round activities with access to north and south connections
4. Safe and comfortable way across Muldoon to access the park

The workshop concluded after the small group presentations. Power of 10 Activity worksheets that individuals or groups filled out during the workshop were collected by the facilitators and submitted as a comment form. The results of the Power of 10 worksheets are summarized below. The meeting ended at the scheduled time of 7:30 PM.

Submitted Handwritten Comments:

The meeting attendees offered the following written comments through the Power of 10 Activity Handout:

Short Term: "Clean and Green"

Trails and Pathways

- Multi-use pathways and trails for use year-round (bike, hike, cross-country ski, etc.)
- Separated facilities for walkers and bikers
- Natural trails
- Trails along the creek with benches, foot bridges, and salmon viewing opportunities
- Connections to the community and other trails
 - Connection along JBER and to existing North-South trails
 - Adjacent neighborhoods and Windsong Park

Viewpoint of Chugach Mountains

- Area with benches to stargaze and watch aurora
- Distinct area with good signage to direct users here

Access and Connections

- Multiple access points including connection through Windsong Park and adjacent neighborhoods – foot bridges from Early View, Windsong and from front of the park
- Handicap accessible and accessible for all ages
- Locate anticipated popular pedestrian uses closer to Muldoon Road so people do not have to walk longer distances or across parking lots to get to activities
- Safe non-motorized crossing across Muldoon
- Purchase of the Muldoon Estates parcel and area of 14th Street to provide parking and access

Parking

- Multiple parking areas and access points for adjacent community and “external” community
- Use existing parking area in the adjacent mall and Muldoon Community Center/Library
- Lighted parking areas for safety
- Discourage street parking in adjacent neighborhoods for park access

Lighting

- Lighting is needed for safety reasons and to deter unwanted activities
- Trails and parking areas should be lighted

Park Activity Areas

- Children’s Park/play-area/playground
 - Easily accessible from the Boy’s and Girl’s Club, Library, and adjacent residential areas
 - Destination playground similar to Russian Jack park
- Ice-skating Rink
- Sledding Hill
- Skateboard Park
- Bouldering wall (rock climbing)
- Orienteering Activities and Geocache
- Community Gardens
- Arboretum
- Dog Park which is fenced in
- Fire pits, BBQ grills, and hot coal dump bins

Pavilions and Gathering Areas

- Farmer’s Market Location – sheltered or unsheltered
- Picnic Shelters
- Gazebos in eastern half of parcel
- Picnic areas (sheltered or unsheltered) with grills
- Restrooms or pit toilets

Iconic Structure

- Located near the old greenhouse location
- Muldoon logo made of flowers and vegetation
- Pavilion or chalet

Page 5

Environment and Sustainability

- Education opportunities
- Interpretive signs/panels and artwork
- Keep the park natural with wooded areas – resist overbuilding to maintain green space and quiet
- Add landscaping
- Bird watching and berry picking opportunities to be maintained
- Clear brush and ground vegetation to open sightlines for security and safety
- Build Park with sustainable design and materials, trying to use materials already on-site
- Enhance creek fishing and fish viewing opportunities
- Bear-safe waste disposal containers and dog waste disposal bags

Public Art

- Educational interpretive panels
- Take advantage of homestead site for history education
- Alaska Native Heritage Center- incorporate Athabascan culture into iconography of Park

Long Term: “Dream Big”

- Safe crossing of Muldoon to get to the park - pedestrian overpass like on 36th Ave.
- Apple orchard or something similar
- Covered pavilions with fire pits
- Chalet for year-round use with running water, electricity, and restrooms large enough to accommodate multiple families
- Amphitheater
- Farmers Market location with shelters for vendors
- Chester Creek overlooks
 - Dedicate something to Mann Leiser
 - Alaska Native Culture
- All-inclusive playground
- Fenced dog park
- Volleyball courts
- Putting green (golf)
- RV camper spot for a park caretaker
- Zip line – similar to Ocean View Park
- Bike trail loop system that could bring sled dogs to the area and connect to other events like Fur Rondy, Mayor’s Marathon, etc.
- DeBarr Road extension to access parking for park

Page 6

Some comments received specifically stated Park activities, land uses, or qualities they did not want to have as part of the Muldoon Town Square Park, including:

- Community Gardens: too much space is required, produces waste, and requires management and enforcement
- Dog Park – waste is a concern, not family friendly and has noise concerns
- Do not extend Debarr Road
- No sports fields or facilities – noise generators

The Power of 10 Activities worksheet included a question asking what Partners could help realize their vision with a simple question asking attendees "Who else could make the improvements to Muldoon Town Square Park a reality?" The answers that were recorded on the worksheets included:

- Alaska Native Heritage Center
- Contractors, building supply stores, etc. donating their time and resources
- Public volunteers like community groups to clear out and help with construction
- Rasmussen Foundation
- Legislators (apply pressure)
- Anchorage Park Foundation
- Cook Inlet Housing Authority or Regional Corp
- Donations from oil companies

Attachments

- a. Sign in sheet
- b. Meeting Agenda and Park History Handout
- c. Power of 10 Activities Handout

DESIGN CHARRETTE

BETTISWORTH NORTH
ARCHITECTURE PLANNING LANDSCAPE INTERIORS

MEETING SUMMARY

DATE/TIME: October 13th, 2015
LOCATION: Boys and Girls Club (Northeast), Anchorage
TOPIC: Muldoon Town Square Park Master Plan: Design Charrette
PARTICIPANTS: Betsy Chivers, Parks Committee
Stu Grenier, Parks Committee
Kristi Wood, Parks Committee
Carla McConnel, Parks Committee
Kendra Kloster, Parks Committee
Nickel Lafleur, Parks Committee
Marlene Lowrey, Parks Committee
Dana Upton, Parks Committee
Steve Rafuse, MOA/P+R
Taylor Keegan, MOA/P+R
Van Le, R&M Consultants
Taryn Olson, R&M Consultants
Jonny Hayes, Bettisworth North

Meeting Purpose

The goal of the Design Charrette is to spatially organize and describe alternative design solutions for the Muldoon Town Square Park Master Plan that identify uses and activities within Muldoon Town Square Park. The Park Committee is responsible for leading the design exercise and encouraged to work in groups to discuss priorities and placement of park features within, and outside, the park boundaries. The design charrette will directly inform the proposed alternatives for presentation to the public. Additional alternatives or modifications may be required dependent on feedback from partner agencies, neighbors and landowners.

The Design Charrette summary that follows describes the discussions and activities of the meeting as they occurred within the confines of the larger group.

Presentation:

A brief presentation was made to update the Parks Committee with references to the project schedule, the Parks Committee role in representing community interests, and the importance of a collaborative and productive design charrette in order to move the Master Plan forward. The evening agenda was developed for the specific purpose of summarizing the input from the Park Committee and Public as alternative solutions for the Master Plan.

- Site Updates and Workshop Summary:
 - A site inventory and analysis board was provided and briefly summarized. The board includes graphic representations of input provided to date overlaid onto the park aerial. Generally, issues and constraints are represented in red and opportunities were described as green with corresponding labels. Desired access points from off-site, identified trail alignments and internal connections were included as described and understood by the team. The Park Committee Site Tour (SPT) was presented and discussed.
 - The Draft Public Workshop Summary was briefly discussed and (4) copies of the summary were provided at each of the tables. The Priorities as presented by each of the workshop groups were recorded on the Design Charrette Agenda for quick reference. The Short Term and Long Term uses and activities, organized as

345 FRONT STREET FARMBANK, ALASKA 99504
PHONE >> (907) 486-5946 FAX >> (907) 486-5944
1600 DENALI STREET SUITE 700 ANCHORAGE, ALASKA 99503
PHONE >> (907) 460-5946 FAX >> (907) 460-5946
WWW.BETTISWORTHNORTH.COM

common themes, were included on the back of the Agenda for quick reference. A short list of "Do Nots", as they were recorded on comment sheets, was also included for the group to consider.

Design Charrette:

Previously developed aerial and map information boards were posted at easels for participant review prior to the beginning of the presentation and exercise. A site opportunities and constraints board summarizing information and input from the Parks Committee and Public Workshop event was also made available. An agenda that included the evening program, and each of the activities and uses identified for the park, was provided to each of the participants. Four Draft Public Workshop Summaries were made available, one at each charrette table, for review. Four 5'-0" x 2'-0" aerial maps with parcel and topography information were laid out on tables as backgrounds for the design exercise. Packets containing cutouts of each of the activities (community gardens, parking, play, etc.) and the design exercise agenda were provided to participants (100'-0") were provided to participants after the brief presentation to execute the design charrette.



The purpose of the Design Charrette is to ensure that the input and intentions of the Park Committee for the organization and layout of the park activities and uses are clearly recorded. The Park Committee were encouraged to work in groups of 2-3 participants and openly and respectfully discuss the activities and their spatial relationships to one another as well as their fit and appropriateness within the park itself.



A member of the Master Plan technical team was made available at each table to answer questions, provide explanation on activities and uses, and to listen and record discussion.

- Exercise:
 - Four tables were occupied with 1-3 participants each. Each table worked towards developing a park design alternative. The tables generally worked from the West (Muldoon) to the East (JBEX). Additional cutout pieces were created and manipulated as desired and designed to be placed on the table and taped to the table to create a design. A total of four alternatives were developed from three of the tables, with the fourth table generating and describing the park spaces, character and design verbally and recorded on a large note pad.
 - Alternatives were photographed during and after the design exercise and will be recorded by the technical team.
 - Graphics will be generated that represent each table's designs as well as a summary of themes for Park Committee review and comment.
- Table Presentations
 - The larger group gathered around each table to listen to the process and resulting design ideas and results.
 - Each table was provided 5-10 minutes to explain the table design discussions, key factors or justifications and resulting layout or design. Questions and feedback from the larger group were encouraged after the each table presentation. Key points were identified by the technical team.
 - Common Themes:
 - Muldoon: Frontage developed as a visible, active, "inviting" space. Discussion included references to, and positive response to, Chicago's recently completed Ice Ribbon. Ice Ribbon images were provided by Park Committee members prior to the project initiation as possible solution and printed for Design Charrette exercise as reference.
 - Identified as preferred location for Farmers' Market
 - Identified as preferred location for Large/Medium Playground.
 - Identified as preferred location for Pavilion
 - The Hill: Event, Social and gathering spaces commonly identified
 - Specialized recreation opportunities (Bouldering, Sledding)



- Preferred location for "Community Icon" or similar feature, as recognizable to the Park and celebrating character of Muldoon.
- Possible location for Pavilion, Greenhouse, Amphitheater
- The Creek
 - Creek crossings (bridges) identified at:
 - Muldoon Frontage to connect with the Hill parcel,
 - from Hill parcel to east at Boston St.
 - at Windsong Park
 - Early View at southeast access and creek access is strongly desired. Recently completed nature path at Realignment Project Area as example. Accessible locations also suggested.
- Boston Street/Center of Park "Neighborhood or Community Center"
 - Various activities and uses were identified by each table.
 - Elements included:
 - Community Garden,
 - Open (large or small, in ROW or on-site)
 - Bicycle Pump Park
 - Amphitheater
 - Trail extending east
 - Playground
 - Boulderling Wall
 - Stedding Area
 - Orchard
 - Dog Area
 - Skate Park
 - Park Host
- East End
 - Area intended to be generally open and natural with passive recreation opportunities, including trails and viewpoints of Windsong Park, Chester Creek, and the front range of the Chugach Mountains.
 - Activities and Uses included:
 - Open Recreation Area
 - Points of Interest
 - Trails
 - Off-Leash Dog Area
 - Restrooms
 - Restrooms
 - Bicycle Pump Park
 - Connections to future North/South Trail along JBER property line
- General Comments
 - Park Committee desires parking to be located off-site, either in privately owned parcels through shared-parking agreements or within 14th Ave and E. Debarr Road Right-of-Way (ROW).
 - Technical staff discussed parking requirements for activities will be defined per Anchorage Municipal Code, Title 21.
 - Discussions with off-site property owners (Private and MOA ROW) will be required to advance parking strategy as identified by Park Committee. Shared concern with not including parking in Design Alternatives for park activities and uses.



GROUP GENERATED CONCEPT DESIGN ALTERNATIVES





DRAFT CONCEPT DESIGN ALTERNATIVES





BEGICH MS POWER OF 10 SUMMARY

HANDOUT

MULDOON TOWN SQUARE PARK MASTER PLAN

INPUT FOR PUBLIC PLANNING PROJECT INFORMATION

GOAL:

Provide the opportunity for the Planning Team and Park Committee to listen to your input, and understand the needs and wants of Begich Middle School Students to advance the vision for the Muldoon Town Square Park Master Plan.

PROJECT LOCATION:

Fred Meyer

Debar Road

Muldoon Town Square Park

Begich Middle School

Crucial Center Drive

Windsong Park

Muldoon Road

PURPOSE:

The Anchorage Parks and Recreation Department is working closely with the Muldoon Town Square Park Committee. Building with North and R&M Consultants to gather public input to development of the Muldoon Town Square Park Master Plan. The Master Plan will identify uses, activities and features to be considered in the park over the next 20 years. The Planning Team has identified Begich Middle School students as important voices in the development of the park, both in the short term and over the next 20 years, as it will be YOUR park. Please consider sharing your input with the Project team so that the park will be something that you want to visit, share and celebrate. Thank you for your input!

PROJECT SCHEDULE:

Please consider participating at upcoming public involvement opportunities.

1. Parks Committee Meeting
2. Public Meeting #2: Concept Alternatives Review
3. Parks Committee Meeting
4. Northeast Community Council: Plan Approval & Resolution
5. Scenic Footfalls Community Council: Plan Approval and Resolution
6. Public Hearing: Parks and Recreation Commission Meeting
7. Public Hearing: Planning and Zoning Commission Meeting

CONTACT:

Stephen Rafuse (MOA Parks + Recreation, Park Planner)

Van Le (R&M Consultants, Public Involvement)

Jonny Hayes (Bettsworth North, Landscape Architect)

Please continue to back of page...

MOA: The Anchorage School District has not received these notices at the respondent's address in their



RafuseSJ@Muni.org

VLe@R&MConsult.com

JHayes@BettsworthNorth.com

Thursday, October 15th (5:30 - 7pm) @ Northside Boys and Girls Club
 Wednesday, November 4th (5:30 - 7:30pm) @ Begich Middle School
 Thursday, November 18th (5:30 - 7pm) @ NE Boys and Girls Club
 Thursday, December 17th (7pm - 9pm) @ NE Boys and Girls Club
 Thursday, January 7th (7pm - 9pm) @ Westland Baptist University
 Thursday, January 14th (5:30pm) @ Spencer Recreation Center
 Late March - Early April @ Icahn Library

PROJECT HISTORY:

To the Denali Athabaskan people, "Chershtnu" (meaning Grass Creek) was an important fishing site. Copper sedimentation in the headwaters of the creek east of Muldoon Road and south of DeBar. "Chershtnu" was long ago anglicized to "Chester" Creek. It never had anything to do with anyone named Chester.

The late Mann Leiser's Alaska Greenhouse, though privately owned, in its heyday was among the most beloved "parks" in town. East Anchorage residents came there year around to marvel at fish and ducks swimming in the creek, next to nursery stock shrubs and trees. Mann Leiser built a greenhouse over Chester Creek and had a permit to use the Creek for non-potable irrigation purposes. However, he did not use the water from Chester Creek, but developed a private water well and septic system on site instead.

The Leiser family home was on a hill behind the greenhouses. The middle and back portion of the property, which extends to the IBERFORT Richardson boundary, was used as a construction dump for building materials. It is also said to contain debris from the 1964 earthquake. No one knows exactly what's under the surface of the old landfill, or where, but it had long been considered problematic for development for any kind of housing.

After Mann Leiser's death, the Alaska Greenhouse property was sold. A greenhouse collapsed under heavy snow and the U.S. government seized the land from its then owners in a drug case. The Municipality of Anchorage bought it from the federal government in 2006. The Municipality designated the eastmost 12 acres as a yet-to-be-developed Muldoon Community Park; the Muldoon Road frontage was to be sold for commercial development to recoup its investment.

The Northwest Community Council had long sought the entire property, including the frontage, for a "Muldoon Park Strip" to bring needed green space to Anchorage's most densely populated area. A big green park fronting on Muldoon Road would help define a Muldoon "town center," as envisioned in the Anchorage 2020 Comprehensive Plan. The property was later sold to the Municipality in 2006 for \$5 Million.

The East Anchorage District Plan, initiated in March 2012 and adopted by the Anchorage Assembly December 2, 2014, designated all 29 acres of the property for a community park. Also in 2012, the Municipality received a \$2 million federal grant to re-align Chester Creek at Muldoon Rd. The project, which will be completed in fall 2015, is aimed at improving water quality and fish passage. The Northeast and Scenic Footfalls Community Councils vigorously opposed the planned realignment of Chester Creek while the East Anchorage District Plan was still being developed. The creek was realigned over their objections.

The 2014 East Anchorage District Plan identifies a "small area planning process" and "development plan" for the Muldoon Town Square Park property as one of the community's Top 5 Priority Actions. As a result of years of dedicated community efforts and in support of the implementation of the district plan, the Anchorage Assembly voted to pass AO 2015-17 and dedicate the entire old Alaska Greenhouse site as park land for "permanent public park and recreational purposes" at a public hearing July 14, 2015.

History provided by Park Committee Members: Jennifer Lowrie, Rachel Wood, and David Ulfrey. Art and Layout by Stephen Hayes

PROJECT SITE:

<http://www.muni.org/Departments/Parks/Pages/MuldoonCommunityParkMasterPlan.aspx>



Thank You for your participation and continued support!

WORKSHEET EXAMPLE

Tydonia Moore

MULDOON TOWN SQUARE PARK MASTER PLAN

PUBLIC PLANNING WORKSHOP



OBJECTIVE:

To identify OPPORTUNITIES and ACTIVITIES for year round use of Muldoon Town Square Park

SHORT TERM: "Clean + Green"

What are 10 things that you would do to improve the Park that could be done right away that would not cost a lot?

1. Basketball
2. Really long lucky slide
3. Swings in a circle
4. bridge for dogs
5. a little dog park
6. by the river
7. (for people don't have to stand there they can use them)
- 8.
- 9.
- 10.

Please continue to back of page...

SUMMARY OF RESULTS

MULDOON TOWN SQUARE PARK MASTER PLAN DRAFT Begich Middle School Power of 10 Summary Results

Begich Middle School Student's Power of 10 Priorities, based on number of times an activity or park aspect was listed in the responses.

Priority No.	Short Term	No. of responses	Long Term	No. of responses
1	Bathrooms – not portables	24	Playground	8
2	Trash Cans and recycling bins	14	Plant more trees	7
3	Playground	13	Water Park/Slides	6
3	Lake/Pond	13	Indoor Pool and Hot tub	6
4	Tree House	12	Sand Box	5
5	Green Grass Field	11	Trampolines	5
5	Basketball Court	11	Safe and Secure	4
5	Benches	11	Long/Big Slide	4
6	Flowers	10		
6	Keep it Clean	10		
6	Trees – plant them and to climb	10		
7	Food Available (multiple categories)	25		

Power of 10 Results: numbers in parenthesis indicate the number of students who included that activity or park aspect in their response.

Power of 10 Notes	Short Term	Long Term
For people who don't have to hold their dog so they can see them play	1. A little dog park by the regular park	Art Station (2)
For wildlife	2. A lot of woods (4)	Basketball hoops (4)
	3. Alligator	Big Football field
	4. Amusement Park	Big Paintball field
	5. Animal Slide	Big Pizza Store
	6. Baby swings (4)	Bike trails (2)
	7. Basketball Court	Biking
	8. Baseball field (5)	Bridge over river
Not porta-potties	9. Bathrooms (24)	Campsites
6 park benches along the playground	10. Benches (11)	Cyber jets
	11. Big Park	Flower Garden
	12. Bike riding	Flying cars
	13. Bike Store	Foam pits to jump in
	14. Bike track & Bike area (concrete to ride bikes)	Forts

SUMMARY OF RESULTS (CONTINUED)

MULDOON TOWN SQUARE PARK MASTER PLAN
DRAFT Begich Middle School Power of 10 Summary Results

15.	Bird fountain	(2)	Free rescued or wounded animals into woods
16.	Bouncy floors	(2)	Gazebo
17.	Bridge	(7)	Get rid of junk food restaurants and grow more trees to make park bigger
18.	Bridge for dogs		Go Cart (3)
19.	Bridges for jungle gym		Holidays in the Park
20.	Burger stand		Long swirl slide (4)
21.	Campsite		Medical station (2)
22.	Carnival every month		Mini sauna
23.	Cars that people push you around		Mini store for goods (2)
24.	Chocolate fountain		New games system
25.	Concrete/Gravel trails	(2)	New planes
26.	Covered picnic area	(3)	No hunting so animals stay safe (2)
27.	Dinosaur Slide		No smoking & must be followed (so animals stay safe) (2)
28.	Dog poop station with bags	(2)	Parking lot (3)
29.	Dog walking park	(8)	Picnic spots
30.	Donation box for animals		Plant Day
31.	Drinking Fountain	(5)	Plant more trees (7)
32.	Enclosed area for shade	(2)	Playground (8)
33.	Equipment Shop		Playground so wheelchairs can go up
34.	Fake animals		Playing fields (2)
35.	Farmer's Market		Pool and hot tub indoors (6)
36.	Fishing in the creek/river		Public bathrooms (2)
37.	Flowers	(10)	Robot
38.	Food court/stand	(10)	Safe and Secure (4)
39.	Food trucks	(2)	Sand box (5)
40.	Football Field	(5)	Sidewalk through park with handprints of the workers who built it
41.	Free, no charge		Sledding Hill
42.	Fruit Market		Snowboard and ski hill
43.	Games store/board games and video games		Statue of Anchorage animals
44.	Giant ice cream slide		Swing Set (2)
45.	Go Cart Track	(2)	Trampolines (5)

2

MULDOON TOWN SQUARE PARK MASTER PLAN
DRAFT Begich Middle School Power of 10 Summary Results

To cover dirt so when it rains it is not muddy	46.	Green Grass field	(11)	Visitor Center (a little ways from the park)
	47.	Gym for working out		Water Park/Water Slide (6)
	48.	Handle bars		Wax Station
	49.	History		Well
	50.	Hockey Rink	(3)	Ziplines (2)
	51.	Hotel for 10 and up with trampoline		Zumiez (store)
	52.	Ice Cream Stand	(10)	
	53.	Ice Rink	(6)	
Wifi	54.	Internet		
	55.	Jump Park/Trampolines	(3)	
	56.	Jungle Jim	(4)	
	57.	Keep clean	(10)	
	58.	Kid safe zones		
	59.	Lake/Pond	(13)	
For fish & swimming	60.	Little Food Cart (Free Food)	(4)	
	61.	Long Boarding Track		
	62.	Make it fun		
	63.	Milk Shake Restaurant		
	64.	Mine (Craft) hotel for kids		
	65.	Mine (Craft) station that you can go inside		
	66.	Mini Statue of Lady Liberty		
	67.	Monkey Bars		
	68.	No fences or construction tools		
	69.	No mud slides or falling rocks		
	70.	No Shooting Sign		
	71.	No telephone wires		
	72.	Paint ball	(2)	
Make it away from park to avoid acids (spills)	73.	Parking lot	(2)	
	74.	Parkour Park	(3)	
	75.	Pet Shop		
	76.	Petting Zoo		
	77.	Picnic Table	(6)	
	78.	Pizza Place		
	79.	Place for geese		
	80.	Place for studying	(2)	
	81.	Place to listen to music		
Native to Alaska	82.	Plants	(3)	
	83.	Playground	(13)	
	84.	Playhouse under the		

3

	playground	
	85. Pool	(5)
	86. Porch	
	87. Really long twisty slide	(2)
	88. Recycling bins	(3)
	89. River	(6)
	90. Rock climbing wall	(3)
With safety gear	91. Roller Rink	
	92. Roller Skating	
	93. Rubber underneath playground and make a safe spot for toddlers	
	94. Seesaw	
	95. Sidewalk	(5)
	96. Skate Park	(7)
	97. Sledding Hill	(8)
	98. Small Candy Store	(2)
	99. Soccer Field	(4)
	100. Solar Panels	
	101. Space Ship	
	102. Sport Courts	
	103. Sport fields	
	104. Stores or Mini Store for goods	(3)
	105. Swings	(9)
	106. Table and chairs	
	107. Tennis Court	(4)
	108. Tetherball	
	109. Tire swing	(2)
	110. Track (to run)	(9)
	111. Trail for running	(4)
	112. Trail Sign	
	113. Trails in the woods	(2)
	114. Trash Cans	(14)
	115. Tree House	(12)
	116. Trees (to climb)	(10)
To make more oxygen	117. United flag	
	118. Concession/Vending Machines	(3)
	119. Volcano	
	120. Volleyball courts	
	121. Walking in the forest	(3)
	122. Walkway	
	123. Water fall	
	124. Water fountain	(9)

5

[illegible]


ONLINE SURVEY RESULTS

Muldoon Town Square Park

Rate your priorities for future investments and improvements at Muldoon Town Square Park?

Answer Options	Highest Priority	Medium Priority	Low Priority	Rating Average	Response Count
Amphitheater	18	27	28	3.02	213
Aboretum or Orchard	26	44	22	3.23	213
Basketball	11	29	39	3.71	211
Bicycle Pump Course	10	25	39	3.37	217
Bouldering Climbing Area	10	25	34	3.37	217
Children's Play Area or Playground	114	47	7	1.88	217
Community Garden	63	46	20	2.57	213
Farmer's Market	43	54	15	2.92	212
Ice Skating Rink	44	50	18	2.92	212
Library and/or Community Room	55	38	26	2.97	215
Multi-use Pathways for year round use	154	33	13	1.60	220
Off-leash Dog Park (fenced)	50	42	7	2.65	213
Open Recreation Fields	50	59	20	3.00	213
Orienteering Activities and Geocache	17	37	62	3.43	212
Parking lot	50	45	23	2.80	213
Picnic Areas	17	37	48	3.05	213
Steeple Hill	11	29	46	3.37	209
Other (please specify)	50	59	24	2.63	214

answered question
skipped question



Highest Priority


Multi-use Pathways for year round use	154
Children's Play Area or Playground	114
Farmer's Market	93
Community Garden	63
Library and/or Community Room	55
Open Recreation Fields	50
Off-leash Dog Park (fenced)	50
Steeple Hill	46
Ice Skating Rink	44
Aboretum or Orchard	44
Bouldering Climbing Area	42
Amphitheater	42
Orienteering Activities and Geocache	37
Basketball	39
Skateboard Park	11

Muldoon Town Square Park

New rank your top 5 priorities for future investments and improvements at Muldoon Community Park?

Answer Options	(1) Highest Priority	(2) 2nd Priority	(3) 3rd Priority	(4) 4th Priority	(5) 5th Priority	Rating Average	Response Count
Amphitheater	3	12	7	4	6	2.94	32
Aboretum or Orchard	10	1	10	9	18	3.50	48
Basketball	2	2	1	5	5	3.60	15
Bicycle Pump Course	24	2	3	2	6	2.03	37
Bouldering Climbing Area	3	14	8	12	3	2.95	40
Children's Play Area or Playground	52	22	21	15	14	2.33	124
Community Garden	21	14	17	14	9	2.51	160
Farmer's Market	10	30	17	17	9	2.51	160
Ice Skating Rink	10	9	9	12	8	2.98	48
Library and/or Community Room	10	12	19	10	6	2.82	57
Multi-use Pathways for year round use	37	40	27	22	16	2.58	142
Off-leash Dog Park (fenced)	11	14	8	14	15	3.13	62
Open Recreation Fields	4	6	5	18	12	3.62	45
Orienteering Activities and Geocache	1	2	5	4	7	3.74	19
Parking lot	9	13	15	4	15	3.05	56
Picnic Areas	3	11	18	25	19	3.61	76
Steeple Hill	0	5	2	6	5	3.61	18
Other (please specify)	0	1	15	12	27	4.18	55

answered question
skipped question




Top 5

Priority	Response Count
1	142
2	124
3	100
4	76
5	67
6	62
7	57
8	56
9	55
10	48
11	45
12	40
13	37
14	32
15	19
16	18
17	15

Muldoon Town Square Park

What is the preferred way you will travel to or access the park?

Answer Options	Response Percent	Response Count
Personalized motorized vehicle	49.3%	110
Public transportation	1.3%	3
Bicycle	26.5%	59
On foot or as a pedestrian	20.6%	46
Other (please specify)	2.2%	5
answered question		223
skipped question		0



Muldoon Town Square Park

What would inspire you to visit this park year-round?

Answer Options

answered question

skipped question

Response Count

110

3

59

46

5

223

0

answered question

skipped question

Response Count

110

3

59

46

5

223

0

answered question

skipped question

Response Count

110

3

59

46

5

223

0

answered question

skipped question

Response Count

110

3

59

46

5

223

0

answered question

skipped question

Response Count

110

3

59

46

5

223

0

answered question

skipped question

Response Count

110

3

59

46

5

223

0

answered question

skipped question

Response Count

110

3

59

46

5

223

0

Muldoon Town Square Park

What feature or characteristics of East Anchorage (Muldoon) is most worthy of celebration?

Answer Options

Number Response Date Response Text Response Count

1 125

2 78

3 125

4 78

5 125

6 78

7 125

8 78

9 125

10 78

11 125

12 78

13 125

14 78

15 125

16 78

17 125

18 78

19 125

20 78

21 125

22 78

23 125

24 78

25 125

26 78

27 125

28 78

29 125

30 78

31 125

32 78

33 125

34 78

35 125

36 78

37 125

38 78

39 125

40 78

41 125

42 78

43 125

44 78

45 125

46 78

47 125

48 78

49 125

50 78

51 125

52 78

53 125

54 78

55 125

56 78

57 125

58 78

59 125

60 78

61 125

62 78

63 125

64 78

65 125

66 78

67 125

68 78

69 125

70 78

71 125

72 78

73 125

74 78

75 125

76 78

77 125

78 78

79 125

80 78

81 125

82 78

83 125

84 78

85 125

86 78

87 125

88 78

89 125

90 78

91 125

92 78

93 125

94 78

Muldoon Town Square Park

What feature or characteristics of East Anchorage (Muldoon) is most worthy of celebration?

Answer Options

Number Response Date Response Text Response Count

1 125

2 78

3 125

4 78

5 125

6 78

7 125

8 78

9 125

10 78

11 125

12 78

13 125

14 78

15 125

16 78

17 125

18 78

19 125

20 78

21 125

22 78

23 125

24 78

25 125

26 78

27 125

28 78

29 125

30 78

31 125

32 78

33 125

34 78

35 125

36 78

37 125

38 78

39 125

40 78

41 125

42 78

43 125

44 78

45 125

46 78

47 125

48 78

49 125

50 78

51 125

52 78

53 125

54 78

55 125

56 78

57 125

58 78

59 125

60 78

61 125

62 78

63 125

64 78

65 125

66 78

67 125

68 78

69 125

70 78

71 125

72 78

73 125

74 78

75 125

76 78

77 125

78 78

79 125

80 78

81 125

82 78

83 125

84 78

85 125

86 78

87 125

88 78

89 125

90 78

91 125

92 78

93 125

94 78

Muldoon Town Square Park

What feature or characteristics of East Anchorage (Muldoon) is most worthy of celebration?

Answer Options

Number Response Date Response Text Response Count

1 125

2 78

3 125

4 78

5 125

6 78

7 125

8 78

9 125

10 78

11 125

12 78

13 125

14 78

15 125

16 78

17 125

18 78

19 125

20 78

21 125

22 78

23 125

24 78

25 125

26 78

27 125

28 78

29 125

30 78

31 125

32 78

33 125

34 78

35 125

36 78

37 125

38 78

39 125

40 78

41 125

42 78

43 125

44 78

45 125

46 78

47 125

48 78

49 125

50 78

51 125

52 78

53 125

54 78

55 125

56 78

57 125

58 78

59 125

60 78

61 125

62 78

63 125

64 78

65 125

66 78

67 125

68 78

69 125

70 78

71 125

72 78

73 125

74 78

75 125

76 78

77 125

78 78

79 125

80 78

81 125

82 78

83 125

84 78

85 125

86 78

87 125

88 78

89 125

90 78

91 1

AGENCY COORDINATION MEETING



R&M CONSULTANTS, INC. | 9101 Vanguard Drive • Anchorage, AK 99507 • 907.532.1707
3514 Industrial Avenue • Fairbanks, AK 99701 • 907.452.5270
9171 Andrus Road • Kodiak, AK 99581 • 907.240.9424

Agency Coordination Meeting Summary

Project Number:	2320.01 (R&M)		
Project Title:	MOA Parks and Recreation Muldoon Town Square Park Master Plan		
Subject:	Muldoon Town Square Park Master Plan Agency Coordination Meeting		
Author:	Van Le, AICP - R&M Consultants, Inc.		
Meeting Location:	MOA Planning Conference Room 170		
Meeting Date:	Thursday, October 22, 2015		
Meeting Outreach:	Agency Email Invitation by Parks and Recreation Department		
Meeting Materials:	PowerPoint Presentation, Aerial Maps, Agenda		
Distribution Date:	Internal Review Version – Public Distribution TBD		
Meeting Attendance:	21 Attendees (sign in)		
Attendees:	Steve Rafuse Taylor Keegan Jonny Hayes, ASLA Van Le, AICP	Project Manager Park Planner Landscape Architect Planner	MOA Parks & Rec MOA Parks & Rec Bettisworth North R&M Consultants
	Nickel LaFleur Dave Ulmer Stu Grenier Genevieve Holubik Kendra Kloster Jerrienne Lowther	Park Committee Park Committee Park Committee/NECC Park Committee Park Committee Park Committee	
	Jeff Urbanus Vivian Underwood	MOA Watershed Mgmt. MOA AMATS	
	Lori Schanche	Transportation Planning MOA Non-Motorized Transportation	
	Russell Oswald, PE Jennifer Noffke Francis McLaughlin	MOA PM&E MOA PM&E MOA Planning	

Stephanie Mormilo	MOA Traffic Engineer
Randy Bergt	MOA Transit
Sharon Ferguson	MOA Planning
Scott Thomas, PE	DOT Traffic Engineer
Jonathon Knowles	DOT Traffic

See also Sign In Sheet

Meeting Summary

The Agency Coordination meeting was programmed to start at 2:30 p.m.

Jonny began the meeting by introducing the project team. Introductions for all attendees and representative organizations followed. Jonny provided a project overview using a PowerPoint presentation. Topics covered included:

- Park History
- Project Schedule
- Site information including photographs of the existing park and Chester Creek realignment project
- Design Alternatives summary from the Park Committee work last week
- Discussion/Issues Topics

The following handouts were available to meeting attendees:

- Power of 10 Activities Summary from Begich Middle School Students
- Design Charrette Concepts Summary for 4 Alternatives developed at the Park Committee Design Charrette on October 13, 2015.

Discussion and Questions

Parking and Vehicular Access into the Park

- See also On-Street Parking along Debarr below.
- Parking requirements will depend on activities and uses programmed for the Park.
- Farmer's Market is vehicle/driving/transporting intensive and may require 100-150 parking spots

14th Avenue Right-of-Way

- 14th Ave currently has 55 feet of right-of-way
- Potential access to the Park from the south
- Need to provide parking
- Need to provide a crossing over Chester Creek, potentially pedestrian only

- Angled on-street parking is typically not permitted within MOA right-of-way
- Street maintenance will not support a hammerhead dead end configuration along 14th Ave as they cannot plow snow
- Need to determine what cul-de-sac width is

Debarr Extension

- Is identified in the Official Streets and Highways Plan 2014, but it is not on a prioritized list of projects that will be funded and completed in the next 20 years or beyond.
- Chester Creek realignment is partially within the Debarr ROW, grade issues as Debarr approaches Boston Street.
- Access to Park will need to be on Boston Street or off Muldoon Road
- NECC wants Debarr Road vacated but some residents want it to be extended for access into the Park and to the neighborhood.

On-Street Parking along Debarr Road (Boston Street to Cross Pointe Loop)

- Insufficient right-of-way to allow on-street parallel or angled parking on one side of roadway.
- Currently on-street parking is prohibited with No Parking Signs posted along the south side of Debarr between Boston and Cross Pointe Loop.

Access from Muldoon

- Currently 30,000 vehicles use Muldoon Road daily
- Moving 30,000 vehicles per day on one roadway requires limiting new conflicts and managing existing conflicts to traffic flow such as direct access off of Muldoon
- DOT's policy is to allow right in, right out only access for parcels adjacent to Muldoon Road.
- Additional development along Muldoon Road within the vicinity of the Park will require more access management in the near term (5-6 years)
- Within 5-6 years, Muldoon Road will need median placement for access management.
- Median project is not yet budgeted or programmed.
- **Debarr Road and Muldoon Intersection:**
 - DOT would not support extending Debarr Road east just for 10 parking spots
 - Changing the intersection there for a 4th leg would also mean a huge public investment for an anticipated fewer than several thousand cars that would use that extension (if it were extended).
 - Adding a 4th leg at the intersection would mean increased delay at that intersection which is already significant. The additional delay would mean delays at other locations along Muldoon Road.
 - Intersection investment could cost approximately \$2 million, just for intersection upgrades to allow for that 4th leg for park access.

Page 3

- If a future extension of Debarr Road continues to Boston Street (and does not just end at the Mall), could potentially be a much larger and more expensive investment.
- A Traffic Impact Analysis (TIA) will be required to determine if that 4th leg (Debarr Extension) is warranted.
- DOT prefers that nearby, existing signalized intersections be used first before creating new ones.

Bike and Pedestrian Connections

- Trails need to be set back from the creek a minimum of 15 feet if they are soft, unpaved trails
- Trails built at-grade are ok in the floodplain
- Boardwalk trails are also ok
- Trail along east boundary of Park along JBER is proposed in the Trails Master Plan; however, no further planning is underway at this time.
- Pedestrian links needed from Windsong Park and neighborhood to the south of the Park

Access to Transit

- **Short term:** Transit is moving its existing Fred Meyer's stop to Debarr Road
- **Long-term:** new transfer/transit hub facility for the Muldoon area

Park Development and Compatibility with Chester Creek and Wetlands

- Creek alignment into the Debarr ROW was the Army Corps of Engineer's decision
- Creek not showing on the Alternatives Summary graphic in its correct position. Chester Creek alignment is within the Debarr right-of-way.
- Fish and Game does not need Parkland for Chester Creek for flood overflow area.

"Town Center" development and the Park's Role

- Town Center as depicted in Anchorage 2020 Comprehensive Plan has not materialized especially with Big Box store development in the area versus mixed use buildings and a more walkable area.

Future Park and Road Maintenance

- Vehicular access for maintenance of trash cans, restrooms (if any) and trails is important.
- Snow removal of parking needs maneuvering room for plow vehicles.

Zoning & Platting

- New Title 21 Land Use Code
- If Community Use Park, then Planning and Zoning Commission Review/Approval is required

Page 4

- Need to research Plat notes to see what restrictions or conditions are placed on the parcels
- B3SL and R2M Zoning Districts permit Parks but the actual uses will determine what level of service will be required for parking etc.

Schedule and Funding

- Aggressive schedule to meet deadline to be able to spend state grant funding on capital improvements by June 2016.
- Plan needs to be drafted by December 2015 and approved by the Planning and Zoning Commission by April 2016.
- Parks and Recreation has \$1 Million until June 2016 (state grant) and another \$500K for park improvements.
- After Master Plan is adopted, the Park can apply for Rasmuson Challenge Grants through the Anchorage Park Foundation.

Activities and Park Uses

- *Will farmer's market be permanent year round structure or seasonal?*
 - Seasonal farmer's market
- *What active recreation activities are planned? Basketball, soccer, football?*
 - Begich Middle School is a ¼ mile away and meets the needs for active recreation facilities
- Uses will determine how much on-site parking is required.

Site Development

- As site is developed, changes in drainage will need to be addressed

Attachments

- a. Sign in sheet
- b. Meeting Agenda

RECORDED PLAT AND LAND USE



Legend

- Muldoon Town Square Park
- Windson Park [PLI]
- Residential [R2-M]
- Commercial [B-3]
- Commercial [B-3SL]
- JBER [T]



PUBLIC WORKSHOP #2



R&M CONSULTANTS, INC.
 9101 Vanguard Drive • Anchorage, AK 99507 • 907.522.1707
 5904 Industrial Avenue #102 • Fairbanks, AK 99701 • 907.452.5270
 9737 Muld Bay Road # 313 • Kotzebue, AK 99503 • 907.220.9434

Public Workshop #2 Summary

Project Number:	2320.01 (R&M)		
Project Title:	MOA Parks and Recreation Muldoon Town Square Park Master Plan		
Subject:	Muldoon Town Square Park Master Plan Public Workshop #2		
Author:	Van Le, AICP & Taryn Oleson, R&M Consultants, Inc.		
Meeting Location:	ASD Begich Middle School, Multi-Purpose Room		
Meeting Date:	Wednesday, November 4 th , 2015		
Meeting Outreach:	Parks And Recreation Department Outreach		
Meeting Materials:	Meeting Agenda and Park History Handout, Public Workshop 1 Draft Vision Statement, Design Alternative Exercise materials		
Distribution Date:	Internal Review Version – Public Distribution TBD		
Meeting Attendance:	29 Attendees (sign in)		
Attendees:	Steve Ratuse Taylor Keegan	Project Manager Park Planner	MOA Parks & Rec MOA Parks & Rec
	Jonny Hayes, ASLA	Landscape Architect	Beltisworth North
	Van Le, AICP Taryn Oleson	Planner Planner/PI Coordinator	R&M R&M
	See also Sign In Sheet		

Meeting Information

The public workshop was advertised to start at 5:30 p.m. Several attendees arrived early and spoke with the Project Team about the Park. The meeting was Workshop style with a formal presentation at the beginning of the meeting. The room was set up to allow for free movement of attendees with easels displaying aerial imagery of Muldoon Town Square park site, online survey results, and products from the first public workshop and Parks Committee Design Charrette. Ten round tables were set up with workshop materials including agenda and draft vision statement handouts, a marker and large post-it paper (see attached graphics).

A welcome table with sign-in sheets, handouts and a comment box was set up near the entrance of Begich Middle School's multi-purpose room. Refreshments and a kids' coloring station were also available near the entrance to the room.

The following handouts were available to meeting attendees:


- Meeting Agenda and Park History Handout
- Public Planning Workshop 1 Draft Vision Statement
- Design Alternatives Exercise Handout

Workshop

The public workshop began with a presentation given by Steve Ratuse, Jonny Hayes and Van Le. The presentation included the public process and purpose of the workshop, the project timeline, existing conditions, and the results of public involvement to date. Van discussed the draft vision statement that was produced from the results of the first public planning workshop and requested attendees to record and submit any changes they would like to make to the vision statement.


Steve presented the results of the online survey, as of Monday, November 2nd, 2015, that included individual's identified priorities and modes of travel to the park. Jonny then presented the results of the Parks Committee Design Charrette and Agency Coordination meeting and how those meetings shaped the design alternatives this workshop will be using. The public workshop exercise was then explained as Taryn and Van handed out folders containing design alternatives for the exercise.

The design exercise identified distinct alternatives for three main sections of the park: the western Muldoon Road frontage segment (simply titled "Muldoon"), the far eastern part of the park ("Chugach"), and the center area of the park ("Core"). Each section of the park had four alternatives, for a total of 12 different design pieces. Jonny presented each of the alternatives, providing more detailed explanation for each of the four Muldoon segment alternatives to introduce the concepts and describe common key attributes. Following the presentation, attendees formed groups and were tasked with taking the 12 design segments and designing their preferred alternative, consisting of one Muldoon,



Core, and Chugach segment stitched together to create an preferred master plan alternative. Members of the project team served as facilitators and were readily available to answer questions as they arose.

Any amendments to a segment of their preferred alternative were recorded on large blue post-its available at each table graphically made on the workshop exercise lasted about 40 minutes. Following the exercise, a representative from each table came forward to show and explain their group's preferred alternative, including any amendments or clarifications to everyone in attendance. As they presented, Jonny recorded the three chosen segments for each preferred alternative.



The workshop concluded after the group presentations. Notes recorded on the preferred alternatives and the draft vision statement edits were collected. The results of the design exercise are summarized below. The meeting ended at the scheduled time of 7:30 PM.

Design Exercise Result:

Preferred Alternatives by Segment

Table/Group	Selected Segment Alternative	
	Muldoon	Core
A	2.0	2.0
B	2.0	2.0
C	2.0	4.0
D	2.0	1.0
E	4.0	1.0
F	2.0	2.0
		Chugach
		1.0
		3.0
		4.0
		1.0
		4.0
		2.0

Each preferred alternative generated presented minor modifications to the designs presented, including:

Table "A" notes:

- Muldoon 2
 - Vacant northwest parcel could be a library
 - Like temporary parking
 - Would like safe stream access from parking
 - Play area – should have edge (depression or fence) that promotes safety
 - Amphitheater – may not be needed or need to ensure use first
- Core 2
 - Restrooms

- Dog park with parking access
- More parking
- Playground closer to the community gardens
- Chugach 1
 - Windsong access
 - Open play environment (without actual structure)

Table "B" notes:

- Muldoon 2
 - Add a sledding hill
 - Pedestrian overpass to cross Muldoon Road
 - Ask the owner of the small vacant northwest parcel to donate the land for a tax write-off
 - Buy the property south of 14th avenue for parking
- Core 2
 - Make parking lot smaller – 50 cars is plenty large
 - Add an orchard or arboretum east of the picnic and play area
- Chugach 3
 - Add fenced dog park to open space

Table "C" notes:

- Muldoon 2
 - Add pavilion feature shown in Muldoon 1
- Core 4
 - Add dog park near community garden
 - Add additional access to Windsong Park
- Chugach 4
 - Add additional access to Windsong
- General suggestion
 - Add volleyball courts
 - Right turn lane off Muldoon Road if possible into park
 - Protected left turn lane off Muldoon Road into the park
 - No tennis

Table "D" notes:

- Muldoon 2
 - Increase distance between parking (impervious surfaces) and the creek to maintain stream health
 - No amphitheater
 - Nature walk through the hill/trails with interpretive signs
 - No sledding hill
 - If parking is not needed in the frontage, put some picnic tables along the creek or other things to celebrate the creek
- Chugach 1
 - Remove parking in rear parcel

Table "E" notes:

- Core 1

- Remove the pump track
 - Relocate community gardens to the south side of the parcel for more direct sunlight
- Chugach 4
 - Add connections/access to Windsong park and neighborhood as is shown in the Chugach 3 alternative

Table "F" notes:

- Core 2
 - Add pump track west of the picnic areas and rock wall/play area
- Chugach 2
 - Move dog park farther west so it's between the Core and Chugach areas
 - Have open area be larger to include where dog park was originally shown
 - Add 25-40 stalls of parking along Debarr Road/park boundary east of the Cross Point/Debarr intersection

Submitted Draft Vision Statement Comments:

The meeting attendees offered the following written comments on the Public Planning Workshop 1 Draft Vision Statement:

"Muldoon Town Square Park is a gathering place and destination for East Anchorage and the greater community where families and people of all ages and abilities can access and participate in healthy park activities in a safe, clean and comfortable environment in a unique and beautiful setting."

- Replace "East Anchorage" with "the community of Muldoon and East Anchorage at large..."
- Add something that emphasizes the natural setting and natural environment

Attachments

- Sign in sheet (Available Upon Request)
- Meeting Agenda and Park History Handout
- Public Planning Workshop 1 Draft Vision Statement
- Design Alternative Exercise materials
- Preferred Alternative Workshop Results, as presented

MULDOON TOWN SQUARE PARK MASTER PLAN

PUBLIC PLANNING WORKSHOP AGENDA + PROJECT INFORMATION

MEETING GOALS:

Inform participants of project progress and provide opportunities to engage in respectful dialogue to advance the Preferred Alternative and Vision for Muldoon Town Square Park.

EXPECTED MEETING OUTCOMES:

- Confirm Input Received to Date
- Identify Preferred Master Plan Configuration(s)

AGENDA:

Wednesday, November 4th, 2015 | Begich Middle School Multipurpose Room | 5:30p - 7:30

5:30 - 5:45 Welcome

5:46 - 6:15 Presentation

6:16 - 7:00 Workshop Exercise

7:01 - 7:15 Group Reports

7:16 - 7:30 Next Steps

Familiarize with Project and Site, Chat with Neighbors
Public Input Results and Design Charette Alternatives Review
Evaluate Alternatives and Share Park Vision in Facilitated Group Setting
Listen to Groups' Preferred Alternatives and Vision Statements
Adjust and Advance Preferred Alternative for Public Approval Process

PROJECT SCHEDULE:

Please consider participating at upcoming public involvement opportunities.

- Parks Committee Meeting**
Thursday, Nov. 19th (5:30-7pm) @ NE Boys and Girls Club
- Northeast Community Council: Approval & Resolution**
Thursday, Dec. 17th (7pm-9pm) @ NE Boys and Girls Club
- Scenic Foothills Community Council: Approval and Resolution**
Thursday, Jan. 7th (7pm-9pm) @ Wayland Baptist University
- Public Hearing: Parks and Recreation Commission**
Thursday, Jan. 14th (6-9pm) @ Spenard Recreation Center
- Public Hearing: Planning and Zoning Commission**
Late March – Early April @ Loussac Library

CONTACT:

Stephen Rafuse [MOA Parks + Recreation, Park Planner]
RafuseSJ@Muni.org
Van Le [R&M Consultants, Public Involvement]
VLe@RMConsult.com
Jonny Hayes [Bettisworth North, Landscape Architect]
JHayes@BettisworthNorth.com

Please continue to back of page...



PROJECT HISTORY:

To the Deni'ina Athabaskan people, "Chanishnu" (meaning Grass Creek), was an important fishing site. Coho salmon spawn in the headwaters of the creek east of Muldoon Road and south of DeBarr. "Chanishnu" was long ago anglicized to "Chester" Creek, it never had anything to do with anyone named Chester.

The late Mann Leiser's Alaska Greenhouse, though privately owned, in its heyday was among the most beloved "parks" in town. East Anchorage residents came there year around to marvel at fish and ducks swimming in the creek, next to nursery stock shrubs and trees. Mann Leiser built a greenhouse over Chester Creek and had a permit to use the Creek for non-potable irrigation purposes. However, he did not use the water from Chester Creek, but developed a private water well and septic system on site instead.

The Leiser family home was on a hill behind the greenhouses. The middle and back portion of the property, which extends to the JBER/Port Richardson boundary, was used as a construction dump for building materials. It is also said to contain debris from the 1964 earthquake. No one knows exactly what's under the surface of the old landfill, or where, but it had long been considered problematic for development for any kind of housing.

After Mann Leiser's death, the Alaska Greenhouse property was sold. A greenhouse collapsed under heavy snow and the U.S. government seized the land from its then owners in a drug case. The Municipality of Anchorage bought it from the federal government in 2006. The Municipality designated the easternmost 12 acres as a yet-to-be-developed Muldoon Community Park; the Muldoon Road frontage was to be sold for commercial development to recoup its investment.

The Northeast Community Council had long sought the entire property, including the frontage, for a "Muldoon Park Strip" to bring needed green space to Anchorage's most densely populated area. A big green park fronting on Muldoon Road would help define a Muldoon "town center," as envisioned in the Anchorage 2020 Comprehensive Plan. The property was later sold to the Municipality in 2006 for \$5 Million.

The East Anchorage District Plan, initiated in March 2012 and adopted by the Anchorage Assembly December 2, 2014, designated all 29 acres of the property for a community park. Also in 2012, the Municipality received a \$2 Million federal grant to re-align Chester Creek at Muldoon Rd. The project, which will be completed in fall 2015, is aimed at improving water quality and fish passage. The Northeast and Scenic Foothills Community Councils vigorously opposed the planned realignment of Chester Creek while the East Anchorage District Plan was still being developed. The creek was realigned over their objections.

The 2014 East Anchorage District Plan identifies a "small area planning process" and "development plan" for the Muldoon Town Square Park property as one of the community's Top 5 Priority Actions. As a result of years of dedicated community efforts and in support of the implementation of the district plan, the Anchorage Assembly voted to pass AO 2015-17 and dedicate the entire old Alaska Greenhouse site as park land for "permanent public park and recreational purposes" at a public hearing, July 14, 2015.


- History provided by Park Committee Members: Jennifer Lowther, Kristi Wood, and David Umer. Additional Content by Stephen Palouse

PROJECT SITE: <http://www.muni.org/Departments/parks/Pages/MuldoonCommunityParkMasterPlan.aspx>



Thank You for your participation and continued support!


Attachment C



CONCEPT DESIGN ALTERNATIVES

LEGEND

- Muldoon Town Square Park
- Windsong Park
- Pedestrian Entry
- Vehicle Entry
- Multi-Use Path (Paved)
- Nature Trail (Soft Surface)
- Bridge + Boardwalk
- Chester Creek



LEGEND

- Mudloon Town Square Park
- Windsong Park
- Pedestrian Entry
- Vehicle Entry
- Multi-Use Path (Paved)
- Nature Trail (Soft Surface)
- Bridge + Boardwalk
- Chester Creek

1 THE WEST
A year-round ribbon of activity will inspire passers-by and establish Mudloon Town Square Park as a contemporary new reference point for East Anchorage. The Ribbon will host events, daily play opportunities and winter ice skating.


Debarr Road

2 THE HILL
A series of terraces, terraces, rain, the Hill visible from Mudloon Road, and double as seating for the new community amphitheater. The terraces will anchor the treasured pavilion, a community-use facility with majestic views over the park east to the Chugach Mountains.

3 THE CORE
A community garden, small play area, picnic area, open recreation and seating will open up the core of the park, improving visibility and providing desired open space. A climbing wall perched up on a higher elevation will visually connect to the Treasured Pavilion and areas further east, orienting visitors along the trails and providing a unique recreational opportunity in East Anchorage.

4 THE CONNECTIONS
A series of lighted multi-use path loops will encourage short strolls and link together to form longer exercise loops. Bridges, a Boardwalk and Viewpoints will connect users across Chester Creek and within the park.

5 THE EAST
A small parking area will support a desired off-leash dog park, a small open recreation area, and connect to the multi-use paths encircling year-round use. The destination viewpoint at the far east will be visible across the recreation area and serve as a welcome resting point for users along the trail.



LEGEND

- Mudloon Town Square Park
- Windsong Park
- Pedestrian Entry
- Vehicle Entry
- Multi-Use Path (Paved)
- Nature Trail (Soft Surface)
- Chester Creek
- Bridge + Boardwalk

1 THE WEST
A classic approach into the park along Mudloon Road will be included with a pair of community pavilions and a Dedication Playground. Adjacent picnic areas and plaza will host family picnics as well as larger community events.


Debarr Road

2 THE HILL
The Hill will be a stand-alone destination with a boulder and lawn terrace, amphitheater, climbing to the top, and crash structure. It will include a picnic area, climbing structure, and a dog park. A signed lawn will serve as a sliding hill in winter months on the back side, taking advantage of existing grades and improving visibility.

3 THE CORE
A larger parking area winds its way into the park, supporting activities to the west and providing users with immediate access to the community garden, picnic area, and off-leash dog park. A stroll along the Orchard Loop brings users close to Chester Creek and offers an easily accessible vantage point across Windsong Park.

4 THE CONNECTIONS
A series of lighted multi-use path loops will encourage short strolls and link together to form longer exercise loops. Bridges, a Boardwalk and Viewpoints will connect users across Chester Creek and within the park.

5 THE EAST
A small parking area that takes advantage of existing R.O.W. will support the network of trails and small open recreation area. The East end will largely remain untouched for continued reactivation, with viewpoints and connectors to adjacent neighborhoods provided to increase use and activity.



LEGEND



1 THE WEST
An arid and accessible community center will celebrate the diversity of Muldoon with public art opportunities and connect visitors to Chester Creek while providing enough parking to support desired event and market programming within the park.


Debarr Road

2 THE HILL
A midsize stage and community pavilion anchors the Chester Creek cobble with a destination playground and signed lawn seating recessed into the hill for performances. A multi-use path loop encircles the Hill and provides easy access to adjacent neighborhood and nature trails.

3 THE CORE
A linear stretch of activity in the Core is envisioned to visibly and actively link the park from West to East. A parking area supports events on the Hill and activities in the Core, including the community use pavilion, community gardens, open recreation and sledding.

4 THE CONNECTIONS
A series of lighted multi-use path loops link together to form a series of loops. A central "artery" will lobby and physically connect the activities of the park from Muldoon Road to the open areas to the East Bridge and Marysville. It will connect users across Chester Creek and within the park.

5 THE EAST
A system of paths and trails will weave around large open spaces, encouraging visibility and safety within the park. A neighborhood play area will perch atop higher elevation between the open spaces will be a destination for nearby residents.



CONCEPT DESIGN ALTERNATIVES: MULDOON AREA

LEGEND

Muldoon Town Square Park

Windsong Park

Pedestrian Entry


Vehicle Entry

Multi-Use Path (Paved)


Nature Trail (Soft Surface)

Chester Creek


Bridge + Boardwalk




MULDOON 1.0



MULDOON 2.0



MULDOON 3.0



MULDOON 4.0


Muldoon Region
Muldoon Town Square
Park Master Plan




CONCEPT DESIGN ALTERNATIVES: MULDOON AREA PERSPECTIVES




MULDOON 1.0



MULDOON 2.0



MULDOON 3.0



MULDOON 4.0


CONCEPT DESIGN ALTERNATIVE ELEVATIONS: MULDOON AREA




MULDOON 1.0



MULDOON 3.0



MULDOON 2.0



MULDOON 4.0

CONCEPT DESIGN ALTERNATIVES: CORE AREA

LEGEND

Muldoon Town Square Park



Windsong Park



Pedestrian Entry



Vehicle Entry



Multi-Use Path (Paved)



Nature Trail (Soft Surface)



Chester Creek




Bridge + Boardwalk

Core Region


Muldoon Town Square
Park Master Plan




BETTISWORTH-NORTH




CORE 1.0



CORE 2.0



CORE 3.0





CORE 4.0


CONCEPT DESIGN ALTERNATIVES: CHUGACH AREA

LEGEND

Muldoon Town Square Park




CHUGACH 1.0



CHUGACH 2.0



CHUGACH 3.0






CHUGACH 4.0


Chugach Region
Muldoon Town Square
Park Master Plan




GROUP GENERATED PREFERRED ALTERNATIVES









PARK COMMITTEE MEETING



R&M CONSULTANTS, INC.

9101 Vanguard Drive • Anchorage, AK 99507 • 907.532.1307
3204 Industrial Avenue #102 • Fairbanks, AK 99701 • 907.452.5270
9737 Mud Bay Road #301 • Ketchikan, AK 99901 • 907.220.9424

Park Committee Meeting #3 Summary

Project Number:	2320.01 (R&M)												
Project Title:	MOA Parks and Recreation Muldoon Town Square Park Master Plan												
Subject:	Park Committee Meeting #3												
Author:	Van Le, AICP, R&M Consultants, Inc.												
Meeting Location:	Boys and Girls Club, Muldoon Branch												
Meeting Date:	Thursday, November 19, 2015, 5:30 PM to 7 PM												
Meeting Outreach:	Parks And Recreation Department Outreach												
Meeting Materials:	Meeting Agenda, Preferred Alternative, Updated Draft Vision Statement												
Distribution Date:	Internal Review Version – Public Distribution TBD												
Meeting Attendance:	9 Attendees (See Sign in)												
Attendees:	<table><tr><td>Steve Rafuse</td><td>Project Manager</td><td>MOA Parks & Rec</td></tr><tr><td>Taylor Keegan</td><td>Park Planner</td><td>MOA Parks & Rec</td></tr><tr><td>Jonny Hayes, ASLA</td><td>Landscape Architect</td><td>Bettisworth North</td></tr><tr><td>Van Le, AICP</td><td>Senior Planner</td><td>R&M Consultants, Inc.</td></tr></table>	Steve Rafuse	Project Manager	MOA Parks & Rec	Taylor Keegan	Park Planner	MOA Parks & Rec	Jonny Hayes, ASLA	Landscape Architect	Bettisworth North	Van Le, AICP	Senior Planner	R&M Consultants, Inc.
Steve Rafuse	Project Manager	MOA Parks & Rec											
Taylor Keegan	Park Planner	MOA Parks & Rec											
Jonny Hayes, ASLA	Landscape Architect	Bettisworth North											
Van Le, AICP	Senior Planner	R&M Consultants, Inc.											

Meeting Goal: To achieve consensus on a Preferred Alternative in preparation for the NECC meeting in December.

Meeting Summary

Jonny began Park Committee Meeting 3 by providing a project recap including the Open House on November 4. Jonny noted that based on comments at the Open House, the Draft Vision has been updated. Steve provided an overview of the Master Plan schedule including attending the special NE Community Council meeting on December 17 to receive a Resolution of Support to move forward to the Parks and Recreation Commission in January. Jonny summarized the Preferred Alternatives process from the planning that took place with Open House #1, Park Committee Meetings and Design Charrette and Open House #2 exercise.

Preferred Alternative Overview and Discussion

Areas of general consensus:

- Muldoon
- Core
- Chugach

Questions to Resolve:

1. Ice Ribbon Configuration

- Overall, the group feels that the updated design looks good
- Ribbon configuration has been modified to allow year-round access to the play area
 - The previous ribbon configuration enclosed the playground creating access challenges and hazards in winter
- Updated ice ribbon has a "roundabout" that will allow skaters to still skate in a loop and allow for a farmers market/vendor booths in the summer months

2. Off-Leash Dog Park

- There are over 50,000 registered dogs in Anchorage and there is a demand for off-leash areas.
- A fenced dog area where people can run their dogs off-leash will bring in more year-round park users and will improve park safety.
- Residents in the neighborhood are concerned about the additional traffic that park use might generate. Developing a dog park with access off of Boston/Debar Streets will minimize the impacts of traffic to the neighborhood.
- A dog park will provide a needed service for residents in multi-family housing developments (i.e. Grass Creek across Muldoon is multi-family with little private yards for people with dogs.).
- **Option 2 Dog Park**, located south of the bouldering play area in the Core area parcel is favored over **Option 3**.

3. Off-Site Parking

- East 14th Avenue on-street parking is not possible until the two vacant parcels south of the right-of-way are developed.
 - Currently only 30 feet of ROW is available for access and parking and is not enough to provide on-street parallel or perpendicular parking.
 - Dedication of the additional ROW can only happen when the two parcels are developed, at which time the MOA will require the additional 25 ft. be dedicated as public ROW.
- Shared parking agreement with owner of the Muldoon Mall north of the Park is currently in discussions between the MOA's Parks and Recreation Department Director and the owners.
 - There is a possibility that an agreement can be worked out.
 - Debar Road ROW vacation may be part of the discussions to enable the agreement.
 - Discussions are preliminary and no decisions have been made.

- Objections to the on-site parking shown on the Preferred Alternative from one Park Committee Member.
 - One solution is to provide only the minimum required.
 - Agency meeting in October required that on-site parking be provided otherwise Master Plan will not be approved.
 - Site has to absorb some of the impacts otherwise the neighborhood will bear the brunt of park use impacts.

4. Other Uses and Activities

- A caretaker or park host position should be considered for the core area to help with maintenance and safety.
 - The utilities desired for the Community Garden (water, power) could help support a Park Host at the east end of the Core parking area.
- Possible iconic structure or public art, sloped lawn, low stage and available power to serve as a support space for community events.
- Heart of park and design needs to be mindful of safety and security, including sight-lines, meet universal access requirements and be easy to maintain.
- Materials should be fireproof
- Design and planning should deter non-park uses and undesirable activities

Discussion and Questions

Q. If an area in the park does not have consensus on what the use will be, can we say it will be a flexible space?

- Yes, user preferences and priorities will change over time and flex spaces will allow for these changes in public wants and needs. However, it is important that the Preferred Alternative does not leave too much ambiguity to ensure that the park serves its intended purpose and functions as a unified whole and not pieced together.

Q. Can we cushion a use with flexible space so we are not locked in if we are unsure?

- For Park Plan approval, we need to have decisions made about where park elements will go and what general park uses will be in the park, along with parking, access etc. For programmatic elements, those do not need to be definitive at this point. Keep in mind that if spaces are not defined, it will be more difficult to implement based on the short schedule to use the state funding. Also, another use that will be less desirable could potentially attach itself to the park that will have bigger impacts than planned.

Q. Is it an "if/then" situation with certain uses (does one preclude the other)?

- We worked to make the preferred uses compatible in the space; for example we found a way to include both a dog park for those users and a bike park/pump track.

Q. Do we need a permanent structure for farmer's market?

- Not necessarily. A more flexible festival feel with temporary tents can be taken down. A permanent pavilion or structure will require more significant funds and occupy space that might otherwise support recreation. There are also concerns with a permanent structure attracting illicit activities. The draft master plan shows (1) pavilion structure that would support the play area, ice ribbon and community events.

Page 3

Q. How much do the bridges cost?

- Approximately \$250K for vehicle supported bridges such as the ones at Westchester Lagoon.

Q. Is the Spine shown on the Preferred Alternative graphic open to automobiles?

- The Spine will provide pedestrian only access but will be designed to accommodate emergency and maintenance vehicles.

Q. Are there restrooms at the pavilions?

- Yes, the current policy for public parks is to include screened porta-potties at the on-site parking lots or at the pavilion near the destination play and ice ribbon.

Q. How will the snow removal from the Mall's parking lot be addressed?

- Snow removal will be addressed as part of the shared parking agreement discussion.

Attachments

- Sign in sheet
- Meeting Agenda
- Updated Draft Vision Statement
- Preferred Alternative


Images from Parks Committee Meeting #3

Page 4

DRAFT PREFERRED ALTERNATIVES







REVISED PREFERRED ALTERNATIVES




PARK VISION

The question:

20 years from now.... what will
Muldoon Town Square Park look like?

Public Planning Workshops 1 & 2 Draft Vision Statement:

*"Muldoon Town Square Park is a gathering place and destination for East Anchorage and the greater community where families and people of all ages and abilities can access and participate in healthy park activities in a safe, clean, comfortable environment in a unique, and beautiful **natural** setting."*



APPENDIX B

RESOLUTIONS

SIGNED RESOLUTIONS OF SUPPORT

NECC

Northeast Community Council

A RESOLUTION OF THE NORTHEAST COMMUNITY COUNCIL IN SUPPORT OF THE MULDOON TOWN SQUARE PARK MASTER PLAN

WHEREAS, the Northeast Community Council provides a direct and continuing means of citizen participation in government and local affairs as designated by the Anchorage Assembly;

WHEREAS, Muldoon Town Square Park master plan fulfills the requirements for a small area plan as identified in the East Anchorage District Plan; and

WHEREAS, Muldoon Town Square Park master plan provides a 20-year vision that will guide future development of the park; and

WHEREAS, the Muldoon Town Square Park master plan is the product of extensive public engagement and community participation including an online survey, input from students at Begich M.S. and Bartlett H.S., monthly meetings with the Parks Committee, and regular updates to the NECC; and

WHEREAS, the Parks Committee consists of members of the Northeast Community Council, and Scenic Foothills Community Council; and

WHEREAS, the Parks Committee served in an advisory role to the planning team and was responsible for ensuring that the master plan is consistent with the vision and desires of the community; and

WHEREAS, the master plan identifies the following improvements: community event space and pavilion, winter ice skating ribbon, destination playground, creek access, fenced off-leash dog park, a community garden, a boulder climbing area, a bicycle pump park, open fields for recreation, a mix of paved and soft-surface trails, improved neighborhood access, space for public art, and parking.

NOW, THEREFORE, BE IT RESOLVED that the Northeast Community Council supports approval of the Muldoon Town Square Park master plan by the Parks and Recreation Commission

PASSED AND APPROVED by the Northeast Community Council this 17th day of December, 2015, by a vote of 7 in favor, 0 opposed, and 1 abstained.

NECC President

1

SCENIC FOOTHILLS COMMUNITY COUNCIL

RESOLUTION 02 - 2016

A resolution of the scenic foothills community council in support of the muldoon town square park master plan

WHEREAS, the Scenic Foothills Community Council provides a direct and continuing means of citizen participation in government and local affairs as designated by the Anchorage Assembly;

WHEREAS, Muldoon Town Square Park master plan fulfills the requirements for a small area plan as identified in the East Anchorage District Plan; and

WHEREAS, Muldoon Town Square Park master plan provides a 20-year vision that will guide future development of the park; and

WHEREAS, the Muldoon Town Square Park master plan is the product of extensive public engagement and community participation including an online survey, input from students at Begich M.S. and Bartlett H.S., monthly meetings with the Parks Committee, and two public workshops; and

WHEREAS, the Parks Committee consists of members of the Northeast Community Council, and Scenic Foothills Community Council; and

WHEREAS, the Parks Committee served in an advisory role to the planning team and was responsible for ensuring that the master plan is consistent with the vision and desires of the community; and

WHEREAS, the master plan identifies the following improvements: community event space and pavilion, winter ice skating ribbon, destination playground, creek access, fenced off-leash dog park, a community garden, a boulder climbing area, a bicycle pump park, open fields for recreation, a mix of paved and soft-surface trails, improved neighborhood access, space for public art, and parking.

NOW, THEREFORE, BE IT RESOLVED that the Scenic Foothills Community Council supports approval of the Muldoon Town Square Park master plan by the Parks and Recreation Commission.

PASSED AND APPROVED by the Scenic Foothills Community Council this 7th day of January, 2016, by a unanimous vote.

SFCC President

ATTEST: Council Member



**Municipality of Anchorage, Alaska
Parks & Recreation Department**

632 W. 6th Avenue, Suite 630
P.O. Box 196650
Anchorage, AK 99519
Tel 907-543-4355
URL www.municipalityofanchorage.org/parks



**PRC RES NO. 2016-01
Muldoon Town Square Park Master Plan**

WHEREAS, the Anchorage Parks and Recreation Commission serves in an advisory capacity to both the Mayor and the Assembly, and

WHEREAS, the Anchorage Parks and Recreation Commission has the responsibility and duty to provide for the long term vision of our park system by ensuring that a balance of parks, natural resources, and recreation facilities provides for the health, welfare, and safety of all residents of the Anchorage Bowl; and

WHEREAS, the Muldoon Town Square Park master plan provides a 20 year vision that will address issues and guide future development at the park, and

WHEREAS, the Anchorage Parks and Recreation Department hosted two public workshops and worked with an advisory group to assist the Department in identifying and prioritizing desired improvements for Muldoon Town Square Park; and

WHEREAS, the improvements proposed in the master plan are based on community and stakeholder input and have been vetted by the advisory group through deliberation and consensus; and

WHEREAS, the improvements proposed in the master plan have received support and approval from both the Northeast and Scenic Foothills Community Councils;

WHEREAS, the improvements identified in the master plan include developed access to Chester Creek, a destination inclusive playground, parking lots, community event space that can support the Muldoon Farmers Market and Spirit of Muldoon Picnic, a pavilion, restrooms, a multi-purpose year-round ribbon, bicycle pump park, boulder play area, community garden, community orchard, tennis dog park, open recreation space, space for a park float, view points of the Chugach Mountains, a mix of hard and soft surface trails, and improved neighborhood access

NOW, THEREFORE, BE IT RESOLVED that the Anchorage Parks and Recreation Commission approves the master plan submitted by the Department and the advisory group for Muldoon Town Square Park.

PASSED AND APPROVED by the Anchorage Parks and Recreation Commission this 14th day of January, 2016.

ATTEST: 
Chair, Parks and Recreation Commission

John Rodda, Director
Parks & Recreation Department
PARKS & RECREATION DEPARTMENT
Municipality of Anchorage, Alaska