2024 MASS Division 30 Summary of Changes

Section/	Article	Change
Detail	Article	Change
30.01	1.2	ASTM / AASHTO standards removed: • ASTM A185 / AAASHTO M 55 ASTM / AASHTO standards added: • ASTM A184 • ASTM C143 / AASHTO T 119
		 ASTM C150 / AASHTO M 85 (Originally AASHTO T119) ASTM C330 / AASHTO M 195 ASTM C1240 / AASHTO M 307 ASTM D1557 / AASHTO T 180 ASTM A1064 / AAHSTO M 336
30.01	1.6	Concrete mix requirements for Class AA-3 updated.
30.01	1.9	Weather Limitations updated.
30.01	1.10	Protection of Work updated.
30.02	-	Pay item for High-Performance P.C.C. Curb and Gutter at narrowing tapers added.
30.02 / 30-1	ı	Curb and Gutter Type 2 and Type 3 updated.
30.03	3.3	Requirements for welded steel wire fabric at concrete sidewalks adjoining driveways added.
30.04	4.2	Plastic detectable warning panels removed. The following cast iron detectable warning panel manufactures added: • Advantage Tactile Systems • EJ Group, Inc. • Tuf Tile
30.04	4.3	Requirements for welded steel wire fabric at ramp runs longer than ten feet (10') in legnth added.
30.04 / 30-8 to 30- 13	-	 Detail 30-8 - Curb Ramp Notes (Updated) Detail 30-9 - Perpendicular Curb Ramp (Updated) Detail 30-10 - Parallel Curb Ramp (Updated) Detail 30-11 - Blended Transition Curb Ramp (New Detail) Detail 30-12 - Unidirectional Curb Ramp (Updated) Detail 30-13 - Accessible Curb and Gutter Cross Sections (Updated)
-	1	Original Section 30.07 Concrete - Building Structures removed.
30.07	-	New Section added - Portland Cement Concrete Driveway
30.08 / 30-19	-	New Detail added - P.C.C. Cluster Mailbox Base.
30.12	-	New Section added - High-Performance Concrete.